

# PIC18FXX8 Data Sheet

28/40-Pin High-Performance, Enhanced Flash Microcontrollers with CAN Module

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not
  mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, microID, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart, rfPIC and SmartShunt are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AmpLab, FilterLab, Migratable Memory, MXDEV, MXLAB, SEEVAL, SmartSensor and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, Linear Active Thermistor, Mindi, MiWi, MPASM, MPLIB, MPLINK, PICkit, PICDEM, PICDEM.net, PICLAB, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, REAL ICE, rfLAB, rfPICDEM, Select Mode, Smart Serial, SmartTel, Total Endurance, UNI/O, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2006, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2002

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and water fabrication facilities in Chandler and Tempe, Arizona, Gresham, Oregon and Mountain View, California. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



## PIC18FXX8

### 28/40-Pin High-Performance, Enhanced Flash Microcontrollers with CAN

#### **High-Performance RISC CPU:**

- Linear program memory addressing up to 2 Mbytes
- · Linear data memory addressing to 4 Kbytes
- Up to 10 MIPS operation
- DC 40 MHz clock input
- 4 MHz-10 MHz oscillator/clock input with PLL active
- 16-bit wide instructions, 8-bit wide data path
- · Priority levels for interrupts
- 8 x 8 Single-Cycle Hardware Multiplier

#### **Peripheral Features:**

- · High current sink/source 25 mA/25 mA
- · Three external interrupt pins
- Timer0 module: 8-bit/16-bit timer/counter with 8-bit programmable prescaler
- Timer1 module: 16-bit timer/counter
- Timer2 module: 8-bit timer/counter with 8-bit period register (time base for PWM)
- Timer3 module: 16-bit timer/counter
- Secondary oscillator clock option Timer1/Timer3
- Capture/Compare/PWM (CCP) modules;
   CCP pins can be configured as:
  - Capture input: 16-bit, max resolution 6.25 ns
  - Compare: 16-bit, max resolution 100 ns (Tcy)
  - PWM output: PWM resolution is 1 to 10-bit Max. PWM freq. @:8-bit resolution = 156 kHz 10-bit resolution = 39 kHz
- Enhanced CCP module which has all the features of the standard CCP module, but also has the following features for advanced motor control:
  - 1, 2 or 4 PWM outputs
  - Selectable PWM polarity
  - Programmable PWM dead time
- Master Synchronous Serial Port (MSSP) with two modes of operation:
  - 3-wire SPI™ (Supports all 4 SPI modes)
  - I<sup>2</sup>C™ Master and Slave mode
- · Addressable USART module:
  - Supports interrupt-on-address bit

#### **Advanced Analog Features:**

- 10-bit, up to 8-channel Analog-to-Digital Converter module (A/D) with:
  - Conversion available during Sleep
  - Up to 8 channels available
- · Analog Comparator module:
  - Programmable input and output multiplexing
- · Comparator Voltage Reference module
- Programmable Low-Voltage Detection (LVD) module:
  - Supports interrupt-on-Low-Voltage Detection
- Programmable Brown-out Reset (BOR)

#### **CAN bus Module Features:**

- · Complies with ISO CAN Conformance Test
- · Message bit rates up to 1 Mbps
- · Conforms to CAN 2.0B Active Spec with:
  - 29-bit Identifier Fields
  - 8-byte message length
  - 3 Transmit Message Buffers with prioritization
  - 2 Receive Message Buffers
  - 6 full, 29-bit Acceptance Filters
  - Prioritization of Acceptance Filters
  - Multiple Receive Buffers for High Priority Messages to prevent loss due to overflow
  - Advanced Error Management Features

#### **Special Microcontroller Features:**


- Power-on Reset (POR), Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Watchdog Timer (WDT) with its own on-chip RC oscillator
- · Programmable code protection
- Power-saving Sleep mode
- Selectable oscillator options, including:
  - 4x Phase Lock Loop (PLL) of primary oscillator
- Secondary Oscillator (32 kHz) clock input
- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via two pins

#### Flash Technology:

- · Low-power, high-speed Enhanced Flash technology
- · Fully static design
- Wide operating voltage range (2.0V to 5.5V)
- · Industrial and Extended temperature ranges

	Program Memory		Data Memory				ors	, ,	MSSP			
Device	Flash (bytes)	# Single-Word Instructions	SRAM (bytes)	EEPROM (bytes)	I/O	10-bit A/D (ch)		CCP/ ECCP (PWM)	SPI™	Master I <sup>2</sup> C™	USART	Timers 8/16-bit
PIC18F248	16K	8192	768	256	22	5		1/0	Υ	Υ	Υ	1/3
PIC18F258	32K	16384	1536	256	22	5	_	1/0	Υ	Υ	Υ	1/3
PIC18F448	16K	8192	768	256	33	8	2	1/1	Υ	Υ	Υ	1/3
PIC18F458	32K	16384	1536	256	33	8	2	1/1	Υ	Υ	Υ	1/3

#### Pin Diagrams



#### Pin Diagrams (Continued) **TQFP** → ₩D1/PSP1/C1IN-→ ₩D0/PSP0/C1IN+ → ₩C2/CCP1 → ₩C2/CCP1 NC -RD3/PSP3/C2IN RC7/RX/DT -NC RD4/PSP4/ECCP1/P1A □ 2 32 RC0/T1OSO/T1CKI RD5/PSP5/P1B 3 31 OSC2/CLKO/RA6 RD6/PSP6/P1C 4 30 OSC1/CLKI 5 6 RD7/PSP7/P1D 29 Vss PIC18F448 28 - VDD PIC18F458 $V_{DD}$ 27 RE2/AN7/CS/C2OUT RB0/INT0 8 RE1/AN6/WR/C1OUT 26 9 RB1/INT1 ◄ 25 🗀 RE0//AN5/RD RB2/CANTX/INT2 10 24 RA5/AN4/SS/LVDIN 23 🗖 □ 11 RB3/CANRX RA4/T0CKI NC RB4← RB5/PGM ← RB6/PGC ← RB7/PGD ← RA0/ANO/CVREF ← RA2/AN2/VREF ← RA3/AN3/NEF+ ← SPDIP, SOIC MCLR/VPP ►RB7/PGD RA0/AN0/CVREF 27 ►RB6/PGC 2 RA1/AN1 26 RB5/PGM RA2/AN2/VREF-25 -RB4 RA3/AN3/VREF+ ► RB3/CANRX PIC18F248 PIC18F258 24 RA4/T0CKI 23 RB2/CANTX/INT2 RA5/AN4/SS/LVDIN -22 RB1/INT1 -RB0/INT0 Vss 21 OSC1/CLKI 20 -VDD 9 OSC2/CLKO/RA6 10 19 -Vss RC0/T1OSO/T1CKI · 11 18 RC7/RX/DT RC1/T1OSI 12 17 ► RC6/TX/CK RC2/CCP1 13 → RC5/SDO 16 RC3/SCK/SCL RC4/SDI/SDA 15

## www.DataPIC18FXX8

#### **Table of Contents**

1.0	Device Overview	7
2.0	Oscillator Configurations	17
3.0	Reset	25
4.0	Memory Organization	37
5.0	Data EEPROM Memory	59
6.0	Flash Program Memory	65
7.0	8 x 8 Hardware Multiplier	75
8.0	Interrupts	77
9.0	I/O Ports	93
10.0	Parallel Slave Port	. 107
11.0	Timer0 Module	. 109
12.0	Timer1 Module	. 113
13.0	Timer2 Module	. 117
14.0	Timer3 Module	. 119
15.0	Capture/Compare/PWM (CCP) Modules	. 123
16.0	Enhanced Capture/Compare/PWM (ECCP) Module	. 131
17.0	Master Synchronous Serial Port (MSSP) Module	. 143
18.0	Addressable Universal Synchronous Asynchronous Receiver Transmitter (USART)	. 183
19.0	CAN Module	
20.0	Compatible 10-Bit Analog-to-Digital Converter (A/D) Module	. 241
21.0	Comparator Module	. 249
22.0	Comparator Voltage Reference Module	. 255
23.0	Low-Voltage Detect	. 259
24.0	Special Features of the CPU	. 265
25.0	Instruction Set Summary	. 281
26.0	Development Support	. 323
27.0	Electrical Characteristics	. 329
28.0	DC and AC Characteristics Graphs and Tables	. 361
29.0	Packaging Information	. 377
Appe	endix A: Data Sheet Revision History	. 385
Appe	endix B: Device Differences	. 385
	endix C: Device Migrations	
	endix D: Migrating From Other PICmicro® Devices	
	· · · · · · · · · · · · · · · · · · ·	
On-L	ine Support	. 397
Syste	ems Information and Upgrade Hot Line	. 397
Read	ler Response	. 398
PIC1	8EXX8 Product Identification System	399

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

## www.DataPIC18FXX8

NOTES:

#### 1.0 DEVICE OVERVIEW

This document contains device specific information for the following devices:

- PIC18F248
- PIC18F258
- PIC18F448
- PIC18F458

These devices are available in 28-pin, 40-pin and 44-pin packages. They are differentiated from each other in four ways:

 PIC18FX58 devices have twice the Flash program memory and data RAM of PIC18FX48 devices (32 Kbytes and 1536 bytes vs. 16 Kbytes and 768 bytes, respectively).

- PIC18F2X8 devices implement 5 A/D channels, as opposed to 8 for PIC18F4X8 devices.
- 3. PIC18F2X8 devices implement 3 I/O ports, while PIC18F4X8 devices implement 5.
- Only PIC18F4X8 devices implement the Enhanced CCP module, analog comparators and the Parallel Slave Port.

All other features for devices in the PIC18FXX8 family, including the serial communications modules, are identical. These are summarized in Table 1-1.

Block diagrams of the PIC18F2X8 and PIC18F4X8 devices are provided in Figure 1-1 and Figure 1-2, respectively. The pinouts for these device families are listed in Table 1-2.

TABLE 1-1: PIC18FXX8 DEVICE FEATURES

Features		PIC18F248	PIC18F258	PIC18F448	PIC18F458	
Operating Freque	ency	DC – 40 MHz	DC – 40 MHz	DC – 40 MHz	DC – 40 MHz	
Internal	Bytes	16K	32K	16K	32K	
Program Memory	# of Single-Word Instructions	8192	16384	8192	16384	
Data Memory (B	ytes)	768	1536	768	1536	
Data EEPROM N	Memory (Bytes)	256	256	256	256	
Interrupt Sources	3	17	17	21	21	
I/O Ports		Ports A, B, C	Ports A, B, C	Ports A, B, C, D, E	Ports A, B, C, D, E	
Timers		4	4	4	4	
Capture/Compare	e/PWM Modules	1	1	1	1	
Enhanced Captu PWM Modules	re/Compare/		_	1	1	
Serial Communications		MSSP, CAN, Addressable USART	MSSP, CAN, Addressable USART	MSSP, CAN, Addressable USART	MSSP, CAN, Addressable USART	
Parallel Communications (PSP)		No	No	Yes	Yes	
10-bit Analog-to-D	Digital Converter	5 input channels	5 input channels	8 input channels	8 input channels	
Analog Comparat	ors	No	No	2	2	
Analog Comparat	ors VREF Output	N/A	N/A	Yes	Yes	
Resets (and Dela	ays)	POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)  POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)		POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)	POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)	
Programmable Lo	ow-Voltage Detect	Yes	Yes	Yes	Yes	
Programmable B	rown-out Reset	Yes	Yes	Yes	Yes	
CAN Module		Yes	Yes	Yes	Yes	
In-Circuit Serial F (ICSP™)	Programming™	Yes	Yes	Yes	Yes	
Instruction Set		75 Instructions	75 Instructions	75 Instructions	75 Instructions	
Packages		28-pin SPDIP 28-pin SOIC	28-pin SPDIP 28-pin SOIC	40-pin PDIP 44-pin PLCC 44-pin TQFP	40-pin PDIP 44-pin PLCC 44-pin TQFP	

FIGURE 1-1: PIC18F248/258 BLOCK DIAGRAM Data Bus<8> **PORTA** RA0/AN0/CVREF RA1/AN1 Table Pointer<21> 21 Data Latch RA2/AN2/VREF-8 Data RAM RA3/AN3/VREF+ 21 inc/dec logic up to 1536 bytes RA4/T0CKI RA5/AN4/SS/LVDIN Address Latch OSC2/CLKO/RA6 PCLATU PCLATH **PORTB** 12 RB0/INT0 Address<12> PCU PCH PCL RB1/INT1 Program Counter 4N BSR 4 12 RB2/CANTX/INT2 RB3/CANRX Bank0, F Address Latch FSR0 RB4 Program Memory up to 32 Kbytes FSR1 31 Level Stack RB5/PGM FSR2 12 RB6/PGC RB7/PGD Data Latch nc/ded Decode **PORTC** Table Latch RC0/T1OSO/T1CKI RC1/T1OSI **T/8** 16 RC2/CCP1 ROM Latch RC3/SCK/SCL RC4/SDI/SDA RC5/SDO ΙR RC6/TX/CK RC7/RX/DT PRODH PRODL Instruction 8 x 8 Multiply Decode & Control OSC2/CLKO/RA6 OSC1/CLKI BITOP W Power-up **∤**8 Timer Timing Generation Oscillator T10SI T10SO Start-up Timer ALŮ<8> Power-on Reset 8 Watchdog 4X PLL Timer Brown-out Precision Reset Band Gap Test Mode Reference Select Band Gap MCLR VDD. VSS **PBOR** Timer0 Timer2 Timer3 Timer1 PLVD ADC Synchronous Data EEPROM CCP1 **USART CAN Module** Serial Port

Data Bus<8> **PORTA** RA0/AN0/CVREF RA1/AN1 21 Table Pointer<21> Data Latch RA2/AN2/VREF--8 Data RAM RA3/AN3/VREF+ 21 inc/dec logic up to 1536 Kbytes RA4/T0CKI RA5/AN4/SS/LVDIN Address Latch OSC2/CLKO/RA6 PCLATU PCLATH **PORTB** 12 RB0/INT0 Address<12> PCU PCH PCL RB1/INT1 Program Counter 12 4 RB2/CANTX/INT2 Bank0, F RB3/CANRX BSR Address Latch FSR0 RB4 FSR1 Program Memory up to 32 Kbytes 31 Level Stack RB5/PGM FSR2 12 RB6/PGC RB7/PGD Data Latch Decode logic **PORTC** Table Latch RC0/T1OSO/T1CKI RC1/T1OSI 8 RC2/CCP1 ROM Latch RC3/SCK/SCL RC4/SDI/SDA RC5/SDO IR RC6/TX/CK RC7/RX/DT 8 PORTD RD0/PSP0/C1IN+ PRODH PRODL RD1/PSP1/C1IN-Instruction RD2/PSP2/C2IN+ 8 x 8 Multiply Decode & RD3/PSP3/C2IN-Control RD4/PSP4/ECCP1/P1A OSC2/CLKO/RA6 RD5/PSP5/P1B BITOP W OSC1/CLKI RD6/PSP6/P1C Power-up **∤**8 RD7/PSP7/P1D Timer Timing Oscillator **PORTE** Generation Start-up Timer RE0/AN5/RD T10SI ALÚ<8> Power-on RE1/AN6/WR//C1OUT T10S0 4X PLL Reset RE2/AN7/CS/C2OUT 8 Watchdog Timer Precision Brown-out Band Gap Reset Reference Test Mode Select Band Gap MCLR VDD, VSS **PBOR** 10-bit Parallel Timer0 Timer1 Timer2 Timer3 PI VD ADC Slave Port Synchronous Enhanced Data EEPROM Comparators CCP1 USART **CAN Module** CCP Serial Port

FIGURE 1-2: PIC18F448/458 BLOCK DIAGRAM

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS

	Pi	in Numb	er					
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC	.,,,,	.,,,,		
MCLR/VPP MCLR	1	1	18	2	I	ST	Master Clear (input) or programming voltage (output).  Master Clear (Reset) input. This pin is an active low Reset	
VPP					Р	_	to the device. Programming voltage input.	
NC	_	_	12, 13, 33, 34	1, 17, 28, 40	_	_	These pins should be left unconnected.	
OSC1/CLKI OSC1 CLKI	9	13	30	14	I	CMOS/ST	Oscillator crystal or external clock input.  Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; otherwise, CMOS.  External clock source input.  Always associated with pin function OSC1 (see OSC1/CLKI, OSC2/CLKO pins).	
OSC2/CLKO/RA6 OSC2	10	14	31	15	0	_	Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.	
CLKO					0	_	In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.	
RA6					I/O	TTL	General purpose I/O pin.	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pin Number							
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC	.,,,,	.,,,,		
							PORTA is a bidirectional I/O port.	
RA0/AN0/CVREF	2	2	19	3	I/O	TTL	Digital I/O	
RA0 AN0					1/0	Analog	Digital I/O. Analog input 0.	
CVREF					Ó	Analog	Comparator voltage reference output.	
RA1/AN1	3	3	20	4				
RA1 AN1					I/O I	TTL	Digital I/O.	
ANT					ı	Analog	Analog input 1.	
RA2/AN2/VREF-	4	4	21	5				
RA2					I/O	TTL	Digital I/O.	
AN2 Vref-						Analog Analog	Analog input 2. A/D reference voltage	
VIII.						7 ti lalog	(Low) input.	
RA3/AN3/VREF+	5	5	22	6				
RA3 AN3					I/O I	TTL Analog	Digital I/O. Analog input 3.	
VREF+					i	Analog	A/D reference voltage	
						_	(High) input.	
RA4/T0CKI	6	6	23	7	I/O	TTI /OD	Digital I/O	
RA4					1/0	TTL/OD	Digital I/O – open-drain when configured as output.	
TOCKI					I	ST	Timer0 external clock input.	
RA5/AN4/SS/LVDIN	7	7	24	8				
RA5					I/O	TTL	Digital I/O.	
AN4 SS						Analog ST	Analog input 4. SPI™ slave select input.	
LVDIN					i	Analog	Low-Voltage Detect input.	
RA6							See the OSC2/CLKO/RA6 pin.	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	n Numb						
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC	,,,,,	-,,,,,		
							PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs.	
RB0/INT0 RB0 INT0	21	33	8	36	I/O I	TTL ST	Digital I/O. External interrupt 0.	
RB1/INT1 RB1 INT1	22	34	9	37	I/O I	TTL ST	Digital I/O. External interrupt 1.	
RB2/CANTX/INT2 RB2 CANTX INT2	23	35	10	38	I/O O I	TTL TTL ST	Digital I/O. Transmit signal for CAN bus. External interrupt 2.	
RB3/CANRX RB3 CANRX	24	36	11	39	I/O I	TTL TTL	Digital I/O. Receive signal for CAN bus.	
RB4	25	37	14	41	I/O	TTL	Digital I/O. Interrupt-on-change pin.	
RB5/PGM RB5	26	38	15	42	I/O	TTL	Digital I/O. Interrupt-on-change pin.	
PGM					I	ST	Low-voltage ICSP™ programming enable.	
RB6/PGC RB6	27	39	16	43	I/O	TTL	Digital I/O. In-Circuit Debugger pin.	
PGC					I	ST	Interrupt-on-change pin. ICSP programming clock.	
RB7/PGD RB7	28	40	17	44	I/O	TTL	Digital I/O. In-Circuit Debugger pin.	
PGD					I/O	ST	Interrupt-on-change pin. ICSP programming data.	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	n Numb	er					
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC	,,,,,	.,,,,		
RC0/T1OSO/T1CKI RC0 T1OSO T1CKI	11	15	32	16	I/O O I	ST — ST	PORTC is a bidirectional I/O port.  Digital I/O. Timer1 oscillator output. Timer1/Timer3 external clock input.	
RC1/T1OSI RC1 T1OSI	12	16	35	18	I/O I	ST CMOS	Digital I/O. Timer1 oscillator input.	
RC2/CCP1 RC2 CCP1	13	17	36	19	I/O I/O	ST ST	Digital I/O. Capture 1 input/Compare 1 output/PWM1 output.	
RC3/SCK/SCL RC3 SCK	14	18	37	20	I/O I/O	ST ST	Digital I/O. Synchronous serial clock input/output for SPI™ mode.	
SCL					I/O	ST	Synchronous serial clock input/output for I <sup>2</sup> C™ mode.	
RC4/SDI/SDA RC4 SDI SDA	15	23	42	25	I/O I I/O	ST ST ST	Digital I/O. SPI data in. I <sup>2</sup> C data I/O.	
RC5/SDO RC5 SDO	16	24	43	26	I/O O	ST —	Digital I/O. SPI data out.	
RC6/TX/CK RC6 TX	17	25	44	27	I/O O	ST —	Digital I/O. USART asynchronous transmit.	
СК					I/O	ST	USART synchronous clock (see RX/DT).	
RC7/RX/DT RC7 RX DT	18	26	1	29	I/O I I/O	ST ST ST	Digital I/O. USART asynchronous receive. USART synchronous data (see TX/CK).	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	n Numb			,	- ,		
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC	-,,,,	-71		
DD0/D0D0/O4IN		10	00				PORTD is a bidirectional I/O port. These pins have TTL input buffers when external memory is enabled.	
RD0/PSP0/C1IN+ RD0 PSP0 C1IN+	_	19	38	21	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 1 input.	
RD1/PSP1/C1IN- RD1 PSP1 C1IN-	_	20	39	22	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 1 input.	
RD2/PSP2/C2IN+ RD2 PSP2 C2IN+	_	21	40	23	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 2 input.	
RD3/PSP3/C2IN- RD3 PSP3 C2IN-	_	22	41	24	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 2 input.	
RD4/PSP4/ECCP1/ P1A	_	27	2	30				
RD4 PSP4 ECCP1 P1A					I/O I/O I/O O	ST TTL ST —	Digital I/O. Parallel Slave Port data. ECCP1 capture/compare. ECCP1 PWM output A.	
RD5/PSP5/P1B RD5 PSP5 P1B	_	28	3	31	I/O I/O O	ST TTL —	Digital I/O. Parallel Slave Port data. ECCP1 PWM output B.	
RD6/PSP6/P1C RD6 PSP6 P1C	_	29	4	32	I/O I/O O	ST TTL —	Digital I/O. Parallel Slave Port data. ECCP1 PWM output C.	
RD7/PSP7/P1D RD7 PSP7 P1D	_	30	5	33	I/O I/O O	ST TTL —	Digital I/O. Parallel Slave Port data. ECCP1 PWM output D.	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	in Numb	er					
Pin Name	PIC18F248/258 PIC18F448/458			458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	PDIP TQFP PLCC		-,,,,,	.,,,,		
RE0/AN5/RD RE0 AN5 RD	_	8	25	9	I/O   	ST Analog TTL	PORTE is a bidirectional I/O port.  Digital I/O. Analog input 5. Read control for Parallel Slave	
RE1/AN6/WR/C1OUT RE1 AN6 WR	_	9	26	10	//O  -  -  -  -	ST Analog TTL Analog	Port (see WR and CS pins).  Digital I/O. Analog input 6. Write control for Parallel Slave Port (see CS and RD pins). Comparator 1 output.	
RE2/AN7/CS/C2OUT RE2 AN7 CS  C2OUT	_	10	27	11	//O - - O	ST Analog TTL Analog	Digital I/O. Analog input 7. Chip select control for Parallel Slave Port (see RD and WR pins). Comparator 2 output.	
Vss	19, 8	12, 31	6, 29	13, 34	_	_	Ground reference for logic and I/O pins.	
VDD	20	11, 32	7, 28	12, 35	_	_	Positive supply for logic and I/O pins.	

ST = Schmitt Trigger input with CMOS levels

I = Input

P = Power

CMOS = CMOS compatible input or output

Analog = Analog input

O = Output

## www.DataPIC18FXX8

NOTES:

## 2.0 OSCILLATOR CONFIGURATIONS

#### 2.1 Oscillator Types

The PIC18FXX8 can be operated in one of eight oscillator modes, programmable by three configuration bits (FOSC2, FOSC1 and FOSC0).

•		•
1.	LP	Low-Power Crystal
2.	XT	Crystal/Resonator
3.	HS	High-Speed Crystal/Resonator
4.	HS4	High-Speed Crystal/Resonator with PLL enabled
5.	RC	External Resistor/Capacitor
6.	RCIO	External Resistor/Capacitor with I/O pin enabled
7.	EC	External Clock
8.	ECIO	External Clock with I/O pin enabled


## 2.2 Crystal Oscillator/Ceramic Resonators

In XT, LP, HS or HS4 (PLL) Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-1 shows the pin connections. An external clock source may also be connected to the OSC1 pin, as shown in Figure 2-3 and Figure 2-4.

The PIC18FXX8 oscillator design requires the use of a parallel cut crystal.

**Note:** Use of a series cut crystal may give a frequency out of the crystal manufacturer's specifications.

# FIGURE 2-1: CRYSTAL/CERAMIC RESONATOR OPERATION (HS, XT OR LP OSC CONFIGURATION)



Note 1: See Table 2-1 and Table 2-2 for recommended values of C1 and C2.

- 2: A series resistor (Rs) may be required for AT strip cut crystals.
- 3: RF varies with the crystal chosen.

#### TABLE 2-1: CERAMIC RESONATORS

Ranges Tested:									
Mode Freq OSC1 OSC2									
XT	455 kHz	68-100 pF	68-100 pF						
	2.0 MHz	15-68 pF	15-68 pF						
	4.0 MHz	15-68 pF	15-68 pF						
HS	8.0 MHz	10-68 pF	10-68 pF						
	16.0 MHz	10-22 pF	10-22 pF						

These values are for design guidance only. See notes following Table 2-2.

Resonators Used:							
455 kHz	Panasonic EFO-A455K04B	±0.3%					
2.0 MHz	Murata Erie CSA2.00MG	±0.5%					
4.0 MHz Murata Erie CSA4.00MG ±0.5%							
8.0 MHz	Murata Erie CSA8.00MT	±0.5%					
16.0 MHz	Murata Erie CSA16.00MX	±0.5%					
All resonators used did not have built-in capacitors.							

Osc Type	Crystal Freq	Cap. Range C1	Cap. Range C2
LP	32.0 kHz	33 pF	33 pF
	200 kHz	15 pF	15 pF
XT	200 kHz	47-68 pF	47-68 pF
	1.0 MHz	15 pF	15 pF
	4.0 MHz	15 pF	15 pF
HS	4.0 MHz	15 pF	15 pF
	8.0 MHz	15-33 pF	15-33 pF
	20.0 MHz	15-33 pF	15-33 pF
	25.0 MHz	15-33 pF	15-33 pF

These values are for design guidance only. See notes on this page.

Crystals Used						
32.0 kHz	Epson C-001R32.768K-A	±20 PPM				
200 kHz	STD XTL 200.000KHz	±20 PPM				
1.0 MHz	ECS ECS-10-13-1	±50 PPM				
4.0 MHz	ECS ECS-40-20-1	±50 PPM				
8.0 MHz	EPSON CA-301 8.000M-C	±30 PPM				
20.0 MHz	EPSON CA-301 20.000M-C	±30 PPM				

- **Note 1:** Recommended values of C1 and C2 are identical to the ranges tested (Table 2-1).
  - 2: Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **4:** Rs may be required in HS mode, as well as XT mode, to avoid overdriving crystals with low drive level specification.


#### 2.3 RC Oscillator

For timing insensitive applications, the "RC" and "RCIO" device options offer additional cost savings. The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values and the operating temperature. In addition to this, the oscillator frequency will vary from unit to unit due to normal process parameter variation. Furthermore, the difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to take into account variation due to tolerance of external R and C components used. Figure 2-2 shows how the RC combination is connected.

In the RC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic.

**Note:** If the oscillator frequency divided by 4 signal is not required in the application, it is recommended to use RCIO mode to save current.

FIGURE 2-2: RC OSCILLATOR MODE




The RCIO Oscillator mode functions like the RC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6).

#### 2.4 External Clock Input

The EC and ECIO Oscillator modes require an external clock source to be connected to the OSC1 pin. The feedback device between OSC1 and OSC2 is turned off in these modes to save current. There is no oscillator start-up time required after a Power-on Reset or after a recovery from Sleep mode.


In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-3 shows the pin connections for the EC Oscillator mode.

FIGURE 2-3: EXTERNAL CLOCK INPUT OPERATION (EC OSC CONFIGURATION)



The ECIO Oscillator mode functions like the EC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. Figure 2-4 shows the pin connections for the ECIO Oscillator mode.

FIGURE 2-4: EXTERNAL CLOCK INPUT OPERATION (ECIO CONFIGURATION)



#### 2.5 HS4 (PLL)


A Phase Locked Loop circuit is provided as a programmable option for users that want to multiply the frequency of the incoming crystal oscillator signal by 4. For an input clock frequency of 10 MHz, the internal clock frequency will be multiplied to 40 MHz. This is useful for customers who are concerned with EMI due to high-frequency crystals.

The PLL can only be enabled when the oscillator configuration bits are programmed for HS mode. If they are programmed for any other mode, the PLL is not enabled and the system clock will come directly from OSC1.

The PLL is one of the modes of the FOSC2:FOSC0 configuration bits. The oscillator mode is specified during device programming.

A PLL lock timer is used to ensure that the PLL has locked before device execution starts. The PLL lock timer has a time-out referred to as TPLL.

FIGURE 2-5: PLL BLOCK DIAGRAM



#### 2.6 Oscillator Switching Feature


The PIC18FXX8 devices include a feature that allows the system clock source to be switched from the main oscillator to an alternate low-frequency clock source. For the PIC18FXX8 devices, this alternate clock source is the Timer1 oscillator. If a low-frequency crystal (32 kHz, for example) has been attached to the Timer1 oscillator pins and the Timer1 oscillator has been enabled, the device can switch to a Low-Power Execution mode. Figure 2-6 shows a block diagram of the system clock sources. The clock switching feature is enabled by programming the Oscillator Switching Enable (OSCSEN) bit in Configuration register, CONFIG1H, to a '0'. Clock switching is disabled in an erased device. See Section 12.2 "Timer1 Oscillator" for further details of the Timer1 oscillator and Section 24.1 "Configuration Bits" for Configuration register details.

#### 2.6.1 SYSTEM CLOCK SWITCH BIT

The system clock source switching is performed under software control. The system clock switch bit, SCS (OSCCON register), controls the clock switching. When the SCS bit is '0', the system clock source comes from the main oscillator selected by the FOSC2:FOSC0 configuration bits. When the SCS bit is set, the system clock source comes from the Timer1 oscillator. The SCS bit is cleared on all forms of Reset.

The Timer1 oscillator must be enabled to switch the system clock source. The Timer1 oscillator is enabled by setting the T1OSCEN bit in the Timer1 Control register (T1CON). If the Timer1 oscillator is not enabled, any write to the SCS bit will be ignored (SCS bit forced cleared) and the main oscillator continues to be the system clock source.

FIGURE 2-6: DEVICE CLOCK SOURCES



#### REGISTER 2-1: OSCCON: OSCILLATOR CONTROL REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-1
_	_	_	_	_	_		SCS
bit 7							bit 0

Note:

#### bit 7-1 Unimplemented: Read as '0'

bit 0 SCS: System Clock Switch bit

When  $\overline{OSCSEN}$  configuration bit =  $\underline{0}$  and T1OSCEN bit is set:

1 = Switch to Timer1 oscillator/clock pin

0 = Use primary oscillator/clock input pin

When OSCSEN is clear or T1OSCEN is clear:

Bit is forced clear.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 2.6.2 OSCILLATOR TRANSITIONS


The PIC18FXX8 devices contain circuitry to prevent "glitches" when switching between oscillator sources. Essentially, the circuitry waits for eight rising edges of the clock source that the processor is switching to. This ensures that the new clock source is stable and that its pulse width will not be less than the shortest pulse width of the two clock sources.

Figure 2-7 shows a timing diagram indicating the transition from the main oscillator to the Timer1 oscillator. The Timer1 oscillator is assumed to be running all the time. After the SCS bit is set, the processor is frozen at the next occurring Q1 cycle. After eight synchronization cycles are counted from the Timer1 oscillator, operation resumes. No additional delays are required after the synchronization cycles.


The sequence of events that takes place when switching from the Timer1 oscillator to the main oscillator will depend on the mode of the main oscillator. In addition to eight clock cycles of the main oscillator, additional delays may take place.

If the main oscillator is configured for an external crystal (HS, XT, LP), the transition will take place after an oscillator start-up time (Tost) has occurred. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for HS, XT and LP modes is shown in Figure 2-8.

#### FIGURE 2-7: TIMING DIAGRAM FOR TRANSITION FROM OSC1 TO TIMER1 OSCILLATOR



#### FIGURE 2-8: TIMING DIAGRAM FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS, XT, LP)




### www.DataPIC18FXX8


If the main oscillator is configured for HS4 (PLL) mode, an oscillator start-up time (ToST) plus an additional PLL time-out (TPLL) will occur. The PLL time-out is typically 2 ms and allows the PLL to lock to the main oscillator frequency. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for HS4 mode is shown in Figure 2-9.

If the main oscillator is configured in the RC, RCIO, EC or ECIO modes, there is no oscillator start-up time-out. Operation will resume after eight cycles of the main oscillator have been counted. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for RC, RCIO, EC and ECIO modes is shown in Figure 2-10.

#### FIGURE 2-9: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS WITH PLL)



#### FIGURE 2-10: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (RC, EC)



## 2.7 Effects of Sleep Mode on the On-Chip Oscillator

When the device executes a SLEEP instruction, the on-chip clocks and oscillator are turned off and the device is held at the beginning of an instruction cycle (Q1 state). With the oscillator off, the OSC1 and OSC2 signals will stop oscillating. Since all the transistor switching currents have been removed, Sleep mode achieves the lowest current consumption of the device (only leakage currents). Enabling any on-chip feature that will operate during Sleep will increase the current consumed during Sleep. The user can wake from Sleep through external Reset, Watchdog Timer Reset or through an interrupt.

#### 2.8 Power-up Delays

Power-up delays are controlled by two timers so that no external Reset circuitry is required for most applications. The delays ensure that the device is kept in Reset until the device power supply and clock are stable. For additional information on Reset operation, see **Section 3.0 "Reset"**.

The first timer is the Power-up Timer (PWRT), which optionally provides a fixed delay of TPWRT (parameter #D033) on power-up only (POR and BOR). The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable.

With the PLL enabled (HS4 Oscillator mode), the time-out sequence following a Power-on Reset is different from other oscillator modes. The time-out sequence is as follows: the PWRT time-out is invoked after a POR time delay has expired, then the Oscillator Start-up Timer (OST) is invoked. However, this is still not a sufficient amount of time to allow the PLL to lock at high frequencies. The PWRT timer is used to provide an additional fixed 2 ms (nominal) to allow the PLL ample time to lock to the incoming clock frequency.

TABLE 2-3: OSC1 AND OSC2 PIN STATES IN SLEEP MODE

OSC Mode	OSC1 Pin	OSC2 Pin	
RC	Floating, external resistor should pull high	At logic low	
RCIO	Floating, external resistor should pull high	Configured as PORTA, bit 6	
ECIO	Floating	Configured as PORTA, bit 6	
EC	Floating	At logic low	
LP, XT and HS	Feedback inverter disabled at quiescent voltage level	Feedback inverter disabled at quiescent voltage level	

Note: See Table 3-1 in Section 3.0 "Reset" for time-outs due to Sleep and MCLR Reset.

## www.DataPIC18FXX8

NOTES:

#### 3.0 RESET

The PIC18FXX8 differentiates between various kinds of RESET:

- Power-on Reset (POR) a)
- MCLR Reset during normal operation
- MCLR Reset during Sleep c)
- Watchdog Timer (WDT) Reset during normal operation
- e) Programmable Brown-out Reset (PBOR)
- f) **RESET Instruction**
- Stack Full Reset g)
- Stack Underflow Reset h)

Most registers are unaffected by a Reset. Their status is unknown on POR and unchanged by all other Resets. The other registers are forced to a "Reset"

state on Power-on Reset, MCLR, WDT Reset, Brownout Reset, MCLR Reset during Sleep and by the RESET instruction.


Most registers are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. Status bits from the RCON register, RI, TO, PD, POR and BOR are set or cleared differently in different Reset situations, as indicated in Table 3-2. These bits are used in software to determine the nature of the Reset. See Table 3-3 for a full description of the Reset states of all registers.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 3-1.

The Enhanced MCU devices have a MCLR noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

A WDT Reset does not drive MCLR pin low.

FIGURE 3-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



#### 3.1 Power-on Reset (POR)

A Power-on Reset pulse is generated on-chip when a VDD rise is detected. To take advantage of the POR circuitry, connect the MCLR pin directly (or through a resistor) to VDD. This eliminates external RC components usually needed to create a Power-on Reset delay. A minimum rise rate for VDD is specified (refer to parameter D004). For a slow rise time, see Figure 3-2.

When the device starts normal operation (exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met. Brown-out Reset may be used to meet the voltage start-up condition.


#### 3.2 MCLR

PIC18FXX8 devices have a noise filter in the  $\overline{\text{MCLR}}$  Reset path. The filter will detect and ignore small pulses.

It should be noted that a WDT Reset does not drive  $\overline{\text{MCLR}}$  pin low.

The behavior of the ESD protection on the MCLR pin differs from previous devices of this family. Voltages applied to the pin that exceed its specification can result in both Resets and current draws outside of device specification during the Reset event. For this reason, Microchip recommends that the MCLR pin no longer be tied directly to VDD. The use of an RC network, as shown in Figure 3-2, is suggested.

## FIGURE 3-2: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



Note 1: External Power-on Reset circuit is required only if the VDD power-up slope is too slow.

The diode D helps discharge the capacitor quickly when VDD powers down.

- 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that the voltage drop across R does not violate the device's electrical specification.
- 3: R1 =  $100\Omega$  to 1 k $\Omega$  will limit any current flowing into  $\overline{\text{MCLR}}$  from external capacitor C, in the event of  $\overline{\text{MCLR}}/\text{VPP}$  pin breakdown due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

#### 3.3 Power-up Timer (PWRT)

The Power-up Timer provides a fixed nominal time-out (parameter #33), only on power-up from the POR. The Power-up Timer operates on an internal RC oscillator. The chip is kept in Reset as long as the PWRT is active. The PWRT's time delay allows VDD to rise to an acceptable level. A configuration bit (PWRTEN in CONFIG2L register) is provided to enable/disable the PWRT.

The power-up time delay will vary from chip to chip due to VDD, temperature and process variation. See DC parameter #33 for details.

#### 3.4 Oscillator Start-up Timer (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over (parameter #32). This additional delay ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP, HS and HS4 modes and only on Power-on Reset or wake-up from Sleep.

#### 3.5 PLL Lock Time-out

With the PLL enabled, the time-out sequence following a Power-on Reset is different from other oscillator modes. A portion of the Power-up Timer is used to provide a fixed time-out that is sufficient for the PLL to lock to the main oscillator frequency. This PLL lock time-out (TPLL) is typically 2 ms and follows the oscillator start-up time-out (OST).

#### 3.6 Brown-out Reset (BOR)

A configuration bit, BOREN, can disable (if clear/programmed), or enable (if set), the Brown-out Reset circuitry. If VDD falls below parameter D005 for greater than parameter #35, the brown-out situation resets the chip. A Reset may not occur if VDD falls below parameter D005 for less than parameter #35. The chip will remain in Brown-out Reset until VDD rises above BVDD. The Power-up Timer will then be invoked and will keep the chip in Reset an additional time delay (parameter #33). If VDD drops below BVDD while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be initialized. Once VDD rises above BVDD, the Power-up Timer will execute the additional time delay.

#### 3.7 Time-out Sequence

On power-up, the time-out sequence is as follows: First, PWRT time-out is invoked after the POR time delay has expired, then OST is activated. The total time-out will vary based on oscillator configuration and the status of the PWRT. For example, in RC mode with the PWRT disabled, there will be no time-out at all. Figure 3-3, Figure 3-4, Figure 3-5, Figure 3-6 and Figure 3-7 depict time-out sequences on power-up.

Since the time-outs occur from the POR pulse, if MCLR is kept low long enough, the time-outs will expire. Bringing MCLR high will begin execution immediately (Figure 3-5). This is useful for testing purposes or to synchronize more than one PIC18FXX8 device operating in parallel.

Table 3-2 shows the Reset conditions for some Special Function Registers, while Table 3-3 shows the Reset conditions for all registers.

TABLE 3-1: TIME-OUT IN VARIOUS SITUATIONS

Oscillator	Power-up	(2)	D(2)	Wake-up from
Configuration	PWRTEN = 0	PWRTEN = 1	Brown-out <sup>(2)</sup>	Sleep or Oscillator Switch
HS with PLL enabled <sup>(1)</sup>	72 ms + 1024 Tosc + 2 ms	1024 Tosc + 2 ms	72 ms + 1024 Tosc + 2 ms	1024 Tosc + 2 ms
HS, XT, LP	72 ms + 1024 Tosc	1024 Tosc	72 ms + 1024 Tosc	1024 Tosc
EC	72 ms	_	72 ms	_
External RC	72 ms	_	72 ms	_

**Note 1:** 2 ms = Nominal time required for the 4x PLL to lock.

2: 72 ms is the nominal Power-up Timer delay.

REGISTER 3-1: RCON REGISTER BITS AND POSITIONS

R/W-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-0	R/W-1
IPEN	_	_	RI	TO	PD	POR	BOR
bit 7							bit 0


TABLE 3-2: STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR RCON REGISTER

Condition	Program Counter	RCON Register	RI	то	PD	POR	BOR	STKFUL	STKUNF
Power-on Reset	0000h	01 110q	1	1	1	0	0	u	u
MCLR Reset during normal operation	0000h	00 011q	u	u	u	u	u	u	u
Software Reset during normal operation	0000h	00 011q	0	u	u	u	u	u	u
Stack Full Reset during normal operation	0000h	00 011q	u	u	u	1	1	u	1
Stack Underflow Reset during normal operation	0000h	00 011q	u	u	u	1	1	1	u
MCLR Reset during Sleep	0000h	00 011q	u	1	0	u	u	u	u
WDT Reset	0000h	00 011q	u	0	1	u	u	u	u
WDT Wake-up	PC + 2	01 101q	u	0	0	u	u	u	u
Brown-out Reset	0000h	01 110q	1	1	1	u	0	u	u
Interrupt wake-up from Sleep	PC + 2 <sup>(1)</sup>	01 101q	u	1	0	u	u	u	u

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0'

**Note 1:** When the wake-up is due to an interrupt and the GIEH or GIEL bits are set, the PC is loaded with the interrupt vector (000008h or 000018h).





#### FIGURE 3-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1







FIGURE 3-5: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2







## www.DataPIC18FXX8

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS

Register	Applicabl		Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
TOSU	PIC18F2X8	PIC18F4X8	0 0000	0 0000	0 uuuu <b>(3)</b>
TOSH	PIC18F2X8		0000 0000	0000 0000	uuuu uuuu(3)
TOSL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu(3)
STKPTR	PIC18F2X8		00-0 0000	uu-0 0000	uu-u uuuu( <b>3)</b>
PCLATU	PIC18F2X8	PIC18F4X8	0 0000	0 0000	u uuuu
PCLATH	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
PCL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	PC + 2 <sup>(2)</sup>
TBLPTRU	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu
TBLPTRH	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TBLPTRL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TABLAT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
PRODH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
PRODL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
INTCON	PIC18F2X8	PIC18F4X8	0000 000x	0000 000u	uuuu uuuu(1)
INTCON2	PIC18F2X8	PIC18F4X8	1111-1	1111-1	uuuu-u <sup>(1)</sup>
INTCON3	PIC18F2X8	PIC18F4X8	11-0 0-00	11-0 0-00	uu-u u-uu <sup>(1)</sup>
INDF0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
POSTINC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
POSTDEC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
PREINC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
PLUSW0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
FSR0H	PIC18F2X8	PIC18F4X8	xxxx	uuuu	uuuu
FSR0L	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
WREG	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
INDF1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
POSTINC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
POSTDEC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
PREINC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A
PLUSW1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A

 $\label{eq:update} \begin{tabular}{ll} \textbf{Legend:} & u = \text{unchanged}, \ x = \text{unknown}, \ - = \text{unimplemented bit}, \ \text{read as `0'}, \ q = \text{value depends on condition}. \\ & Shaded \ cells \ indicate \ conditions \ do \ not \ apply \ for \ the \ designated \ device. \\ \end{tabular}$ 

- **Note 1:** One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
FSR1H	PIC18F2X8 PIC18F4X8	xxxx	uuuu	uuuu
FSR1L	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
BSR	PIC18F2X8 PIC18F4X8	0000	0000	uuuu
INDF2	PIC18F2X8 PIC18F4X8	N/A	N/A	N/A
POSTINC2	PIC18F2X8 PIC18F4X8	N/A	N/A	N/A
POSTDEC2	PIC18F2X8 PIC18F4X8	N/A	N/A	N/A
PREINC2	PIC18F2X8 PIC18F4X8	N/A	N/A	N/A
PLUSW2	PIC18F2X8 PIC18F4X8	N/A	N/A	N/A
FSR2H	PIC18F2X8 PIC18F4X8	xxxx	uuuu	uuuu
FSR2L	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
STATUS	PIC18F2X8 PIC18F4X8	x xxxx	u uuuu	u uuuu
TMR0H	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TMR0L	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
T0CON	PIC18F2X8 PIC18F4X8	1111 1111	1111 1111	uuuu uuuu
OSCCON	PIC18F2X8 PIC18F4X8	0	0	u
LVDCON	PIC18F2X8 PIC18F4X8	00 0101	00 0101	uu uuuu
WDTCON	PIC18F2X8 PIC18F4X8	0	0	u
RCON <sup>(4)</sup>	PIC18F2X8 PIC18F4X8	01 110q	00 011q	01 101q
TMR1H	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TMR1L	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
T1CON	PIC18F2X8 PIC18F4X8	0-00 0000	u-uu uuuu	u-uu uuuu
TMR2	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
PR2	PIC18F2X8 PIC18F4X8	1111 1111	1111 1111	1111 1111
T2CON	PIC18F2X8 PIC18F4X8	-000 0000	-000 0000	-uuu uuuu
SSPBUF	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
SSPADD	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
SSPSTAT	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
SSPCON1	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
SSPCON2	PIC18F2X8 PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
ADRESH	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
ADRESL	PIC18F2X8 PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
ADCON0	PIC18F2X8 PIC18F4X8	0000 00-0	0000 00-0	uuuu uu-u

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable		Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
ADCON1	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu
CCPR1H	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCPR1L	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCP1CON	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu
ECCPR1H	PIC18F2X8		xxxx xxxx	uuuu uuuu	uuuu uuuu
ECCPR1L	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
ECCP1CON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000
ECCP1DEL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000
ECCPAS	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000
CVRCON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
CMCON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TMR3H	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TMR3L	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
T3CON	PIC18F2X8	PIC18F4X8	0000 0000	uuuu uuuu	uuuu uuuu
SPBRG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
RCREG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TXREG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TXSTA	PIC18F2X8	PIC18F4X8	0000 -010	0000 -010	uuuu -uuu
RCSTA	PIC18F2X8	PIC18F4X8	0000 000x	0000 000u	uuuu uuuu
EEADR	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
EEDATA	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
EECON2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
EECON1	PIC18F2X8	PIC18F4X8	xx-0 x000	uu-0 u000	uu-0 u000
IPR3	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu
PIR3	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
PIE3	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
IPR2	PIC18F2X8	PIC18F4X8	-1-1 1111	-1-1 1111	-u-u uuuu
PIR2	PIC18F2X8	PIC18F4X8	-0-0 0000	-0-0 0000	-u-u uuuu <sup>(1)</sup>
PIE2	PIC18F2X8	PIC18F4X8	-0-0 0000	-0-0 0000	-u-u uuuu
IPR1	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu
PIR1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu(1)
PIE1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
				•	•

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
TRISE	PIC18F2X8 PIC18F4X	8 0000 -111	0000 -111	uuuu -uuu
TRISD	PIC18F2X8 PIC18F4X	8 1111 1111	1111 1111	uuuu uuuu
TRISC	PIC18F2X8 PIC18F4X	8 1111 1111	1111 1111	uuuu uuuu
TRISB	PIC18F2X8 PIC18F4X	8 1111 1111	1111 1111	uuuu uuuu
TRISA <sup>(5)</sup>	PIC18F2X8 PIC18F4X	8 -111 1111 <sup>(5)</sup>	-111 1111 <sup>(5)</sup>	-uuu uuuu <sup>(5)</sup>
LATE	PIC18F2X8 PIC18F4X	8xxx	uuu	uuu
LATD	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
LATC	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
LATB	PIC18F2X8 PIC18F4X		uuuu uuuu	uuuu uuuu
LATA <sup>(5)</sup>	PIC18F2X8 PIC18F4X	8 -xxx xxxx <sup>(5)</sup>	-uuu uuuu <sup>(5)</sup>	-uuu uuuu <sup>(5)</sup>
PORTE	PIC18F2X8 PIC18F4X	8xxx	000	uuu
PORTD	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTC	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTB	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTA <sup>(5)</sup>	PIC18F2X8 PIC18F4X	8 -x0x 0000 <sup>(5)</sup>	-u0u 0000 <b>(5)</b>	-uuu uuuu <b>(5)</b>
TXERRCNT	PIC18F2X8 PIC18F4X	0000 0000	0000 0000	uuuu uuuu
RXERRCNT	PIC18F2X8 PIC18F4X	0000 0000	0000 0000	uuuu uuuu
COMSTAT	PIC18F2X8 PIC18F4X	8 0000 0000	0000 0000	uuuu uuuu
CIOCON	PIC18F2X8 PIC18F4X	00	00	uu
BRGCON3	PIC18F2X8 PIC18F4X	-0000	-0000	-uuuu
BRGCON2	PIC18F2X8 PIC18F4X	0000 0000	0000 0000	uuuu uuuu
BRGCON1	PIC18F2X8 PIC18F4X	0000 0000	0000 0000	uuuu uuuu
CANCON	PIC18F2X8 PIC18F4X	8 xxxx xxx-	uuuu uuu-	uuuu uuu-
CANSTAT <sup>(6)</sup>	PIC18F2X8 PIC18F4X	8 xxx- xxx-	uuu- uuu-	uuu- uuu-
RXB0D7	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D6	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D5	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D4	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D3	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D2	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D1	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0D0	PIC18F2X8 PIC18F4X	8 xxxx xxxx	uuuu uuuu	uuuu uuuu

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - **5:** Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices		Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
RXB0DLC	PIC18F2X8	PIC18F4X8	-xxx xxxx	-uuu uuuu	-uuu uuuu
RXB0EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0SIDL	PIC18F2X8	PIC18F4X8	xxxx x-xx	uuuu u-uu	uuuu u-uu
RXB0SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB0CON	PIC18F2X8	PIC18F4X8	000- 0000	000- 0000	uuu- uuuu
RXB1D7	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1DLC	PIC18F2X8	PIC18F4X8	-xxx xxxx	-uuu uuuu	-uuu uuuu
RXB1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1SIDL	PIC18F2X8	PIC18F4X8	xxxx x-xx	uuuu u-uu	uuuu u-uu
RXB1SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXB1CON	PIC18F2X8	PIC18F4X8	000- 0000	000- 0000	uuu- uuuu
TXB0D7	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu
TXB0EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable	licable Devices Power-on Reset, Brown-out Reset		<i>'</i>	Wake-up via WDT or Interrupt
TXB0SIDH	PIC18F2X8		XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB0CON	PIC18F2X8		-000 0-00	-000 0-00	-uuu u-uu
TXB1D7	PIC18F2X8		xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu
TXB1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu
TXB1SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1CON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TXB2D7	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu
TXB2EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu
TXB2SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2CON	PIC18F2X8	PIC18F4X8	-000 0-00	-000 0-00	-uuu u-uu
RXM1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXM1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
		_			

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Register	Applicable Devices PIC18F2X8 PIC18F4X8		able Devices Power-on Reset, Brown-out Reset		Wake-up via WDT or Interrupt	
RXM1SIDL	PIC18F2X8	PIC18F4X8	xxxxx	uuuuu	uuuuu	
RXM1SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXM0EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXM0EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXM0SIDL	PIC18F2X8	PIC18F4X8	XXXXX	uuuuu	uuuuu	
RXM0SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF5EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF5EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF5SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF5SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF4EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF4EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF4SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF4SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF3EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF3EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF3SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF3SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF2EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF2EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF2SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF2SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF1SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF1SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF0EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF0EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
RXF0SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
RXF0SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 3-2 for Reset value for specific condition.
  - 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
  - 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

## 4.0 MEMORY ORGANIZATION

There are three memory blocks in Enhanced MCU devices. These memory blocks are:

- · Enhanced Flash Program Memory
- Data Memory
- EEPROM Data Memory

Data and program memory use separate busses, which allows concurrent access of these blocks. Additional detailed information on data EEPROM and Flash program memory is provided in Section 5.0 "Data EEPROM Memory" and Section 6.0 "Flash Program Memory", respectively.

## 4.1 Program Memory Organization

The PIC18F258/458 devices have a 21-bit program counter that is capable of addressing a 2-Mbyte program memory space.

The Reset vector address is at 0000h and the interrupt vector addresses are at 0008h and 0018h.

FIGURE 4-1: PROGRAM MEMORY MAP
AND STACK FOR
PIC18F248/448





Figure 4-1 shows the diagram for program memory map and stack for the PIC18F248 and PIC18F448. Figure 4-2 shows the diagram for the program memory map and stack for the PIC18F258 and PIC18F458.

# 4.1.1 INTERNAL PROGRAM MEMORY OPERATION

The PIC18F258 and the PIC18F458 have 32 Kbytes of internal Enhanced Flash program memory. This means that the PIC18F258 and the PIC18F458 can store up to 16K of single-word instructions. The PIC18F248 and PIC18F448 have 16 Kbytes of Enhanced Flash program memory. This translates into 8192 single-word instructions, which can be stored in the program memory. Accessing a location between the physically implemented memory and the 2-Mbyte address will cause a read of all '0's (a NOP instruction).

FIGURE 4-2: PROGRAM MEMORY MAP AND STACK FOR PIC18F258/458



#### 4.2 Return Address Stack

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC (Program Counter) is pushed onto the stack when a PUSH, CALL or RCALL instruction is executed, or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN instructions.

The stack operates as a 31-word by 21-bit stack memory and a 5-bit Stack Pointer register, with the Stack Pointer initialized to 00000b after all Resets. There is no RAM associated with Stack Pointer 00000b. This is only a Reset value. During a CALL type instruction, causing a push onto the stack, the Stack Pointer is first incremented and the RAM location pointed to by the Stack Pointer is written with the contents of the PC. During a RETURN type instruction, causing a pop from the stack, the contents of the RAM location indicated by the STKPTR are transferred to the PC and then the Stack Pointer is decremented.

The stack space is not part of either program or data space. The Stack Pointer is readable and writable and the data on the top of the stack is readable and writable through SFR registers. Status bits indicate if the stack pointer is at or beyond the 31 levels provided.

#### 4.2.1 TOP-OF-STACK ACCESS

The top of the stack is readable and writable. Three register locations, TOSU, TOSH and TOSL allow access to the contents of the stack location indicated by the STKPTR register. This allows users to implement a software stack, if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU, TOSH and TOSL registers. These values can be placed on a user defined software stack. At return time, the software can replace the TOSU, TOSH and TOSL and do a return.

The user should disable the global interrupt enable bits during this time to prevent inadvertent stack operations.

# 4.2.2 RETURN STACK POINTER (STKPTR)

The STKPTR register contains the Stack Pointer value, the STKFUL (Stack Full) status bit and the STKUNF (Stack Underflow) status bits. Register 4-1 shows the STKPTR register. The value of the Stack Pointer can be 0 through 31. The Stack Pointer increments when values are pushed onto the stack and decrements when values are popped off the stack. At Reset, the Stack Pointer value will be '0'. The user may read and write the Stack Pointer value. This feature can be used by a Real-Time Operating System for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit can only be cleared in software or by a POR.

The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) configuration bit. Refer to **Section 21.0 "Comparator Module"** for a description of the device configuration bits. If STVREN is set (default), the 31st push will push the (PC + 2) value onto the stack, set the STKFUL bit and reset the device. The STKFUL bit will remain set and the Stack Pointer will be set to 'o'.

If STVREN is cleared, the STKFUL bit will be set on the 31st push and the Stack Pointer will increment to 31. The 32nd push will overwrite the 31st push (and so on), while STKPTR remains at 31.

When the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC and sets the STKUNF bit, while the stack pointer remains at '0'. The STKUNF bit will remain set until cleared in software or a POR occurs.

Note: Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken.

#### STKPTR: STACK POINTER REGISTER **REGISTER 4-1:**

R/C-0	R/C-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
STKFUL	STKUNF	_	SP4	SP3	SP2	SP1	SP0
bit 7							bit 0

bit 0

bit 7 STKFUL: Stack Full Flag bit

1 = Stack became full or overflowed

0 = Stack has not become full or overflowed

bit 6 STKUNF: Stack Underflow Flag bit

1 = Stack underflow occurred

0 = Stack underflow did not occur

bit 5 Unimplemented: Read as '0'


bit 4-0 SP4:SP0: Stack Pointer Location bits

Note: Bit 7 and bit 6 need to be cleared following a stack underflow or a stack overflow.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' n = Value at POR '1' = Bit is set '0' = Bit is cleared C = Clearable bit

#### FIGURE 4-3: RETURN ADDRESS STACK AND ASSOCIATED REGISTERS



#### 4.2.3 PUSH AND POP INSTRUCTIONS

Since the Top-of-Stack (TOS) is readable and writable, the ability to push values onto the stack and pull values off the stack, without disturbing normal program execution, is a desirable option. To push the current PC value onto the stack, a PUSH instruction can be executed. This will increment the Stack Pointer and load the current PC value onto the stack. TOSU, TOSH and TOSL can then be modified to place a return address on the stack.

The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

#### 4.2.4 STACK FULL/UNDERFLOW RESETS

These Resets are enabled by programming the STVREN configuration bit. When the STVREN bit is disabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit, but not cause a device Reset. When the STVREN bit is enabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit and then cause a device Reset. The STKFUL or STKUNF bits are only cleared by the user software or a POR.

## 4.3 Fast Register Stack

A "fast return" option is available for interrupts and calls. A fast register stack is provided for the Status, WREG and BSR registers and is only one layer in depth. The stack is not readable or writable and is loaded with the current value of the corresponding register when the processor vectors for an interrupt. The values in the fast register stack are then loaded back into the working registers if the FAST RETURN instruction is used to return from the interrupt.


A low or high priority interrupt source will push values into the stack registers. If both low and high priority interrupts are enabled, the stack registers cannot be used reliably for low priority interrupts. If a high priority interrupt occurs while servicing a low priority interrupt, the stack register values stored by the low priority interrupt will be overwritten.

If high priority interrupts are not disabled during low priority interrupts, users must save the key registers in software during a low priority interrupt.

If no interrupts are used, the fast register stack can be used to restore the Status, WREG and BSR registers at the end of a subroutine call. To use the fast register stack for a subroutine call, a FAST CALL instruction must be executed.

Example 4-1 shows a source code example that uses the fast register stack.

# EXAMPLE 4-1: FAST REGISTER STACK CODE EXAMPLE



## 4.4 PCL, PCLATH and PCLATU

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide. The low byte is called the PCL register. This register is readable and writable. The high byte is called the PCH register. This register contains the PC<15:8> bits and is not directly readable or writable. Updates to the PCH register may be performed through the PCLATH register. The upper byte is called PCU. This register contains the PC<20:16> bits and is not directly readable or writable. Updates to the PCU register may be performed through the PCLATU register.

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the LSb of PCL is fixed to a value of '0'. The PC increments by 2 to address sequential instructions in the program memory.

The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.

The contents of PCLATH and PCLATU will be transferred to the program counter by an operation that writes PCL. Similarly, the upper two bytes of the program counter will be transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see Section 4.8.1 "Computed GOTO").

#### 4.5 **Clocking Scheme/Instruction** Cycle

The clock input (from OSC1) is internally divided by four to generate four non-overlapping quadrature clocks, namely Q1, Q2, Q3 and Q4. Internally, the Program Counter (PC) is incremented every Q1, the instruction is fetched from the program memory and latched into the instruction register in Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow are shown in Figure 4-4.




FIGURE 4-4: **CLOCK/INSTRUCTION CYCLE** 

#### 4.6 Instruction Flow/Pipelining

An "Instruction Cycle" consists of four Q cycles (Q1, Q2, Q3 and Q4). The instruction fetch and execute are pipelined such that fetch takes one instruction cycle. while decode and execute take another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO), two cycles are required to complete the instruction (Example 4-2).

A fetch cycle begins with the Program Counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the "Instruction Register" (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3 and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).

#### 4.7 **Instructions in Program Memory**

The program memory is addressed in bytes. Instructions are stored as two bytes or four bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSB = 0). Figure 4-3 shows an example of how instruction words are stored in the program memory. To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSB will always read '0' (see Section 4.4 "PCL, PCLATH and PCLATU").

The CALL and GOTO instructions have an absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1>, which accesses the desired byte address in program memory. Instruction #2 in Example 4-3 shows how the instruction "GOTO 000006h" is encoded in the program memory. Program branch instructions that encode a relative address offset operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions by which the PC will be offset. Section 25.0 "Instruction Set Summary" provides further details of the instruction set.

## www.DataPIC18FXX8

## **EXAMPLE 4-2: INSTRUCTION PIPELINE FLOW**

	Tcy0	Tcy1	Tcy2	Tcy3	Tcy4	Tcy5
ı	1010	1011	1012	1010	1014	1013
1. MOVLW 55h	Fetch 1	Execute 1		_		
2. MOVWF PORTB		Fetch 2	Execute 2		_	
3. BRA SUB_1			Fetch 3	Execute 3		
4. BSF PORTA, BIT3 (1		Fetch 4	Flush			
5. Instruction @ addres	ss SUB_1				Fetch SUB_1	Execute SUB_1

**Note:** All instructions are single cycle, except for any program branches. These take two cycles, since the fetch instruction is "flushed" from the pipeline while the new instruction is being fetched and then executed.

## **EXAMPLE 4-3: INSTRUCTIONS IN PROGRAM MEMORY**

Instruction	Opcode	Memory	Address
_			000007h
MOVLW 055h	0E55h	55h	000008h
		0Eh	000009h
GOTO 000006h	0EF03h, 0F000h	03h	00000Ah
		0EFh	00000Bh
		00h	00000Ch
		0F0h	00000Dh
MOVFF 123h, 456h	0C123h, 0F456h	23h	00000Eh
		0C1h	00000Fh
		56h	000010h
		0F4h	000011h
_			000012h

#### 4.7.1 TWO-WORD INSTRUCTIONS

The PIC18FXX8 devices have 4 two-word instructions: MOVFF, CALL, GOTO and LFSR. The 4 Most Significant bits of the second word are set to '1's and indicate a special NOP instruction. The lower 12 bits of the second word contain the data to be used by the instruction. If the first word of the instruction is executed, the data in the second word is accessed. If the second word of the instruction is executed by itself (first word was skipped), it will execute as a NOP. This action is necessary when the two-word instruction is preceded by a conditional instruction that changes the PC. A program example that demonstrates this concept is shown in Example 4-4. Refer to **Section 25.0** "Instruction Set **Summary**" for further details of the instruction set.

## 4.8 Look-up Tables

Look-up tables are implemented two ways. These are:

- Computed GOTO
- · Table Reads

## 4.8.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL).

A look-up table can be formed with an ADDWF  $\,$  PCL instruction and a group of RETLW  $\,$ 0xnn instructions. WREG is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is the ADDWF  $\,$  PCL instruction. The next

instruction executed will be one of the RETLW 0xnn instructions that returns the value 0xnn to the calling function.

The offset value (value in WREG) specifies the number of bytes that the program counter should advance.

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

- **Note 1:** The LSb of PCL is fixed to a value of '0'. Hence, computed GOTO to an odd address is not possible.
  - 2: The ADDWF PCL instruction does not update PCLATH/PCLATU. A read operation on PCL must be performed to update PCLATH and PCLATU.

#### 4.8.2 TABLE READS/TABLE WRITES

A better method of storing data in program memory allows 2 bytes of data to be stored in each instruction location.

Look-up table data may be stored as 2 bytes per program word by using table reads and writes. The Table Pointer (TBLPTR) specifies the byte address and the Table Latch (TABLAT) contains the data that is read from, or written to, program memory. Data is transferred to/from program memory, one byte at a time.

A description of the table read/table write operation is shown in Section 6.1 "Table Reads and Table Writes".

### **EXAMPLE 4-4: TWO-WORD INSTRUCTIONS**

CASE 1:	CASE 1:										
Object Code		Source Code									
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?									
1100 0001 0010 0011	MOVFF REG1, REG2	; No, execute 2-word instruction									
1111 0100 0101 0110		; 2nd operand holds address of REG2									
0010 0100 0000 0000	ADDWF REG3	; continue code									

#### CASE 2:

Object Code	Source Code					
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?				
1100 0001 0010 0011	MOVFF REG1, REG2	; Yes				
1111 0100 0101 0110		; 2nd operand becomes NOP				
0010 0100 0000 0000	ADDWF REG3	; continue code				

## 4.9 Data Memory Organization

The data memory is implemented as static RAM. Each register in the data memory has a 12-bit address, allowing up to 4096 bytes of data memory. Figure 4-6 shows the data memory organization for the PIC18FXX8 devices.

The data memory map is divided into as many as 16 banks that contain 256 bytes each. The lower 4 bits of the Bank Select Register (BSR<3:0>) select which bank will be accessed. The upper 4 bits for the BSR are not implemented.

The data memory contains Special Function Registers (SFRs) and General Purpose Registers (GPRs). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratchpad operations in the user's application. The SFRs start at the last location of Bank 15 (FFFh) and grow downwards. GPRs start at the first location of Bank 0 and grow upwards. Any read of an unimplemented location will read as '0's.

The entire data memory may be accessed directly or indirectly. Direct addressing may require the use of the BSR register. Indirect addressing requires the use of the File Select Register (FSR). Each FSR holds a 12-bit address value that can be used to access any location in the data memory map without banking.

The instruction set and architecture allow operations across all banks. This may be accomplished by indirect addressing or by the use of the MOVFF instruction. The MOVFF instruction is a two-word/two-cycle instruction, that moves a value from one register to another.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle, regardless of the current BSR values, an Access Bank is implemented. A segment of Bank 0 and a segment of Bank 15 comprise the Access RAM. **Section 4.10** "Access Bank" provides a detailed description of the Access RAM.

# 4.9.1 GENERAL PURPOSE REGISTER FILE

The register file can be accessed either directly or indirectly. Indirect addressing operates through the File Select Registers (FSR). The operation of indirect addressing is shown in **Section 4.12 "Indirect Addressing, INDF and FSR Registers"**.

Enhanced MCU devices may have banked memory in the GPR area. GPRs are not initialized by a Power-on Reset and are unchanged on all other Resets.

Data RAM is available for use as GPR registers by all instructions. Bank 15 (F00h to FFFh) contains SFRs. All other banks of data memory contain GPR registers, starting with Bank 0.


#### 4.9.2 SPECIAL FUNCTION REGISTERS


The Special Function Registers (SFRs) are registers used by the CPU and peripheral modules for controlling the desired operation of the device. These registers are implemented as static RAM. A list of these registers is given in Table 4-1.

The SFRs can be classified into two sets: those associated with the "core" function and those related to the peripheral functions. Those registers related to the "core" are described in this section, while those related to the operation of the peripheral features are described in the section of that peripheral feature.

The SFRs are typically distributed among the peripherals whose functions they control.

The unused SFR locations will be unimplemented and read as '0's. See Table 4-1 for addresses for the SFRs.





© 2006 Microchip Town Data Sheet 4U.com

TABLE 4-1: SPECIAL FUNCTION REGISTER MAP

Address	Name	Address	Name	Address	Name	Address	Name
FFFh	TOSU	FDFh	INDF2 <sup>(2)</sup>	FBFh	CCPR1H	F9Fh	IPR1
FFEh	TOSH	FDEh	POSTINC2 <sup>(2)</sup>	FBEh	CCPR1L	F9Eh	PIR1
FFDh	TOSL	FDDh	POSTDEC2 <sup>(2)</sup>	FBDh	CCP1CON	F9Dh	PIE1
FFCh	STKPTR	FDCh	PREINC2 <sup>(2)</sup>	FBCh	ECCPR1H <sup>(5)</sup>	F9Ch	_
FFBh	PCLATU	FDBh	PLUSW2 <sup>(2)</sup>	FBBh	ECCPR1L <sup>(5)</sup>	F9Bh	_
FFAh	PCLATH	FDAh	FSR2H	FBAh	ECCP1CON <sup>(5)</sup>	F9Ah	
FF9h	PCL	FD9h	FSR2L	FB9h	_	F99h	_
FF8h	TBLPTRU	FD8h	STATUS	FB8h	_	F98h	
FF7h	TBLPTRH	FD7h	TMR0H	FB7h	ECCP1DEL <sup>(5)</sup>	F97h	_
FF6h	TBLPTRL	FD6h	TMR0L	FB6h	ECCPAS <sup>(5)</sup>	F96h	TRISE <sup>(5)</sup>
FF5h	TABLAT	FD5h	T0CON	FB5h	CVRCON <sup>(5)</sup>	F95h	TRISD <sup>(5)</sup>
FF4h	PRODH	FD4h	_	FB4h	CMCON <sup>(5)</sup>	F94h	TRISC
FF3h	PRODL	FD3h	OSCCON	FB3h	TMR3H	F93h	TRISB
FF2h	INTCON	FD2h	LVDCON	FB2h	TMR3L	F92h	TRISA
FF1h	INTCON2	FD1h	WDTCON	FB1h	T3CON	F91h	_
FF0h		FD0h	RCON	FB0h	_	F90h	
FEFh		FCFh	TMR1H	FAFh	SPBRG	F8Fh	_
FEEh	POSTINCO <sup>(2)</sup>	FCEh	TMR1L	FAEh	RCREG	F8Eh	
FEDh		FCDh	T1CON	FADh	TXREG	F8Dh	LATE <sup>(5)</sup>
FECh	PREINCO <sup>(2)</sup>	FCCh	TMR2	FACh	TXSTA	F8Ch	LATD <sup>(5)</sup>
FEBh	PLUSW0 <sup>(2)</sup>	FCBh	PR2	FABh	RCSTA	F8Bh	LATC
FEAh	FSR0H	FCAh	T2CON	FAAh	_	F8Ah	LATB
FE9h	FSR0L	FC9h	SSPBUF	FA9h	EEADR	F89h	LATA
FE8h		FC8h	SSPADD	FA8h	EEDATA	F88h	_
FE7h		FC7h	SSPSTAT	FA7h	EECON2	F87h	_
FE6h	POSTINC1 <sup>(2)</sup>	FC6h	SSPCON1	FA6h	EECON1	F86h	_
FE5h		FC5h	SSPCON2	FA5h	IPR3	F85h	_
FE4h		FC4h	ADRESH	FA4h	PIR3	F84h	PORTE <sup>(5)</sup>
FE3h	PLUSW1 <sup>(2)</sup>	FC3h	ADRESL	FA3h	PIE3	F83h	PORTD <sup>(5)</sup>
FE2h	FSR1H	FC2h	ADCON0	FA2h	IPR2	F82h	PORTC
FE1h	FSR1L	FC1h	ADCON1	FA1h	PIR2	F81h	PORTB
FE0h	BSR	FC0h	_	FA0h	PIE2	F80h	PORTA

Note 1: Unimplemented registers are read as '0'.

- 2: This is not a physical register.
- **3:** Contents of register are dependent on WIN2:WIN0 bits in the CANCON register.
- **4:** CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip header file requirement.
- **5:** These registers are not implemented on the PIC18F248 and PIC18F258.

## www.DataPIC18FXX8

TABLE 4-1: SPECIAL FUNCTION REGISTER MAP (CONTINUED)

Address	Name	Address	Name	Address	Name	Address	Name
F7Fh	_	F5Fh	_	F3Fh	_	F1Fh	RXM1EIDL
F7Eh	_	F5Eh	CANSTATRO1 <sup>(4)</sup>	F3Eh	CANSTATRO3 <sup>(4)</sup>	F1Eh	RXM1EIDH
F7Dh	_	F5Dh	RXB1D7	F3Dh	TXB1D7	F1Dh	RXM1SIDL
F7Ch	_	F5Ch	RXB1D6	F3Ch	TXB1D6	F1Ch	RXM1SIDH
F7Bh	_	F5Bh	RXB1D5	F3Bh	TXB1D5	F1Bh	RXM0EIDL
F7Ah	_	F5Ah	RXB1D4	F3Ah	TXB1D4	F1Ah	RXM0EIDH
F79h	_	F59h	RXB1D3	F39h	TXB1D3	F19h	RXM0SIDL
F78h	_	F58h	RXB1D2	F38h	TXB1D2	F18h	RXM0SIDH
F77h	_	F57h	RXB1D1	F37h	TXB1D1	F17h	RXF5EIDL
F76h	TXERRCNT	F56h	RXB1D0	F36h	TXB1D0	F16h	RXF5EIDH
F75h	RXERRCNT	F55h	RXB1DLC	F35h	TXB1DLC	F15h	RXF5SIDL
F74h	COMSTAT	F54h	RXB1EIDL	F34h	TXB1EIDL	F14h	RXF5SIDH
F73h	CIOCON	F53h	RXB1EIDH	F33h	TXB1EIDH	F13h	RXF4EIDL
F72h	BRGCON3	F52h	RXB1SIDL	F32h	TXB1SIDL	F12h	RXF4EIDH
F71h	BRGCON2	F51h	RXB1SIDH	F31h	TXB1SIDH	F11h	RXF4SIDL
F70h	BRGCON1	F50h	RXB1CON	F30h	TXB1CON	F10h	RXF4SIDH
F6Fh	CANCON	F4Fh	_	F2Fh	_	F0Fh	RXF3EIDL
F6Eh	CANSTAT	F4Eh	CANSTATRO2 <sup>(4)</sup>	F2Eh	CANSTATRO4 <sup>(4)</sup>	F0Eh	RXF3EIDH
F6Dh	RXB0D7 <sup>(3)</sup>	F4Dh	TXB0D7	F2Dh	TXB2D7	F0Dh	RXF3SIDL
F6Ch		F4Ch	TXB0D6	F2Ch	TXB2D6	F0Ch	RXF3SIDH
F6Bh	RXB0D5 <sup>(3)</sup>	F4Bh	TXB0D5	F2Bh	TXB2D5	F0Bh	RXF2EIDL
F6Ah	RXB0D4 <sup>(3)</sup>	F4Ah	TXB0D4	F2Ah	TXB2D4	F0Ah	RXF2EIDH
F69h	RXB0D3 <sup>(3)</sup>	F49h	TXB0D3	F29h	TXB2D3	F09h	RXF2SIDL
F68h	RXB0D2 <sup>(3)</sup>	F48h	TXB0D2	F28h	TXB2D2	F08h	RXF2SIDH
F67h		F47h	TXB0D1	F27h	TXB2D1	F07h	RXF1EIDL
F66h		F46h	TXB0D0	F26h	TXB2D0	F06h	RXF1EIDH
F65h		F45h	TXB0DLC	F25h	TXB2DLC	F05h	RXF1SIDL
F64h	RXB0EIDL <sup>(3)</sup>	F44h	TXB0EIDL	F24h	TXB2EIDL	F04h	RXF1SIDH
F63h	RXB0EIDH <sup>(3)</sup>	F43h	TXB0EIDH	F23h	TXB2EIDH	F03h	RXF0EIDL
F62h		F42h	TXB0SIDL	F22h	TXB2SIDL	F02h	RXF0EIDH
	RXB0SIDH <sup>(3)</sup>	F41h	TXB0SIDH	F21h	TXB2SIDH	F01h	RXF0SIDL
F60h	RXB0CON <sup>(3)</sup>	F40h	TXB0CON	F20h	TXB2CON	F00h	RXF0SIDH

Note: Shaded registers are available in Bank 15, while the rest are in Access Bank low.

- Note 1: Unimplemented registers are read as '0'.
  - 2: This is not a physical register.
  - 3: Contents of register are dependent on WIN2:WIN0 bits in the CANCON register.
  - **4:** CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip header file requirement.
  - 5: These registers are not implemented on the PIC18F248 and PIC18F258.

**TABLE 4-2: REGISTER FILE SUMMARY** 

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
TOSU				Tan of Charlet	Inner Dide /T/	2000:46: \				_
TOSH	Top of Stock I	ligh Byte (TOS		Top-of-Stack L	pper byte (1	33<20.10>)			0000 0000	30, 38 30, 38
TOSL		<u> </u>							+	
STKPTR	STKFUL	_ow Byte (TOS STKUNF	<7.0>)	Return Stack F	Pointor				0000 0000	30, 38
PCLATU	SIKFUL	STRUNE	bit 21 <sup>(2)</sup>			.16.				30, 39
PCLATH	Holding Bogin	tor for DC 415:		Holding Regist	lei 101 FC<20	.10>			0 0000	30, 40
PCL		ster for PC<15:8	o>						0000 0000	30, 40
	PC Low Byte	(FC<7.0>)	bit 21 <sup>(2)</sup>	Drogram Mam	on, Toblo Doi	ntor I Innor Du	o /TDI DTD .	20:16: \	0000 0000	30, 40
TBLPTRU	Drogram Man	- Toble Bein		Program Mem TBLPTR<15:8>	•	niter Opper By	e (IDLFIN	20.16>)	00 0000	30, 68
TBLPTRL					?)				0000 0000	30, 68
		nory Table Poin		IDLF I N<1.0>)					0000 0000	30, 68
TABLAT PRODH		nory Table Late	<u> </u>						0000 0000	30, 68
	Product Regis								xxxx xxxx	30, 75
PRODL	Product Regis	PEIE/GIEL	TMPOIE	INT0IE	RBIE	TMDOLE	INTOIF	RBIF	XXXX XXXX	30, 75
INTCON	GIE/GIEH		TMR0IE	INTOIL		TMR0IF	INTOIF		0000 000x	30, 79
INTCON2	RBPU	INTEDG0	INTEDG1	-	-	TMR0IP	- INITOIE	RBIP	1111-1	30, 80
INTCON3	INT2IP	INT1IP		INT2IE	INT1IE		INT2IF	INT1IF	11-0 0-00	30, 81
INDF0				mory – value of					N/A	30, 55
POSTINCO				mory – value of					N/A	30, 55
POSTDEC0				mory – value of					N/A	30, 55
PREINC0				mory – value of					N/A	30, 55
PLUSW0	Uses contents	s of FSR0 to ad	dress data me	mory – value of					N/A	30, 55
FSR0H					Indirect Data	Memory Add	ress Pointer	0 High	xxxx	30, 55
FSR0L		Memory Addres	ss Pointer 0 Lo	w Byte					XXXX XXXX	30, 55
WREG	Working Regi								XXXX XXXX	30, 55
INDF1				mory – value of		• , ,	· ·		N/A	30, 55
POSTINC1				mory – value of					N/A	30, 55
POSTDEC1				mory – value of					N/A	30, 55
PREINC1				mory – value of					N/A	30, 55
PLUSW1	Uses contents	s of FSR1 to ad	dress data me	mory – value of					N/A	30, 55
FSR1H					Indirect Data	Memory Add	ress Pointer	1 High	xxxx	31, 55
FSR1L	Indirect Data I	Memory Addres	ss Pointer 1 Lo	w Byte		<b>5</b>			XXXX XXXX	31, 55
BSR		(5000)		_	Bank Select			. \	0000	31, 54
INDF2				mory – value of					N/A	31, 55
POSTINC2				mory – value of	· · · · · · · · · · · · · · · · · · ·			<u> </u>	N/A	31, 55
POSTDEC2				mory – value of					N/A	31, 55
PREINC2				mory – value of					N/A	31, 55
PLUSW2	Uses contents	s of FSR2 to ad	dress data me	mory – value of					N/A	31, 55
FSR2H		<u> </u>		_	Indirect Data	Memory Add	ress Pointer	2 High	xxxx	31, 55
FSR2L	Indirect Data I	Memory Addres			I	<u> </u>	T		XXXX XXXX	31, 55
STATUS				N	OV	Z	DC	С	0000 0000	31, 57
TMR0H		mer0 Register High Byte								31, 111
TMR0L	Timer0 Regist		To 0.0	<b>T</b> 0.5-	nc:	T05.5-	<b>T</b> 055:	T055-	XXXX XXXX	31, 111
T0CON	TMR0ON	T08BIT	T0CS	TOSE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	31, 109
OSCCON				-	-	-	-	SCS	0	31, 20
LVDCON			IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0	00 0101	31, 261
WDTCON	_	_		_	<u> </u>			SWDTEN	0	31, 272
RCON	IPEN	_	_	RI	TO	PD	POR	BOR	01 110q	31, 58, 91

Legend: Note 1:

 $\mathbf{x} = \text{unknown}, \, \mathbf{u} = \text{unchanged}, \, \text{-= unimplemented}, \, \mathbf{q} = \text{value depends on condition}$ These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

Bit 21 of the TBLPTRU allows access to the device configuration bits. 2:

RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

## www.DataPIC18FXX8

TABLE 4-2: REGISTER FILE SUMMARY (CONTINUED)

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
TMR1H	Timer1 Regist	ter High Byte							xxxx xxxx	31, 116
TMR1L	Timer1 Regist	ter Low Byte							xxxx xxxx	31, 116
T1CON	RD16	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0-00 0000	31, 113
TMR2	Timer2 Regist	ter			•			•	0000 0000	31, 118
PR2	Timer2 Period	l Register							1111 1111	31, 118
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	31, 117
SSPBUF	SSP Receive	Buffer/Transmi	t Register						xxxx xxxx	31, 146
SSPADD	SSP Address	Register in I <sup>2</sup> C	™ Slave mode	e. SSP Baud Ra	ate Reload Re	gister in I <sup>2</sup> C N	/laster mode.	i	0000 0000	31, 152
SSPSTAT	SMP	CKE	D/ <del>A</del>	Р	S	R/W	UA	BF	0000 0000	31, 144, 153
SSPCON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	31, 145, 145
SSPCON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	31, 155
ADRESH	A/D Result Re	egister High By	te						xxxx xxxx	31, 243
ADRESL	A/D Result Re	egister Low Byt	е						xxxx xxxx	31, 243
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	31, 241
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	32, 242
CCPR1H	Capture/Comp	pare/PWM Reg	jister 1 High By	/te					xxxx xxxx	32, 124
CCPR1L	Capture/Comp	pare/PWM Reg	ister 1 Low By	te					xxxx xxxx	32, 124
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	32, 123
ECCPR1H <sup>(1)</sup>	Enhanced Ca	pture/Compare	/PWM Registe	r 1 High Byte					xxxx xxxx	32, 133
ECCPR1L <sup>(1)</sup>	Enhanced Ca	pture/Compare	/PWM Registe	r 1 Low Byte					xxxx xxxx	32, 133
ECCP1CON <sup>(1)</sup>	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000 0000	32, 131
ECCP1DEL <sup>(1)</sup>	EPDC7	EPDC6	EPDC5	EPDC4	EPDC3	EPDC2	EPDC1	EPDC0	0000 0000	32, 140
ECCPAS <sup>(1)</sup>	ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0	0000 0000	32, 142
CVRCON <sup>(1)</sup>	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000 0000	32, 255
CMCON <sup>(1)</sup>	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	32, 249
TMR3H	Timer3 Regist	ter High Byte							xxxx xxxx	32, 121
TMR3L	Timer3 Regist	ter Low Byte			1				xxxx xxxx	32, 121
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	32, 119
SPBRG	USART Baud	Rate Generato	or						0000 0000	32, 185
RCREG	USART Rece	ive Register							0000 0000	32, 191
TXREG	USART Trans	mit Register							0000 0000	32, 189
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	32, 183
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	32, 184
EEADR	EEPROM Add	dress Register							xxxx xxxx	32, 59
EEDATA	EEPROM Dat	ta Register							xxxx xxxx	32, 59
EECON2	EEPROM Cor	ntrol Register 2	(not a physica	l register)					xxxx xxxx	32, 59
EECON1	EEPGD	CFGS	-	FREE	WRERR	WREN	WR	RD	xx-0 x000	32, 60, 67
IPR3	IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP	1111 1111	32, 90
PIR3	IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF	0000 0000	32, 84
PIE3	IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE	0000 0000	32, 87
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP <sup>(1)</sup>	-1-1 1111	32, 89
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>	-0-0 0000	32, 83
PIE2	_	CMIE	-	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>	-0-0 0000	32, 86

 $\textbf{Legend:} \qquad x = \text{unknown, } u = \text{unchanged, -= unimplemented, } q = \text{value depends on condition}$ 

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

2: Bit 21 of the TBLPTRU allows access to the device configuration bits.

3: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

**REGISTER FILE SUMMARY (CONTINUED) TABLE 4-2:** 

TABLE T-2				HIII (CON	1	, 	I		1		
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:	
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	32, 88	
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	32, 82	
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	32, 85	
TRISE <sup>(1)</sup>	IBF	OBF	IBOV	PSPMODE	_	Data Direction	n bits for POF	RTE <sup>(1)</sup>	0000 -111	33, 105	
TRISD <sup>(1)</sup>	Data Direction	n Control Regis	ter for PORTD	(1)					1111 1111	33, 102	
TRISC	Data Direction	n Control Regis	ter for PORTC						1111 1111	33, 100	
TRISB	Data Direction	n Control Regis	ter for PORTB						1111 1111	33, 96	
TRISA <sup>(3)</sup>	_	Data Direction	Control Regis	ter for PORTA					-111 1111	33, 93	
LATE <sup>(1)</sup>	_	_	_	_	_	Read PORTE PORTE Data	Data Latch, Latch <sup>(1)</sup>	Write	xxx	33, 104	
LATD <sup>(1)</sup>	Read PORTD	Data Latch, W	rite PORTD Da	ata Latch <sup>(1)</sup>					xxxx xxxx	33, 102	
LATC	Read PORTO	Data Latch, W	rite PORTC Da	ata Latch					xxxx xxxx	33, 100	
LATB	Read PORTB	Data Latch, W	rite PORTB Da	ata Latch					xxxx xxxx	33, 96	
LATA <sup>(3)</sup>	_	Read PORTA Data Latch, Write PORTA Data Latch							-xxx xxxx	33, 93	
PORTE <sup>(1)</sup>	— — — Read PORTE pins, Write PORTE Data Latch <sup>(1)</sup>								xxx	33, 104	
PORTD <sup>(1)</sup>	Read PORTD	pins, Write PC		xxxx xxxx	33, 102						
PORTC	Read PORTO	Read PORTC pins, Write PORTC Data Latch									
PORTB	Read PORTB	pins, Write PC	RTB Data Late	ch					xxxx xxxx	33, 96	
PORTA <sup>(3)</sup>	_	Read PORTA	pins, Write PO	RTA Data Latc	h				-x0x 0000	33, 93	
TXERRCNT	TEC7	TEC6	TEC5	TEC4	TEC3	TEC2	TEC1	TEC0	0000 0000	33, 209	
RXERRCNT	REC7	REC6	REC5	REC4	REC3	REC2	REC1	REC0	0000 0000	33, 214	
COMSTAT	RXB0OVFL	RXB10VFL	TXBO	TXBP	RXBP	TXWARN	RXWARN	EWARN	0000 0000	33, 205	
CIOCON	_	_	ENDRHI	CANCAP	_	_	_	_	00	33, 221	
BRGCON3	_	WAKFIL	I	_	_	SEG2PH2	SEG2PH1	SEG2PH0	-0000	33, 220	
BRGCON2	SEG2PHTS	SAM	SEG1PH2	SEG1PH1	SEG1PH0	PRSEG2	PRSEG1	PRSEG0	0000 0000	33, 219	
BRGCON1	SJW1	SJW0	BRP5	BRP4	BRP3	BRP2	BRP1	BRP0	0000 0000	33, 218	
CANCON	REQOP2	REQOP1	REQOP0	ABAT	WIN2	WIN1	WIN0	_	xxxx xxx-	33, 201	
CANSTAT	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202	
RXB0D7	RXB0D77	RXB0D76	RXB0D75	RXB0D74	RXB0D73	RXB0D72	RXB0D71	RXB0D70	xxxx xxxx	33, 214	
RXB0D6	RXB0D67	RXB0D66	RXB0D65	RXB0D64	RXB0D63	RXB0D62	RXB0D61	RXB0D60	xxxx xxxx	33, 214	
RXB0D5	RXB0D57	RXB0D56	RXB0D55	RXB0D54	RXB0D53	RXB0D52	RXB0D51	RXB0D50	xxxx xxxx	33, 214	
RXB0D4	RXB0D47	RXB0D46	RXB0D45	RXB0D44	RXB0D43	RXB0D42	RXB0D41	RXB0D40	xxxx xxxx	33, 214	
RXB0D3	RXB0D37	RXB0D36	RXB0D35	RXB0D34	RXB0D33	RXB0D32	RXB0D31	RXB0D30	xxxx xxxx	33, 214	
RXB0D2	RXB0D27	RXB0D26	RXB0D25	RXB0D24	RXB0D23	RXB0D22	RXB0D21	RXB0D20	xxxx xxxx	33, 214	
RXB0D1	RXB0D17	RXB0D16	RXB0D15	RXB0D14	RXB0D13	RXB0D12	RXB0D11	RXB0D10	xxxx xxxx	33, 214	
RXB0D0	RXB0D07	RXB0D06	RXB0D05	RXB0D04	RXB0D03	RXB0D02	RXB0D01	RXB0D00	xxxx xxxx	33, 214	
RXB0DLC	_	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0	-xxx xxxx	34, 213	
RXB0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 213	
RXB0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 212	
RXB0SIDL	SID2	SID1	SID0	SRR	EXID	_	EID17	EID16	xxxx x-xx	34, 212	
RXB0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	34, 212	
RXB0CON	RXFUL	RXM1	RXM0	_	RXRTRRO	RXB0DBEN	JTOFF	FILHIT0	000- 0000	34, 210	

Legend:

x= unknown, u= unchanged, -= unimplemented, q= value depends on condition These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's. Note 1:

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.

RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

## www.DataPIC18FXX8

**TABLE 4-2:** REGISTER FILE SUMMARY (CONTINUED)

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
CANSTATRO1	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
RXB1D7	RXB1D77	RXB1D76	RXB1D75	RXB1D74	RXB1D73	RXB1D72	RXB1D71	RXB1D70	xxxx xxxx	34, 214
RXB1D6	RXB1D67	RXB1D66	RXB1D65	RXB1D64	RXB1D63	RXB1D62	RXB1D61	RXB1D60	xxxx xxxx	34, 214
RXB1D5	RXB1D57	RXB1D56	RXB1D55	RXB1D54	RXB1D53	RXB1D52	RXB1D51	RXB1D50	xxxx xxxx	34, 214
RXB1D4	RXB1D47	RXB1D46	RXB1D45	RXB1D44	RXB1D43	RXB1D42	RXB1D41	RXB1D40	xxxx xxxx	34, 214
RXB1D3	RXB1D37	RXB1D36	RXB1D35	RXB1D34	RXB1D33	RXB1D32	RXB1D31	RXB1D30	xxxx xxxx	34, 214
RXB1D2	RXB1D27	RXB1D26	RXB1D25	RXB1D24	RXB1D23	RXB1D22	RXB1D21	RXB1D20	xxxx xxxx	34, 214
RXB1D1	RXB1D17	RXB1D16	RXB1D15	RXB1D14	RXB1D13	RXB1D12	RXB1D11	RXB1D10	xxxx xxxx	34, 214
RXB1D0	RXB1D07	RXB1D06	RXB1D05	RXB1D04	RXB1D03	RXB1D02	RXB1D01	RXB1D00	xxxx xxxx	34, 214
RXB1DLC	_	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0	-xxx xxxx	34, 213
RXB1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 213
RXB1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 212
RXB1SIDL	SID2	SID1	SID0	SRR	EXID	_	EID17	EID16	xxxx x-xx	34, 212
RXB1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	34, 212
RXB1CON	RXFUL	RXM1	RXM0	_	RXRTRRO	FILHIT2	FILHIT1	FILHIT0	000- 0000	34, 211
CANSTATRO2	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
TXB0D7	TXB0D77	TXB0D76	TXB0D75	TXB0D74	TXB0D73	TXB0D72	TXB0D71	TXB0D70	xxxx xxxx	34, 208
TXB0D6	TXB0D67	TXB0D66	TXB0D65	TXB0D64	TXB0D63	TXB0D62	TXB0D61	TXB0D60	xxxx xxxx	34, 208
TXB0D5	TXB0D57	TXB0D56	TXB0D55	TXB0D54	TXB0D53	TXB0D52	TXB0D51	TXB0D50	xxxx xxxx	34, 208
TXB0D4	TXB0D47	TXB0D46	TXB0D45	TXB0D44	TXB0D43	TXB0D42	TXB0D41	TXB0D40	xxxx xxxx	34, 208
TXB0D3	TXB0D37	TXB0D36	TXB0D35	TXB0D34	TXB0D33	TXB0D32	TXB0D31	TXB0D30	xxxx xxxx	34, 208
TXB0D2	TXB0D27	TXB0D26	TXB0D25	TXB0D24	TXB0D23	TXB0D22	TXB0D21	TXB0D20	xxxx xxxx	34, 208
TXB0D1	TXB0D17	TXB0D16	TXB0D15	TXB0D14	TXB0D13	TXB0D12	TXB0D11	TXB0D10	xxxx xxxx	34, 208
TXB0D0	TXB0D07	TXB0D06	TXB0D05	TXB0D04	TXB0D03	TXB0D02	TXB0D01	TXB0D00	xxxx xxxx	34, 208
TXB0DLC	_	TXRTR	_	_	DLC3	DLC2	DLC1	DLC0	-x xxxx	34, 209
TXB0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 208
TXB0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 207
TXB0SIDL	SID2	SID1	SID0		EXIDE	_	EID17	EID16	xxx- x-xx	34, 207
TXB0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	35, 207
TXB0CON	_	TXABT	TXLARB	TXERR	TXREQ	_	TXPRI1	TXPRI0	-000 0-00	35, 206
CANSTATRO3	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
TXB1D7	TXB1D77	TXB1D76	TXB1D75	TXB1D74	TXB1D73	TXB1D72	TXB1D71	TXB1D70	XXXX XXXX	35, 208
TXB1D6	TXB1D67	TXB1D66	TXB1D65	TXB1D64	TXB1D63	TXB1D62	TXB1D61	TXB1D60	xxxx xxxx	35, 208
TXB1D5	TXB1D57	TXB1D56	TXB1D55	TXB1D54	TXB1D53	TXB1D52	TXB1D51	TXB1D50	xxxx xxxx	35, 208
TXB1D3	TXB1D47	TXB1D46	TXB1D35	TXB1D44	TXB1D33	TXB1D32	TXB1D41	TXB1D30	XXXX XXXX	35, 208
TXB1D3	TXB1D37	TXB1D36	TXB1D35	TXB1D34	TXB1D33	TXB1D32	TXB1D31	TXB1D30	XXXX XXXX	35, 208
TXB1D3	TXB1D37	TXB1D36	TXB1D35	TXB1D34	TXB1D33	TXB1D32	TXB1D31	TXB1D30	XXXX XXXX	35, 208
TXB1D2	TXB1D27	TXB1D16	TXB1D25	TXB1D14	TXB1D23	TXB1D12	TXB1D21	TXB1D20		35, 208
TXB1D1	TXB1D17	TXB1D16	TXB1D15	TXB1D14	TXB1D13	TXB1D12	TXB1D11	TXB1D10	XXXX XXXX	35, 208
TXB1DLC		TXRTR	1701000		DLC3	DLC2	DLC1	DLC0	XXXX XXXX	35, 209
	EID7		EIDE	EID4	EID3				-x xxxx	-
TXB1EIDL	EID7	EID6	EID5	EID4		EID2	EID1	EID0	XXXX XXXX	35, 208
TXB1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	XXXX XXXX	35, 207
TXB1SIDL	SID2	SID1	SID0	- 0.07	EXIDE	CIDE	EID17	EID16	xxx- x-xx	35, 207
TXB1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	XXXX XXXX	35, 207
TXB1CON	_	TXABT	TXLARB	TXERR	TXREQ		TXPRI1	TXPRI0	0000 0000	35, 206

Legend:

x = unknown, u = unchanged, - = unimplemented, q = value depends on condition These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's. Note 1:

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.
3: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

TABLE 4-2: REGISTER FILE SUMMARY (CONTINUED)

TABLE 4-2				ANT (CON		,			Value on	Details on
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Page:
CANSTATRO4	OPMODE2	OPMODE1	OPMODE0	I	ICODE2	ICODE1	ICODE0	ı	xxx- xxx-	33, 202
TXB2D7	TXB2D77	TXB2D76	TXB2D75	TXB2D74	TXB2D73	TXB2D72	TXB2D71	TXB2D70	xxxx xxxx	35, 208
TXB2D6	TXB2D67	TXB2D66	TXB2D65	TXB2D64	TXB2D63	TXB2D62	TXB2D61	TXB2D60	xxxx xxxx	35, 208
TXB2D5	TXB2D57	TXB2D56	TXB2D55	TXB2D54	TXB2D53	TXB2D52	TXB2D51	TXB2D50	xxxx xxxx	35, 208
TXB2D4	TXB2D47	TXB2D46	TXB2D45	TXB2D44	TXB2D43	TXB2D42	TXB2D41	TXB2D40	xxxx xxxx	35, 208
TXB2D3	TXB2D37	TXB2D36	TXB2D35	TXB2D34	TXB2D33	TXB2D32	TXB2D31	TXB2D30	xxxx xxxx	35, 208
TXB2D2	TXB2D27	TXB2D26	TXB2D25	TXB2D24	TXB2D23	TXB2D22	TXB2D21	TXB2D20	xxxx xxxx	35, 208
TXB2D1	TXB2D17	TXB2D16	TXB2D15	TXB2D14	TXB2D13	TXB2D12	TXB2D11	TXB2D10	xxxx xxxx	35, 208
TXB2D0	TXB2D07	TXB2D06	TXB2D05	TXB2D04	TXB2D03	TXB2D02	TXB2D01	TXB2D00	xxxx xxxx	35, 208
TXB2DLC	_	TXRTR	_	-	DLC3	DLC2	DLC1	DLC0	-x xxxx	35, 209
TXB2EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	35, 208
TXB2EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	35, 207
TXB2SIDL	SID2	SID1	SID0	-	EXIDE	-	EID17	EID16	xxx- x-xx	35, 207
TXB2SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	35, 207
TXB2CON	_	TXABT	TXLARB	TXERR	TXREQ	-	TXPRI1	TXPRI0	-000 0-00	35, 206
RXM1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	35, 217
RXM1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	35, 217
RXM1SIDL	SID2	SID1	SID0	-	-	-	EID17	EID16	xxxxx	36, 217
RXM1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 216
RXM0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 217
RXM0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 217
RXM0SIDL	SID2	SID1	SID0	-	-	-	EID17	EID16	xxxxx	36, 217
RXM0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 216
RXF5EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF5EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF5SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF5SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF4EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF4EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF4SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF4SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF3EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF3EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF3SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF3SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF2EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF2EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF2SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF2SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF1SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF0SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215

 $\textbf{Legend:} \qquad x = \text{unknown, } u = \text{unchanged, -= unimplemented, } q = \text{value depends on condition}$ 

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

<sup>2:</sup> Bit 21 of the TBLPTRU allows access to the device configuration bits.

<sup>3:</sup> RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

#### 4.10 Access Bank

The Access Bank is an architectural enhancement that is very useful for C compiler code optimization. The techniques used by the C compiler are also useful for programs written in assembly.

This data memory region can be used for:

- · Intermediate computational values
- · Local variables of subroutines
- Faster context saving/switching of variables
- · Common variables
- Faster evaluation/control of SFRs (no banking)

The Access Bank is comprised of the upper 160 bytes in Bank 15 (SFRs) and the lower 96 bytes in Bank 0. These two sections will be referred to as Access Bank High and Access Bank Low, respectively. Figure 4-6 indicates the Access Bank areas.

A bit in the instruction word specifies if the operation is to occur in the bank specified by the BSR register or in the Access Bank.

When forced in the Access Bank (a = 0), the last address in Access Bank Low is followed by the first address in Access Bank High. Access Bank High maps most of the Special Function Registers so that these registers can be accessed without any software overhead.

## 4.11 Bank Select Register (BSR)

The need for a large general purpose memory space dictates a RAM banking scheme. The data memory is partitioned into sixteen banks. When using direct addressing, the BSR should be configured for the desired bank.

BSR<3:0> holds the upper 4 bits of the 12-bit RAM address. The BSR<7:4> bits will always read '0's and writes will have no effect.

A MOVLB instruction has been provided in the instruction set to assist in selecting banks.


If the currently selected bank is not implemented, any read will return all '0's and all writes are ignored. The Status register bits will be set/cleared as appropriate for the instruction performed.

Each Bank extends up to FFh (256 bytes). All data memory is implemented as static RAM.

A MOVFF instruction ignores the BSR since the 12-bit addresses are embedded into the instruction word.

Section 4.12 "Indirect Addressing, INDF and FSR Registers" provides a description of indirect addressing, which allows linear addressing of the entire RAM space.

## FIGURE 4-7: DIRECT ADDRESSING



- Note 1: For register file map detail, see Table 4-1.
  - 2: The access bit of the instruction can be used to force an override of the selected bank (BSR<3:0>) to the registers of the Access Bank.
  - 3: The MOVFF instruction embeds the entire 12-bit address in the instruction.

# 4.12 Indirect Addressing, INDF and FSR Registers

Indirect addressing is a mode of addressing data memory where the data memory address in the instruction is not fixed. A SFR register is used as a pointer to the data memory location that is to be read or written. Since this pointer is in RAM, the contents can be modified by the program. This can be useful for data tables in the data memory and for software stacks. Figure 4-8 shows the operation of indirect addressing. This shows the moving of the value to the data memory address specified by the value of the FSR register.

Indirect addressing is possible by using one of the INDF registers. Any instruction using the INDF register actually accesses the register indicated by the File Select Register, FSR. Reading the INDF register itself, indirectly (FSR = 0), will read 00h. Writing to the INDF register indirectly, results in a no operation. The FSR register contains a 12-bit address which is shown in Figure 4-8.

The INDFn  $(0 \le n \le 2)$  register is not a physical register. Addressing INDFn actually addresses the register whose address is contained in the FSRn register (FSRn is a pointer). This is indirect addressing.

Example 4-5 shows a simple use of indirect addressing to clear the RAM in Bank 1 (locations 100h-1FFh) in a minimum number of instructions.

# EXAMPLE 4-5: HOW TO CLEAR RAM (BANK 1) USING INDIRECT ADDRESSING

	LFSR	FSR0, 100h	;	
NEXT	CLRF	POSTINC0	;	Clear INDF
			;	register
			;	& inc pointer
	BTFSS	FSROH, 1	;	All done
			;	w/ Bank1?
	BRA	NEXT	;	NO, clear next
CONTINU	E		;	
:			;	YES, continue

There are three indirect addressing registers. To address the entire data memory space (4096 bytes), these registers are 12 bits wide. To store the 12 bits of addressing information, two 8-bit registers are required. These indirect addressing registers are:

- 1. FSR0: composed of FSR0H:FSR0L
- FSR1: composed of FSR1H:FSR1L
- 3. FSR2: composed of FSR2H:FSR2L

In addition, there are registers INDF0, INDF1 and INDF2, which are not physically implemented. Reading or writing to these registers activates indirect addressing, with the value in the corresponding FSR register being the address of the data.

If an instruction writes a value to INDF0, the value will be written to the address indicated by FSR0H:FSR0L. A read from INDF1 reads the data from the address indicated by FSR1H:FSR1L. INDFn can be used in code anywhere an operand can be used.

If INDF0, INDF1 or INDF2 are read indirectly via an FSR, all '0's are read (zero bit is set). Similarly, if INDF0, INDF1 or INDF2 are written to indirectly, the operation will be equivalent to a NOP instruction and the Status bits are not affected.

# 4.12.1 INDIRECT ADDRESSING OPERATION

Each FSR register has an INDF register associated with it, plus four additional register addresses. Performing an operation on one of these five registers determines how the FSR will be modified during indirect addressing.

- When data access is done to one of the five INDFn locations, the address selected will configure the FSRn register to:
  - Do nothing to FSRn after an indirect access (no change) – INDFn
  - Auto-decrement FSRn after an indirect access (post-decrement) POSTDECn
  - Auto-increment FSRn after an indirect access (post-increment) – POSTINCn
  - Auto-increment FSRn before an indirect access (pre-increment) PREINCn
  - Use the value in the WREG register as an offset to FSRn. Do not modify the value of the WREG or the FSRn register after an indirect access (no change) – PLUSWn

When using the auto-increment or auto-decrement features, the effect on the FSR is not reflected in the Status register. For example, if the indirect address causes the FSR to equal '0', the Z bit will not be set.

Incrementing or decrementing an FSR affects all 12 bits. That is, when FSRnL overflows from an increment, FSRnH will be incremented automatically.


Adding these features allows the FSRn to be used as a software stack pointer in addition to its uses for table operations in data memory.

Each FSR has an address associated with it that performs an indexed indirect access. When a data access to this INDFn location (PLUSWn) occurs, the FSRn is configured to add the 2's complement value in the WREG register and the value in FSR to form the address before an indirect access. The FSR value is not changed.

If an FSR register contains a value that indicates one of the INDFn, an indirect read will read 00h (zero bit is set), while an indirect write will be equivalent to a NOP (Status bits are not affected).

If an indirect addressing operation is done where the target address is an FSRnH or FSRnL register, the write operation will dominate over the pre- or post-increment/decrement functions.

## FIGURE 4-8: INDIRECT ADDRESSING



## 4.13 Status Register

The Status register, shown in Register 4-2, contains the arithmetic status of the ALU. The Status register can be the destination for any instruction, as with any other register. If the Status register is the destination for an instruction that affects the Z, DC, C, OV or N bits, then the write to these five bits is disabled. These bits are set or cleared according to the device logic. Therefore, the result of an instruction with the Status register as destination may be different than intended.

For example, CLRF STATUS will clear the upper three bits and set the Z bit. This leaves the Status register as 000 $\mu$  uluu (where  $\mu$  = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the Status register, because these instructions do not affect the Z, C, DC, OV or N bits from the Status register. For other instructions which do not affect the status bits, see Table 25-2.

Note: The C and DC bits operate as a Borrow and Digit Borrow bit respectively, in subtraction.

#### **REGISTER 4-2: STATUS REGISTER**

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
_	_	_	N	OV	Z	DC	С
hit 7							hit 0

## bit 7-5 Unimplemented: Read as '0'

## bit 4 N: Negative bit

This bit is used for signed arithmetic (2's complement). It indicates whether the result of the ALU operation was negative (ALU MSb = 1).

- 1 = Result was negative
- 0 = Result was positive

#### bit 3 **OV:** Overflow bit

This bit is used for signed arithmetic (2's complement). It indicates an overflow of the 7-bit magnitude which causes the sign bit (bit 7) to change state.

- 1 = Overflow occurred for signed arithmetic (in this arithmetic operation)
- 0 = No overflow occurred
- bit 2 Z: Zero bit
  - 1 = The result of an arithmetic or logic operation is zero
  - 0 = The result of an arithmetic or logic operation is not zero

## bit 1 **DC:** Digit Carry/Borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the 4th low-order bit of the result occurred
- 0 = No carry-out from the 4th low-order bit of the result

con

For Borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRCF, RRNCF, RLCF and RLNCF) instructions, this bit is loaded with either bit 4 or bit 3 of the source register.

### bit 0 C: Carry/Borrow bit

Note:

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the Most Significant bit of the result occurred
- 0 = No carry-out from the Most Significant bit of the result occurred

Note:

For Borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low-order bit of the source register.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented b	oit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## 4.14 RCON Register

The Reset Control (RCON) register contains flag bits that allow differentiation between the sources of a device Reset. These flags include the TO, PD, POR, BOR and RI bits. This register is readable and writable.

Note 1: If the BOREN configuration bit is set,

BOR is '1' on Power-on Reset. If the

BOREN configuration bit is clear, BOR is

unknown on Power-on Reset.

The BOR status bit is a "don't care" and is not necessarily predictable if the brown-out circuit is disabled (the BOREN configuration bit is clear). BOR must then be set by the user and checked on subsequent Resets to see if it is clear, indicating a brown-out has occurred.

2: It is recommended that the POR bit be set after a Power-on Reset has been detected, so that subsequent Power-on Resets may be detected.

### REGISTER 4-3: RCON: RESET CONTROL REGISTER

R/W-0	U-0	U-0	R/W-1	R/W	R/W	R/W-0	R/W-0
IPEN	_	_	RI	TO	PD	POR	BOR
bit 7							bit 0

- bit 7 IPEN: Interrupt Priority Enable bit
  - 1 = Enable priority levels on interrupts
  - 0 = Disable priority levels on interrupts (PIC16CXXX Compatibility mode)
- bit 6-5 Unimplemented: Read as '0'
- bit 4 RI: RESET Instruction Flag bit
  - 1 = The RESET instruction was not executed
  - 0 = The RESET instruction was executed causing a device Reset (must be set in software after a Brown-out Reset occurs)
- bit 3 TO: Watchdog Time-out Flag bit
  - 1 = After power-up, CLRWDT instruction or SLEEP instruction
  - 0 = A WDT time-out occurred
- bit 2 **PD:** Power-down Detection Flag bit
  - 1 = After power-up or by the CLRWDT instruction
  - 0 = By execution of the SLEEP instruction
- bit 1 POR: Power-on Reset Status bit
  - 1 = A Power-on Reset has not occurred
  - 0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)
- bit 0 BOR: Brown-out Reset Status bit
  - 1 = A Brown-out Reset has not occurred
  - 0 = A Brown-out Reset occurred (must be set in software after a Brown-out Reset occurs)

Legend	ŀ
Legeniu	١.

R = Readable bit	t = Readable bit W = Writable bit		bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## 5.0 DATA EEPROM MEMORY

The data EEPROM is readable and writable during normal operation over the entire VDD range. The data memory is not directly mapped in the register file space. Instead, it is indirectly addressed through the Special Function Registers (SFR).

There are four SFRs used to read and write the program and data EEPROM memory. These registers are:

- EECON1
- EECON2
- EEDATA
- EEADR

The EEPROM data memory allows byte read and write. When interfacing to the data memory block, EEDATA holds the 8-bit data for read/write and EEADR holds the address of the EEPROM location being accessed. The PIC18FXX8 devices have 256 bytes of data EEPROM with an address range from 00h to FFh.

The EEPROM data memory is rated for high erase/write cycles. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an on-chip timer. The write time will vary with voltage and temperature, as well as from chip-to-chip. Please refer to the specifications for exact limits.

## 5.1 EEADR Register

The address register can address up to a maximum of 256 bytes of data EEPROM.

## 5.2 EECON1 and EECON2 Registers

EECON1 is the control register for EEPROM memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the EEPROM write sequence.

Control bits,  $\overline{\text{RD}}$  and  $\overline{\text{WR}}$ , initiate read and write operations, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the  $\overline{\text{WR}}$  bit in software prevents the accidental or premature termination of a write operation.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset, or a WDT Time-out Reset, during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to the Reset condition forcing the contents of the registers to zero.

**Note:** Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be cleared in software.

## www.DataPIC18FXX8

#### REGISTER 5-1: EECON1: EEPROM CONTROL REGISTER 1

R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0
EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD
bit 7		•			•	•	bit 0

bit 7 **EEPGD:** Flash Program or Data EEPROM Memory Select bit

1 = Access program Flash memory

0 = Access data EEPROM memory

bit 6 CFGS: Flash Program/Data EE or Configuration Select bit

1 = Access Configuration registers

0 = Access program Flash or data EEPROM memory

bit 5 **Unimplemented:** Read as '0'

bit 4 FREE: Flash Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next  $\overline{WR}$  command (reset by hardware)

0 = Perform write only

bit 3 WRERR: Write Error Flag bit

1 = A write operation is prematurely terminated (any MCLR or any WDT Reset during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD or FREE bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: Write Enable bit

1 = Allows write cycles

0 = Inhibits write to the EEPROM or Flash memory

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read

(Read takes one cycle.  $\overline{RD}$  is cleared in hardware. The  $\overline{RD}$  bit can only be set (not cleared) in software.  $\overline{RD}$  bit cannot be set when  $\overline{EEPGD} = 1$ .)

0 = Does not initiate an EEPROM read

Legend:

R = Readable bit W = Writable bit S = Settable bit U = Unimplemented bit, read as '0'

-n =Value at POR '1' = Bit is set '0' = Bit is cleared x =Bit is unknown

# 5.3 Reading the Data EEPROM Memory

To read a data memory location, the user must write the address to the EEADR register, clear the EEPGD and CFGS control bits (EECON1<7:6>) and then set control bit  $\overline{\text{RD}}$  (EECON1<0>). The data is available in the very next instruction cycle of the EEDATA register; therefore, it can be read by the next instruction. EEDATA will hold this value until another read operation or until it is written to by the user (during a write operation).

#### **EXAMPLE 5-1: DATA EEPROM READ**

```
MOVLW
       DATA EE ADDR
MOVWF
       EEADR
                      ;Data Memory Address
                      :to read
BCF
       EECON1, EEPGD ; Point to DATA memory
       EECON1, CFGS ;
BCS
       EECON1, RD
                    ;EEPROM Read
BSF
MOVF
       EEDATA, W
                      ;W = EEDATA
```

# 5.4 Writing to the Data EEPROM Memory

To write an EEPROM data location, the address must first be written to the EEADR register and the data written to the EEDATA register. Then, the sequence in Example 5-2 must be followed to initiate the write cycle.

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write 0AAh to EECON2, then set  $\overline{\text{WR}}$  bit) for each byte. It is strongly recommended that interrupts be disabled during this code segment.

Additionally, the WREN bit in EECON1 must be set to enable writes. This mechanism prevents accidental writes to data EEPROM due to unexpected code execution (i.e., runaway programs). The WREN bit should be kept clear at all times, except when updating the EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit will not affect the current write cycle. The  $\overline{WR}$  bit will be inhibited from being set unless the WREN bit is set. The  $\overline{WREN}$  bit must be set on a previous instruction. Both  $\overline{WR}$  and  $\overline{WREN}$  cannot be set with the same instruction.

At the completion of the write cycle, the  $\overline{\text{WR}}$  bit is cleared in hardware and the EEPROM Write Complete Interrupt Flag bit (EEIF) is set. The user may either enable this interrupt or roll this bit. EEIF must be cleared by software.

## **EXAMPLE 5-2: DATA EEPROM WRITE**

```
MOVLW
                  DATA EE ADDR
           MOVWF
                EEADR
                                 ; Data Memory Address to read
           MOVLW DATA EE DATA
           MOVWF EEDATA
                                ; Data Memory Value to write
                  EECON1, EEPGD ; Point to DATA memory
           BCF
           BCF
                  EECON1, CFGS
                                ; Access program FLASH or Data EEPROM memory
           BSF
                  EECON1, WREN
                                 ; Enable writes
                  INTCON, GIE
           BCF
                                 ; Disable interrupts
Required
           MOVLW
                 55h
           MOVWF EECON2
                                 ; Write 55h
Sequence
           MOVLW 0AAh
                                 ; Write AAh
           MOVWF
                  EECON2
           BSF
                  EECON1, WR
                                ; Set WR bit to begin write
                  INTCON, GIE
           BSF
                                 ; Enable interrupts
                                 : user code execution
           BCF
                  EECON1, WREN
                                 ; Disable writes on write complete (EEIF set)
```

## 5.5 Write Verify

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

Generally, a write failure will be a bit which was written as a '1', but reads back as a '0' (due to leakage off the cell).

## 5.6 Protection Against Spurious Write

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, the WREN bit is cleared. Also, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together reduce the probability of an accidental write during brown-out, power glitch or software malfunction.

## 5.7 Operation During Code-Protect

Data EEPROM memory has its own code-protect mechanism. External read and write operations are disabled if either of these mechanisms are enabled.

The microcontroller itself can both read and write to the internal data EEPROM, regardless of the state of the code-protect configuration bit. Refer to Section 24.0 "Special Features of the CPU" for additional information.

## 5.8 Using the Data EEPROM

The data EEPROM is a high-endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specification D124 or D124A. If this is not the case, an array refresh must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory. A simple data EEPROM refresh routine is shown in Example 5-3.

**Note:** If data EEPROM is only used to store constants and/or data that changes rarely, an array refresh is likely not required. See specification D124 or D124A.

#### **EXAMPLE 5-3: DATA EEPROM REFRESH ROUTINE**

```
; Start at address 0
      CLRF
               EEADR
      BCF
               EECON1, CFGS
                                  ; Set for memory
      BCF
               EECON1, EEPGD
                                  ; Set for Data EEPROM
      BCF
               INTCON, GIE
                                  ; Disable interrupts
               EECON1, WREN
      BSF
                                   ; Enable writes
                                   ; Loop to refresh array
Loop
      BSF
               EECON1, RD
                                   ; Read current address
      MOVLW
               55h
      MOVWF
               EECON2
                                  ; Write 55h
      MOVLW
               0AAh
                                  ; Write AAh
      MOVWF
               EECON2
                                  ; Set WR bit to begin write
      BSF
               EECON1, WR
      BTFSC
               EECON1, WR
                                   ; Wait for write to complete
      BRA
               $-2
      TNCFS7
               EEADR. F
                                   : Increment address
      BRA
               Loop
                                   ; Not zero, do it again
      BCF
               EECON1, WREN
                                   ; Disable writes
      BSF
               INTCON, GIE
                                   ; Enable interrupts
```

TABLE 5-1: REGISTERS ASSOCIATED WITH DATA EEPROM MEMORY

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
EEADR	EEPROM Address Register							xxxx xxxx	uuuu uuuu	
EEDATA	EEPROM Data Register						xxxx xxxx	uuuu uuuu		
EECON2	2 EEPROM Control Register 2 (not a physical register)							_	_	
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	uu-0 u000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP <sup>(1)</sup>	-1-1 1111	-1-1 1111
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>	-0-0 0000	-0-0 0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>	-0-0 0000	-0-0 0000

**Legend:** x = unknown, u = unchanged, r = reserved, - = unimplemented, read as '0'. Shaded cells are not used during Flash/EEPROM access.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

# www.DataPIC18FXX8

NOTES:

## 6.0 FLASH PROGRAM MEMORY

The Flash program memory is readable, writable and erasable during normal operation over the entire VDD range.

A read from program memory is executed on one byte at a time. A write to program memory is executed on blocks of 8 bytes at a time. Program memory is erased in blocks of 64 bytes at a time. A bulk erase operation may not be issued from user code.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, therefore, code cannot execute. An internal programming timer terminates program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

#### 6.1 Table Reads and Table Writes

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:


- Table Read (TBLRD)
- Table Write (TBLWT)

The program memory space is 16 bits wide, while the data RAM space is 8 bits wide. Table reads and table writes move data between these two memory spaces through an 8-bit register (TABLAT).


Table read operations retrieve data from program memory and place it into the data RAM space. Figure 6-1 shows the operation of a table read with program memory and data RAM.

Table write operations store data from the data memory space into holding registers in program memory. The procedure to write the contents of the holding registers into program memory is detailed in **Section 6.5** "Writing to Flash Program Memory". Figure 6-2 shows the operation of a table write with program memory and data RAM.

Table operations work with byte entities. A table block containing data, rather than program instructions, is not required to be word aligned. Therefore, a table block can start and end at any byte address. If a table write is being used to write executable code into program memory, program instructions will need to be word aligned.



#### FIGURE 6-2: TABLE WRITE OPERATION



Note 1: Table Pointer actually points to one of eight holding registers, the address of which is determined by TBLPTRL<2:0>.

The process for physically writing data to the program memory array is discussed in Section 6.5 "Writing to Flash Program Memory".

## 6.2 Control Registers

Several control registers are used in conjunction with the TBLRD and TBLWT instructions. These include the:

- EECON1 register
- · EECON2 register
- TABLAT register
- TBLPTR registers

#### 6.2.1 EECON1 AND EECON2 REGISTERS

EECON1 is the control register for memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the memory write and erase sequences.

Control bit EEPGD determines if the access will be a program or data EEPROM memory access. When clear, any subsequent operations will operate on the data EEPROM memory. When set, any subsequent operations will operate on the program memory.

Control bit CFGS determines if the access will be to the Configuration/Calibration registers or to program memory/data EEPROM memory. When set, subsequent operations will operate on Configuration registers regardless of EEPGD (see Section 24.0 "Special Features of the CPU"). When clear, memory selection access is determined by EEPGD.

The FREE bit, when set, will allow a program memory erase operation. When the FREE bit is set, the erase operation is initiated on the next WR command. When FREE is clear, only writes are enabled.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to Reset values of zero.

Control bits,  $\overline{\text{RD}}$  and  $\overline{\text{WR}}$ , initiate read and write operations, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the  $\overline{\text{WR}}$  bit in software prevents the accidental or premature termination of a write operation. The  $\overline{\text{RD}}$  bit cannot be set when accessing program memory (EEPGD = 1).

**Note:** Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be cleared in software.

### REGISTER 6-1: EECON1: EEPROM CONTROL REGISTER 1

R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0
EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD

bit 7

bit 7 **EEPGD:** Flash Program or Data EEPROM Memory Select bit

1 = Access program Flash memory

0 = Access data EEPROM memory

bit 6 CFGS: Flash Program/Data EE or Configuration Select bit

1 = Access Configuration registers

0 = Access program Flash or data EEPROM memory

bit 5 Unimplemented: Read as '0'

bit 4 FREE: Flash Row Erase Enable bit

1 = Erase the program memory row addressed by TBLPTR on the next  $\overline{\text{WR}}$  command (cleared by completion of erase operation)

0 = Perform write only

bit 3 WRERR: Write Error Flag bit

1 = A write operation is prematurely terminated (any  $\overline{\text{MCLR}}$  or any WDT Reset during self-timed programming in normal operation)

0 = The write operation completed

**Note:** When a WRERR occurs, the EEPGD and CFGS bits are not cleared. This allows tracing of the error condition.

bit 2 WREN: Write Enable bit

1 = Allows write cycles

0 = Inhibits write to the EEPROM or Flash memory

bit 1 WR: Write Control bit

1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)

0 = Write cycle to the EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read

(Read takes one cycle.  $\overline{RD}$  is cleared in hardware. The  $\overline{RD}$  bit can only be set (not cleared) in software.  $\overline{RD}$  bit cannot be set when  $\overline{EEPGD} = 1$ .)

0 = Does not initiate an EEPROM read

## Legend:

 $R = Readable \ bit$   $W = Writable \ bit$   $S = Settable \ bit$   $U = Unimplemented \ bit$ , read as '0'  $-n = Value \ at \ POR$  '1' = Bit is set '0' = Bit is cleared  $x = Bit \ is \ unknown$ 

## 6.2.2 TABLAT – TABLE LATCH REGISTER

The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch is used to hold 8-bit data during data transfers between program memory and data RAM.

# 6.2.3 TBLPTR – TABLE POINTER REGISTER

The Table Pointer (TBLPTR) addresses a byte within the program memory. The TBLPTR is comprised of three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer. The low-order 21 bits allow the device to address up to 2 Mbytes of program memory space. The 22nd bit allows access to the device ID, the user ID and the configuration bits.

The Table Pointer, TBLPTR, is used by the TBLRD and TBLWT instructions. These instructions can update the TBLPTR in one of four ways based on the table operation. These operations are shown in Table 6-1. These operations on the TBLPTR only affect the low-order 21 bits.

## 6.2.4 TABLE POINTER BOUNDARIES

TBLPTR is used in reads, writes and erases of the Flash program memory.

When a TBLRD is executed, all 22 bits of the Table Pointer determine which byte is read from program memory into TABLAT.

When a TBLWT is executed, the three LSbs of the Table Pointer (TBLPTR<2:0>) determine which of the eight program memory holding registers is written to. When the timed write to program memory (long write) begins, the 19 MSbs of the Table Pointer, TBLPTR (TBLPTR<21:3>), will determine which program memory block of 8 bytes is written to. For more detail, see Section 6.5 "Writing to Flash Program Memory".


When an erase of program memory is executed, the 16 MSbs of the Table Pointer (TBLPTR<21:6>) point to the 64-byte block that will be erased. The Least Significant bits (TBLPTR<5:0>) are ignored.

Figure 6-3 describes the relevant boundaries of TBLPTR based on Flash program memory operations.

TABLE 6-1:	TABLE POINTER OPERATIONS WITH TBLRD AND TBLWT INSTRUCTIONS
IADEL U-I.	TABLE FOUNTER OF ENATIONS WITH THEIR AND THEW I MISTINGUING

Example	Operation on Table Pointer
TBLRD* TBLWT*	TBLPTR is not modified
TBLRD*+ TBLWT*+	TBLPTR is incremented after the read/write
TBLRD*- TBLWT*-	TBLPTR is decremented after the read/write
TBLRD+* TBLWT+*	TBLPTR is incremented before the read/write

## FIGURE 6-3: TABLE POINTER BOUNDARIES BASED ON OPERATION




# 6.3 Reading the Flash Program Memory

The TBLRD instruction is used to retrieve data from program memory and places it into data RAM. Table reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next table read operation.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. Figure 6-4 shows the interface between the internal program memory and the TABLAT.

FIGURE 6-4: READS FROM FLASH PROGRAM MEMORY



## EXAMPLE 6-1: READING A FLASH PROGRAM MEMORY WORD

```
MOVLW
                   CODE ADDR UPPER
                                              ; Load TBLPTR with the base
           MOVWF
                   TBLPTRU
                                              ; address of the word
           MOVLW
                   CODE ADDR HIGH
           MOVWF
                   TBLPTRH
                  CODE_ADDR_LOW
           MOVLW
           MOVWF
                   TBLPTRL
READ WORD
           TBLRD*+
                                              ; read into TABLAT and increment
           MOVF
                   TABLAT, W
                                              ; get data
           MOVWF
                  WORD LSB
           TBLRD*+
                                              ; read into TABLAT and increment
           MOVF
                   TABLAT, W
                                              ; get data
           MOVWF
                  WORD_MSB
```

## 6.4 Erasing Flash Program Memory

The minimum erase block is 32 words or 64 bytes. Only through the use of an external programmer, or through ICSP control, can larger blocks of program memory be bulk erased. Word erase in the Flash array is not supported.

When initiating an erase sequence from the micro-controller itself, a block of 64 bytes of program memory is erased. The Most Significant 16 bits of the TBLPTR<21:6> point to the block being erased. TBLPTR<5:0> are ignored.

The EECON1 register commands the erase operation. The EEPGD bit must be set to point to the Flash program memory. The WREN bit must be set to enable write operations. The FREE bit is set to select an erase operation.

For protection, the write initiate sequence for EECON2 must be used.

A long write is necessary for erasing the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

## 6.4.1 FLASH PROGRAM MEMORY ERASE SEQUENCE

The sequence of events for erasing a block of internal program memory location is:

- Load Table Pointer with address of row being erased.
- 2. Set the EECON1 register for the erase operation:
  - set the EEPGD bit to point to program memory;
  - clear the CFGS bit to access program memory;
  - · set the WREN bit to enable writes:
  - · set the FREE bit to enable the erase.
- 3. Disable interrupts.
- 4. Write 55h to EECON2.
- 5. Write 0AAh to EECON2.
- Set the WR bit. This will begin the row erase cycle.
- 7. The CPU will stall for duration of the erase (about 2 ms using internal timer).
- 8. Re-enable interrupts.

## **EXAMPLE 6-2: ERASING A FLASH PROGRAM MEMORY ROW**

```
MOVT.W
                      upper (CODE ADDR)
                                             ; load TBLPTR with the base
               MOVWF
                      TBLPTRU
                                             ; address of the memory block
               MOVLW
                      high (CODE ADDR)
               MOVWF
                      TBLPTRH
                      low (CODE ADDR)
               MOVLW
               MOVWF
                      TBLPTRL
   ERASE ROW
                      EECON1, EEPGD
               BSF
                                            ; point to FLASH program memory
               BCF
                      EECON1, CFGS
                                            ; access FLASH program memory
                                            ; enable write to memory
               BSF
                      EECON1, WREN
               BSF
                      EECON1, FREE
                                             ; enable Row Erase operation
               BCF
                      INTCON, GIE
                                             ; disable interrupts
               MOVLW 55h
               MOVWF EECON2
                                             ; write 55H
Required
               MOVLW 0AAh
Sequence
               MOVWF EECON2
                                             ; write OAAH
               BSF
                      EECON1, WR
                                             ; start erase (CPU stall)
               NOP
                                             ; NOP needed for proper code execution
               BSF
                      INTCON, GIE
                                             ; re-enable interrupts
```

#### 6.5 Writing to Flash Program Memory

The minimum programming block is 4 words or 8 bytes. Word or byte programming is not supported.

Table writes are used internally to load the holding registers needed to program the Flash memory. There are 8 holding registers used by the table writes for programming.

Since the Table Latch (TABLAT) is only a single byte, the TBLWT instruction has to be executed 8 times for each programming operation. All of the table write operations will essentially be short writes, because only the holding registers are written. At the end of updating 8 registers, the EECON1 register must be written to, to start the programming operation with a long write.

The long write is necessary for programming the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

The EEPROM on-chip timer controls the write time. The write/erase voltages are generated by an on-chip charge pump rated to operate over the voltage range of the device for byte or word operations.

## 6.5.1 FLASH PROGRAM MEMORY WRITE SEQUENCE


The sequence of events for programming an internal program memory location should be:

- 1. Read 64 bytes into RAM.
- 2. Update data values in RAM as necessary.
- 3. Load Table Pointer with address being erased.
- 4. Do the row erase procedure.
- 5. Load Table Pointer with address of first byte being written.
- Write the first 8 bytes into the holding registers using the TBLWT instruction, auto-increment may be used.
- 7. Set the EECON1 register for the write operation:
  - set the EEPGD bit to point to program memory;
  - · clear the CFGS bit to access program memory;
  - · set the WREN to enable byte writes.
- 8. Disable interrupts.
- 9. Write 55h to EECON2.
- 10. Write AAh to EECON2.
- 11. Set the WR bit. This will begin the write cycle.
- 12. The CPU will stall for duration of the write (about 2 ms using internal timer).
- 13. Re-enable interrupts.
- 14. Repeat steps 6-14 seven times to write 64 bytes.
- 15. Verify the memory (table read).

This procedure will require about 18 ms to update one row of 64 bytes of memory. An example of the required code is given in Example 6-3.

Note: Before setting the WR bit, the Table Pointer address needs to be within the intended address range of the 8 bytes in the holding registers.

FIGURE 6-5: TABLE WRITES TO FLASH PROGRAM MEMORY



#### **EXAMPLE 6-3: WRITING TO FLASH PROGRAM MEMORY**

```
MOVLW
                                               ; number of bytes in erase block
              MOVWF COUNTER
              MOVLW high (BUFFER ADDR)
                                               ; point to buffer
              MOVWF FSR0H
              MOVLW low (BUFFER ADDR)
              MOVWF FSR0L
              MOVLW
                    upper (CODE ADDR)
                                              ; Load TBLPTR with the base
                     TBLPTRU
                                              ; address of the memory block
              MOVWF
              MOVLW
                     high (CODE_ADDR)
                     TBLPTRH
              MOVWF
              MOVLW low (CODE_ADDR)
              MOVWF TBLPTRL
READ_BLOCK
              TBLRD*+
                                              ; read into TABLAT, and inc
              MOVF TABLAT, W
                                              ; get data
                                              ; store data
              MOVWF POSTINCO
              DECFSZ COUNTER
                                              ; done?
                     READ BLOCK
                                              ; repeat
MODIFY_WORD
              MOVLW DATA ADDR HIGH
                                              ; point to buffer
              MOVWF FSR0H
              MOVLW DATA_ADDR_LOW
              MOVWF FSR0L
              MOVLW NEW_DATA_LOW
                                             ; update buffer word
              MOVWF POSTINCO
              MOVLW NEW_DATA_HIGH
              MOVWF
                     INDF0
ERASE_BLOCK
              MOVLW upper (CODE ADDR)
                                              ; load TBLPTR with the base
              MOVWF
                     TBLPTRU
                                              ; address of the memory block
              MOVLW high (CODE_ADDR)
              MOVWF TBLPTRH
              MOVLW low (CODE_ADDR)
              MOVWF TBLPTRL
                     EECON1, EEPGD
                                             ; point to FLASH program memory
              BSF
                                             ; access FLASH program memory
              BCF
                     EECON1, CFGS
                                              ; enable write to memory
              BSF
                     EECON1, WREN
                     EECON1, FREE
              BSF
                                              ; enable Row Erase operation
              BCF
                    INTCON, GIE
                                              ; disable interrupts
              MOVLW 55h
Required
              MOVWF EECON2
                                              ; write 55H
              MOVLW 0AAh
Sequence
              MOVWF EECON2
                                              ; write AAH
                     EECON1, WR
              BSF
                                               ; start erase (CPU stall)
              NOP
                                            ; re-enable interrupts
                     INTCON, GIE
              BSF
              TBLRD*-
                                              ; dummy read decrement
WRITE_BUFFER_BACK
              MOVLW 8
                                              ; number of write buffer groups of 8 bytes
              MOVWF
                     COUNTER HI
              MOVLW high (BUFFER ADDR)
                                              ; point to buffer
              MOVWF FSR0H
              MOVLW low (BUFFER ADDR)
              MOVWF FSR0L
PROGRAM LOOP
              MOVLW
                                               ; number of bytes in holding register
              MOVWF
                     COUNTER
WRITE WORD TO HREGS
              MOVFW POSTINCO, W
                                              ; get low byte of buffer data
              MOVWF TABLAT
                                              ; present data to table latch
              TBLWT+*
                                              ; write data, perform a short write
                                              ; to internal TBLWT holding register.
              DECFSZ COUNTER
                                               ; loop until buffers are full
              BRA WRITE WORD TO HREGS
```

#### **EXAMPLE 6-3: WRITING TO FLASH PROGRAM MEMORY (CONTINUED)**

```
WRITE WORD TO HREGS
               MOVFW
                      POSTINCO, W
                                                 ; get low byte of buffer data
               MOVWF TABLAT
                                                 ; present data to table latch
               TBLWT+*
                                                 ; write data, perform a short write
                                                 ; to internal TBLWT holding register.
               DECFSZ COUNTER
                                                 ; loop until buffers are full
               BRA
                      WRITE WORD TO HREGS
PROGRAM_MEMORY
                      EECON1, EEPGD
                                                 ; point to FLASH program memory
               BSF
                      EECON1, CFGS
               BCF
                                                ; access FLASH program memory
               BSF
                      EECON1, WREN
                                                ; enable write to memory
               BCF
                      INTCON, GIE
                                                 ; disable interrupts
               MOVIW
                     55h
                                                 ; write 55h
Required
               MOVWF
                      EECON2
Sequence
               MOVLW
                      0AAh
                                                 ; write OAAh
               MOVWF
                      EECON2
                                                 ; start program (CPU stall)
               BSF
                      EECON1, WR
               NOP
                      INTCON, GIE
                                                 ; re-enable interrupts
               BSF
               DECFSZ COUNTER HI
                                                 ; loop until done
               BRA
                      PROGRAM LOOP
                      EECON1, WREN
               BCF
                                                 ; disable write to memory
```

#### 6.5.2 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

## 6.5.3 UNEXPECTED TERMINATION OF WRITE OPERATION

If a write is terminated by an unplanned event, such as loss of power or an unexpected Reset, the memory location just programmed should be verified and reprogrammed if needed. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, users can check the WRERR bit and rewrite the location.

## 6.5.4 PROTECTION AGAINST SPURIOUS WRITES

To reduce the probability against spurious writes to Flash program memory, the write initiate sequence must also be followed. See Section 24.0 "Special Features of the CPU" for more detail.

## 6.6 Flash Program Operation During Code Protection

See Section 24.0 "Special Features of the CPU" for details on code protection of Flash program memory.

## www.DataPIC18FXX8

TABLE 6-2: REGISTERS ASSOCIATED WITH PROGRAM FLASH MEMORY

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other Resets
TBLPTRU	_	_	bit 21	bit 21 Program Memory Table Pointer Upper Byte (TBLPTR<20:16>)						00 0000
TBPLTRH	Program M	lemory Tab	le Pointer l	High Byte (1	TBLPTR<15	:8>)			0000 0000	0000 0000
TBLPTRL	Program Memory Table Pointer Low Byte (TBLPTR<7:0>)								0000 0000	0000 0000
TABLAT	Program M	lemory Tab	le Latch						0000 0000	0000 0000
INTCON	GIE/GIEH	PEIE/ GIEL	TMR0IE	INTE	RBIE	TMR0IF	INTF	RBIF	0000 000x	0000 000u
EECON2	EEPROM	Control Re	gister 2 (no	t a physical	register)				_	_
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	uu-0 u000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP <sup>(1)</sup>	-1-1 1111	-1-1 1111
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>	-0-0 0000	-0-0 0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>	-0-0 0000	-0-0 0000

 $\label{eq:local_local_local} \begin{tabular}{ll} $\mathbf{x}$ = unknown, $\mathbf{u}$ = unchanged, $-$ = unimplemented, read as `0'. \\ & Shaded cells are not used during Flash/EEPROM access. \\ \end{tabular}$ 

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

#### 7.0 8 x 8 HARDWARE MULTIPLIER

#### 7.1 Introduction

An 8 x 8 hardware multiplier is included in the ALU of the PIC18FXX8 devices. By making the multiply a hardware operation, it completes in a single instruction cycle. This is an unsigned multiply that gives a 16-bit result. The result is stored in the 16-bit product register pair (PRODH:PRODL). The multiplier does not affect any flags in the ALUSTA register.

Making the 8 x 8 multiplier execute in a single cycle gives the following advantages:

- · Higher computational throughput
- Reduces code size requirements for multiply algorithms

The performance increase allows the device to be used in applications previously reserved for Digital Signal Processors.

Table 7-1 shows a performance comparison between Enhanced devices using the single-cycle hardware multiply and performing the same function without the hardware multiply.

#### 7.2 Operation

Example 7-1 shows the sequence to do an 8 x 8 unsigned multiply. Only one instruction is required when one argument of the multiply is already loaded in the WREG register.

Example 7-2 shows the sequence to do an 8 x 8 signed multiply. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

## EXAMPLE 7-1: 8 x 8 UNSIGNED MULTIPLY ROUTINE

MOVF	ARG1, W	;
MULWF	ARG2	; ARG1 * ARG2 ->
		; PRODH:PRODL

## EXAMPLE 7-2: 8 x 8 SIGNED MULTIPLY ROUTINE

MOVF	ARG1,	W		
MULWF	ARG2		;	ARG1 * ARG2 ->
			;	PRODH: PRODL
BTFSC	ARG2,	SB	;	Test Sign Bit
SUBWF	PRODH		;	PRODH = PRODH
			;	- ARG1
MOVF	ARG2,	W		
BTFSC	ARG1,	SB	;	Test Sign Bit
SUBWF	PRODH		;	PRODH = PRODH
			;	- ARG2

#### TABLE 7-1: PERFORMANCE COMPARISON

		Program	Cycles		Time	
Routine	Multiply Method	Memory (Words)	(Max)	@ 40 MHz	@ 10 MHz	@ 4 MHz
9 v 9 unaigned	Without hardware multiply	13	69	6.9 μs	27.6 μs	69 μs
8 x 8 unsigned	Hardware multiply	1	1	100 ns	400 ns	1 μs
9 v 9 signed	Without hardware multiply	33	91	9.1 μs	36.4 μs	91 μs
8 x 8 signed	Hardware multiply	6	6	600 ns	2.4 μs	6 μs
16 v 16 unsigned	Without hardware multiply	21	242	24.2 μs	96.8 μs	242 μs
16 x 16 unsigned	Hardware multiply	24	24	2.4 μs	9.6 μs	24 μs
16 v 16 signed	Without hardware multiply	52	254	25.4 μs	102.6 μs	254 μs
16 x 16 signed	Hardware multiply	36	36	3.6 µs	14.4 μs	36 μs

Example 7-3 shows the sequence to do a 16 x 16 unsigned multiply. Equation 7-1 shows the algorithm that is used. The 32-bit result is stored in four registers, RES3:RES0.

# EQUATION 7-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0 = ARG1H:ARG1L • ARG2H:ARG2L

= (ARG1H • ARG2H • 2^{16}) + (ARG1H • ARG2L • 2^{8}) + (ARG1L • ARG2H • 2^{8}) + (ARG1L • ARG2L)
```

## EXAMPLE 7-3: 16 x 16 UNSIGNED MULTIPLY ROUTINE

```
ARG1L, W
MOVF
MULWF
       ARG2L
                    ; ARG1L * ARG2L ->
                    ; PRODH:PRODL
       PRODH, RES1
MOVFF
MOVFF
       PRODL, RESO
MOVF
       ARG1H, W
MULWF
       ARG2H
                   ; ARG1H * ARG2H ->
                   ; PRODH:PRODL
       PRODH, RES3 ;
MOVFF
MOVFF
       PRODL, RES2 ;
MOVF
       ARG1L, W
                    ; ARG1L * ARG2H ->
MULWF
       ARG2H
                    ; PRODH:PRODL
MOVF
       PRODL, W
                    ;
                   ; Add cross
ADDWF
       RES1
                   ; products
MOVF
       PRODH, W
ADDWFC RES2
CLRF
       WREG
ADDWFC RES3
MOVF
       ARG1H, W
                   ; ARG1H * ARG2L ->
MULWF
       ARG2L
                   ; PRODH:PRODL
MOVF
       PRODL, W
                   ; Add cross
MOVF
       PRODH, W ; products
ADDWFC RES2
CLRF
       WREG
ADDWFC RES3
                    ;
```

Example 7-4 shows the sequence to do a 16 x 16 signed multiply. Equation 7-2 shows the algorithm used. The 32-bit result is stored in four registers, RES3:RES0. To account for the sign bits of the arguments, each argument pair's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

# EQUATION 7-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0

= ARG1H:ARG1L • ARG2H:ARG2L

= (ARG1H • ARG2H • 2<sup>16</sup>) +
(ARG1H • ARG2L • 2<sup>8</sup>) +
(ARG1L • ARG2H • 2<sup>8</sup>) +
(ARG1L • ARG2L) +
(-1 • ARG2H<-7> • ARG1H:ARG1L • 2<sup>16</sup>) +
(-1 • ARG1H<-7> • ARG2H:ARG2L • 2<sup>16</sup>)
```

## EXAMPLE 7-4: 16 x 16 SIGNED MULTIPLY ROUTINE

```
ARG1L, W
   MOVE
                        ; ARG1L * ARG2L ->
           ARG2L
   MIIIWE
                        ; PRODH: PRODL
   MOVFF
           PRODH, RES1
   MOVFF
           PRODL, RESO
           ARG1H, W
   MOVF
   MULWF
           ARG2H
                        ; ARG1H * ARG2H ->
                        ; PRODH: PRODL
   MOVFF
           PRODH, RES3 ;
           PRODL, RES2 ;
   MOVFF
   MOVF
           ARG1L, W
   MULWF
           ARG2H
                        ; ARG1L * ARG2H ->
                        ; PRODH: PRODL
   MOVF
           PRODL, W
                        ; Add cross
   ADDWF
           RES1
   MOVF
           PRODH, W
                        ; products
   ADDWFC RES2
   CLRF
           WREG
   ADDWFC RES3
           ARG1H, W
   MOVF
                        ; ARG1H * ARG2L ->
   MULWF
           ARG2L
                        ; PRODH: PRODL
   MOVF
           PRODL, W
                        ; Add cross
   ADDWF
           RES1
   MOVF
           PRODH, W
                        ; products
   ADDWFC RES2
   CLRF
           WREG
   ADDWFC RES3
           ARG2H, 7
                        ; ARG2H:ARG2L neg?
   BTFSS
   BRA
           SIGN ARG1
                        ; no, check ARG1
           ARG1L, W
   MOVF
   SUBWF
           RES2
   MOVF
           ARG1H, W
   SUBWFB RES3
SIGN ARG1
   BTFSS
           ARG1H, 7
                        ; ARG1H:ARG1L neq?
   BRA
           CONT CODE
                        ; no, done
   MOVF
           ARG2L, W
   SUBWE
           RES2
   MOVF
           ARG2H, W
   SUBWFB RES3
CONT_CODE
```

#### 8.0 INTERRUPTS

The PIC18FXX8 devices have multiple interrupt sources and an interrupt priority feature that allows each interrupt source to be assigned a high priority level or a low priority level. The high priority interrupt vector is at 000008h and the low priority interrupt vector is at 000018h. High priority interrupt events will override any low priority interrupts that may be in progress.

There are 13 registers that are used to control interrupt operation. These registers are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2, PIR3
- PIE1, PIE2, PIE3
- IPR1, IPR2, IPR3

It is recommended that the Microchip header files, supplied with MPLAB® IDE, be used for the symbolic bit names in these registers. This allows the assembler/compiler to automatically take care of the placement of these bits within the specified register.

Each interrupt source has three bits to control its operation. The functions of these bits are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- · Priority bit to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON register). When interrupt priority is enabled, there are two bits that enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts. Setting the GIEL bit (INTCON register) enables all interrupts that have the priority bit cleared. When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 000008h or 000018h, depending on the priority level. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PICmicro® mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. The PEIE bit (INTCON register) enables/disables all peripheral interrupt sources. The GIE bit (INTCON register) enables/disables all interrupt sources. All interrupts branch to address 000008h in Compatibility mode.

When an interrupt is responded to, the global interrupt enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High priority interrupt sources can interrupt a low priority interrupt.

The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (000008h or 000018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.


The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used), which re-enables interrupts.

For external interrupt events, such as the INT pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set regardless of the status of their corresponding enable bit or the GIE bit.

Note:

Do not use the MOVFF instruction to modify any of the interrupt control registers while **any** interrupt is enabled. Doing so may cause erratic microcontroller behavior.

FIGURE 8-1: **INTERRUPT LOGIC** 



#### 8.1 INTCON Registers

The INTCON registers are readable and writable registers which contain various enable, priority and flag bits. Because of the number of interrupts to be controlled, PIC18FXX8 devices have three INTCON registers. They are detailed in Register 8-1 through Register 8-3.

Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows software polling.

#### REGISTER 8-1: INTCON: INTERRUPT CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF
bit 7							bit 0

Note:

bit 7 GIE/GIEH: Global Interrupt Enable bit

#### When IPEN (RCON<7>) = 0:

- 1 = Enables all unmasked interrupts
- 0 = Disables all interrupts

#### When IPEN (RCON<7>) = 1:

- 1 = Enables all high priority interrupts
- 0 = Disables all priority interrupts
- bit 6 **PEIE/GIEL:** Peripheral Interrupt Enable bit

#### When IPEN (RCON<7>) = 0:

- 1 = Enables all unmasked peripheral interrupts
- 0 = Disables all peripheral interrupts

#### When IPEN (RCON<7>) = 1:

- 1 = Enables all low priority peripheral interrupts
- 0 = Disables all low priority peripheral interrupts
- bit 5 TMR0IE: TMR0 Overflow Interrupt Enable bit
  - 1 = Enables the TMR0 overflow interrupt
  - 0 = Disables the TMR0 overflow interrupt
- bit 4 INT0IE: INT0 External Interrupt Enable bit
  - 1 = Enables the INT0 external interrupt
  - 0 = Disables the INT0 external interrupt
- bit 3 RBIE: RB Port Change Interrupt Enable bit
  - 1 = Enables the RB port change interrupt
  - 0 = Disables the RB port change interrupt
- bit 2 TMR0IF: TMR0 Overflow Interrupt Flag bit
  - 1 = TMR0 register has overflowed (must be cleared in software)
  - 0 = TMR0 register did not overflow
- bit 1 INT0IF: INT0 External Interrupt Flag bit
  - 1 = The INT0 external interrupt occurred (must be cleared in software by reading PORTB)
  - 0 = The INT0 external interrupt did not occur
- bit 0 RBIF: RB Port Change Interrupt Flag bit
  - 1 = At least one of the RB7:RB4 pins changed state (must be cleared in software)
  - 0 = None of the RB7:RB4 pins have changed state

**Note:** A mismatch condition will continue to set this bit. Reading PORTB will end the mismatch condition and allow the bit to be cleared.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### www.DataPIC18FXX8

#### REGISTER 8-2: INTCON2: INTERRUPT CONTROL REGISTER 2

R/W-1	R/W-1	R/W-1	U-0	U-0	R/W-1	U-0	R/W-1
RBPU	INTEDG0	INTEDG1	_	_	TMR0IP	_	RBIP
bit 7							bit 0

bit 7 RBPU: PORTB Pull-up Enable bit

1 = All PORTB pull-ups are disabled

0 = PORTB pull-ups are enabled by individual port latch values

bit 6 INTEDG0: External Interrupt 0 Edge Select bit

1 = Interrupt on rising edge0 = Interrupt on falling edge

bit 5 INTEDG1: External Interrupt 1 Edge Select bit

1 = Interrupt on rising edge0 = Interrupt on falling edge

bit 4-3 Unimplemented: Read as '0'

bit 2 TMR0IP: TMR0 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 **Unimplemented:** Read as '0'

bit 0 RBIP: RB Port Change Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

Note:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows software polling.

#### REGISTER 8-3: INTCON3: INTERRUPT CONTROL REGISTER 3

R/W-1	R/W-1	U-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0
INT2IP	INT1IP	_	INT2IE	INT1IE	1	INT2IF	INT1IF

bit 7 bit 0

bit 7 INT2IP: INT2 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 **INT1IP:** INT1 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 5 Unimplemented: Read as '0'

bit 4 INT2IE: INT2 External Interrupt Enable bit

1 = Enables the INT2 external interrupt

0 =Disables the INT2 external interrupt

bit 3 INT1IE: INT1 External Interrupt Enable bit

1 = Enables the INT1 external interrupt

0 = Disables the INT1 external interrupt

bit 2 Unimplemented: Read as '0'

bit 1 INT2IF: INT2 External Interrupt Flag bit

1 = The INT2 external interrupt occurred (must be cleared in software)

0 = The INT2 external interrupt did not occur

bit 0 INT1IF: INT1 External Interrupt Flag bit

1 = The INT1 external interrupt occurred (must be cleared in software)

0 = The INT1 external interrupt did not occur

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

**Note:** Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows software polling.

#### 8.2 PIR Registers

The Peripheral Interrupt Request (PIR) registers contain the individual flag bits for the peripheral interrupts (Register 8-4 through Register 8-6). Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Request (Flag) registers (PIR1, PIR2, PIR3).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the Global Interrupt Enable bit, GIE (INTCON register).
  - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt and after servicing that interrupt.

#### REGISTER 8-4: PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1

R/W-0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0
PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF
bit 7							bit 0

bit 7 **PSPIF:** Parallel Slave Port Read/Write Interrupt Flag bit<sup>(1)</sup>

1 = A read or a write operation has taken place (must be cleared in software)

0 = No read or write has occurred

bit 6 ADIF: A/D Converter Interrupt Flag bit

1 = An A/D conversion completed (must be cleared in software)

0 = The A/D conversion is not complete

bit 5 RCIF: USART Receive Interrupt Flag bit

1 = The USART receive buffer, RCREG, is full (cleared when RCREG is read)

0 = The USART receive buffer is empty

bit 4 TXIF: USART Transmit Interrupt Flag bit

1 =The USART transmit buffer, TXREG, is empty (cleared when TXREG is written)

0 = The USART transmit buffer is full

bit 3 SSPIF: Master Synchronous Serial Port Interrupt Flag bit

1 = The transmission/reception is complete (must be cleared in software)

0 = Waiting to transmit/receive

bit 2 CCP1IF: CCP1 Interrupt Flag bit

#### Capture mode:

1 = A TMR1 register capture occurred (must be cleared in software)

0 = No TMR1 register capture occurred

#### Compare mode:

1 = A TMR1 register compare match occurred (must be cleared in software)

0 = No TMR1 register compare match occurred

#### PWM mode:

Unused in this mode.

bit 1 TMR2IF: TMR2 to PR2 Match Interrupt Flag bit

1 = TMR2 to PR2 match occurred (must be cleared in software)

0 = No TMR2 to PR2 match occurred

bit 0 TMR1IF: TMR1 Overflow Interrupt Flag bit

1 = TMR1 register overflowed (must be cleared in software)

0 = TMR1 register did not overflow

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:						
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

#### REGISTER 8-5: PIR2: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 2

U-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	CMIF <sup>(1)</sup>	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>

bit 7 bit 0

bit 7 **Unimplemented:** Read as '0'

bit 6 **CMIF:** Comparator Interrupt Flag bit<sup>(1)</sup>

1 = Comparator input has changed

0 = Comparator input has not changed

bit 5 **Unimplemented:** Read as '0'

bit 4 **EEIF:** EEPROM Write Operation Interrupt Flag bit

1 = Write operation is complete (must be cleared in software)

0 = Write operation is not complete

bit 3 **BCLIF:** Bus Collision Interrupt Flag bit

1 = A bus collision occurred (must be cleared in software)

0 = No bus collision occurred

bit 2 LVDIF: Low-Voltage Detect Interrupt Flag bit

1 = A low-voltage condition occurred (must be cleared in software)

0 = The device voltage is above the Low-Voltage Detect trip point

bit 1 TMR3IF: TMR3 Overflow Interrupt Flag bit

1 = TMR3 register overflowed (must be cleared in software)

0 = TMR3 register did not overflow

bit 0 **ECCP1IF:** ECCP1 Interrupt Flag bit<sup>(1)</sup>

#### Capture mode:

1 = A TMR1 (TMR3) register capture occurred (must be cleared in software)

0 = No TMR1 (TMR3) register capture occurred

#### Compare mode:

1 = A TMR1 register compare match occurred (must be cleared in software)

0 = No TMR1 register compare match occurred

#### PWM mode:

Unused in this mode.

-n = Value at POR

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:
R = Readable bit

W = Writable bit '1' = Bit is set

U = Unimplemented bit, read as '0'

'0' = Bit is cleared

x = Bit is unknown

### www.DataPIC:18FXX8

#### **REGISTER 8-6:** PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3

bit 7									
	IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF	
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	

bit 0

bit 7 IRXIF: Invalid Message Received Interrupt Flag bit

1 = An invalid message has occurred on the CAN bus

0 = An invalid message has not occurred on the CAN bus

bit 6 WAKIF: Bus Activity Wake-up Interrupt Flag bit

1 = Activity on the CAN bus has occurred

0 = Activity on the CAN bus has not occurred

bit 5 **ERRIF:** CAN bus Error Interrupt Flag bit

1 = An error has occurred in the CAN module (multiple sources)

0 = An error has not occurred in the CAN module

bit 4 TXB2IF: Transmit Buffer 2 Interrupt Flag bit

1 = Transmit Buffer 2 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 2 has not completed transmission of a message

bit 3 TXB1IF: Transmit Buffer 1 Interrupt Flag bit

1 = Transmit Buffer 1 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 1 has not completed transmission of a message

bit 2 TXB0IF: Transmit Buffer 0 Interrupt Flag bit

1 = Transmit Buffer 0 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 0 has not completed transmission of a message

bit 1 RXB1IF: Receive Buffer 1 Interrupt Flag bit

1 = Receive Buffer 1 has received a new message

0 = Receive Buffer 1 has not received a new message

bit 0 **RXB0IF:** Receive Buffer 0 Interrupt Flag bit

1 = Receive Buffer 0 has received a new message

0 = Receive Buffer 0 has not received a new message

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 8.3 PIE Registers

The Peripheral Interrupt Enable (PIE) registers contain the individual enable bits for the peripheral interrupts (Register 8-7 through Register 8-9). Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Enable registers (PIE1, PIE2, PIE3). When IPEN is clear, the PEIE bit must be set to enable any of these peripheral interrupts.

#### REGISTER 8-7: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE
hit 7							hit 0

bit 7	<b>PSPIE:</b> Parallel Slave Port Read/Write Interrupt Enable bit <sup>(1)</sup>	1

1 =Enables the PSP read/write interrupt

0 = Disables the PSP read/write interrupt

bit 6 ADIE: A/D Converter Interrupt Enable bit

1 = Enables the A/D interrupt

0 = Disables the A/D interrupt

bit 5 RCIE: USART Receive Interrupt Enable bit

1 =Enables the USART receive interrupt

0 = Disables the USART receive interrupt

bit 4 TXIE: USART Transmit Interrupt Enable bit

1 =Enables the USART transmit interrupt

0 = Disables the USART transmit interrupt

bit 3 SSPIE: Master Synchronous Serial Port Interrupt Enable bit

1 = Enables the MSSP interrupt

0 = Disables the MSSP interrupt

bit 2 **CCP1IE**: CCP1 Interrupt Enable bit

1 =Enables the CCP1 interrupt

0 = Disables the CCP1 interrupt

bit 1 TMR2IE: TMR2 to PR2 Match Interrupt Enable bit

1 = Enables the TMR2 to PR2 match interrupt

0 = Disables the TMR2 to PR2 match interrupt

bit 0 TMR1IE: TMR1 Overflow Interrupt Enable bit

1 = Enables the TMR1 overflow interrupt

0 = Disables the TMR1 overflow interrupt

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### www.DataPIC18FXX8

#### REGISTER 8-8: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

U-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	CMIE <sup>(1)</sup>	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>
bit 7							bit 0

bit 7 **Unimplemented:** Read as '0'

bit 6 **CMIE:** Comparator Interrupt Enable bit<sup>(1)</sup>

1 = Enables the comparator interrupt0 = Disables the comparator interrupt

bit 5 **Unimplemented:** Read as '0'

bit 4 **EEIE**: EEPROM Write Interrupt Enable bit

1 =Enabled 0 =Disabled

bit 3 BCLIE: Bus Collision Interrupt Enable bit

1 = Enabled0 = Disabled

bit 2 LVDIE: Low-Voltage Detect Interrupt Enable bit

1 = Enabled0 = Disabled

bit 1 TMR3IE: TMR3 Overflow Interrupt Enable bit

1 = Enables the TMR3 overflow interrupt0 = Disables the TMR3 overflow interrupt

bit 0 **ECCP1IE**: ECCP1 Interrupt Enable bit<sup>(1)</sup>

1 =Enables the ECCP1 interrupt

0 = Disables the ECCP1 interrupt

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### PIC18FXX8

REGISTER 8-9: PIE3: F	PERIPHERAL	INTERRUPT	ENABLE	REGISTER 3
-----------------------	------------	-----------	--------	------------

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE
bit 7							bit 0

bit 7 IRXIE: Invalid CAN Message Received Interrupt Enable bit

1 = Enables the invalid CAN message received interrupt

0 = Disables the invalid CAN message received interrupt

bit 6 **WAKIE:** Bus Activity Wake-up Interrupt Enable bit

1 = Enables the bus activity wake-up interrupt

0 = Disables the bus activity wake-up interrupt

bit 5 ERRIE: CAN bus Error Interrupt Enable bit

1 = Enables the CAN bus error interrupt

0 = Disables the CAN bus error interrupt

bit 4 TXB2IE: Transmit Buffer 2 Interrupt Enable bit

1 = Enables the Transmit Buffer 2 interrupt

0 =Disables the Transmit Buffer 2 interrupt

bit 3 **TXB1IE:** Transmit Buffer 1 Interrupt Enable bit

1 = Enables the Transmit Buffer 1 interrupt

0 = Disables the Transmit Buffer 1 interrupt

bit 2 **TXB0IE:** Transmit Buffer 0 Interrupt Enable bit

1 = Enables the Transmit Buffer 0 interrupt

0 = Disables the Transmit Buffer 0 interrupt

bit 1 RXB1IE: Receive Buffer 1 Interrupt Enable bit

1 = Enables the Receive Buffer 1 interrupt

0 = Disables the Receive Buffer 1 interrupt

bit 0 RXB0IE: Receive Buffer 0 Interrupt Enable bit

1 = Enables the Receive Buffer 0 interrupt

0 = Disables the Receive Buffer 0 interrupt

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 8.4 IPR Registers

The Interrupt Priority (IPR) registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Priority registers (IPR1, IPR2 and IPR3). The operation of the priority bits requires that the Interrupt Priority Enable bit (IPEN) be set.

#### REGISTER 8-10: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP
bit 7							bit 0

bit 7 **PSPIP:** Parallel Slave Port Read/Write Interrupt Priority bit<sup>(1)</sup>

1 = High priority

0 = Low priority

bit 6 ADIP: A/D Converter Interrupt Priority bit

1 = High priority

0 = Low priority

bit 5 RCIP: USART Receive Interrupt Priority bit

1 = High priority

0 = Low priority

bit 4 TXIP: USART Transmit Interrupt Priority bit

1 = High priority

0 = Low priority

bit 3 SSPIP: Master Synchronous Serial Port Interrupt Priority bit

1 = High priority

0 = Low priority

bit 2 **CCP1IP**: CCP1 Interrupt Priority bit

1 = High priority

0 = Low priority

bit 1 TMR2IP: TMR2 to PR2 Match Interrupt Priority bit

1 = High priority

0 = Low priority

bit 0 TMR1IP: TMR1 Overflow Interrupt Priority bit

1 = High priority

0 = Low priority

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### REGISTER 8-11: IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2

U-0	R/W-1	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
_	CMIP <sup>(1)</sup>		EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP <sup>(1)</sup>

bit 7

bit 7 **Unimplemented:** Read as '0'

bit 6 **CMIP:** Comparator Interrupt Priority bit<sup>(1)</sup>

1 = High priority0 = Low priority

bit 5 **Unimplemented:** Read as '0'

bit 4 **EEIP**: EEPROM Write Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 BCLIP: Bus Collision Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 LVDIP: Low-Voltage Detect Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 TMR3IP: TMR3 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 **ECCP1IP**: ECCP1 Interrupt Priority bit<sup>(1)</sup>

1 = High priority0 = Low priority

**Note 1:** This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### www.DataPIC18FXX8

#### **IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3 REGISTER 8-12:**

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP
bit 7							bit 0

bit 0

bit 7 **IRXIP:** Invalid Message Received Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 WAKIP: Bus Activity Wake-up Interrupt Priority bit

1 = High priority

0 = Low priority

bit 5 **ERRIP:** CAN bus Error Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 4 TXB2IP: Transmit Buffer 2 Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 3 TXB1IP: Transmit Buffer 1 Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 2 **TXB0IP:** Transmit Buffer 0 Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 1 **RXB1IP:** Receive Buffer 1 Interrupt Priority bit

> 1 = High priority 0 = Low priority

RXB0IP: Receive Buffer 0 Interrupt Priority bit bit 0

> 1 = High priority 0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 8.5 RCON Register

The Reset Control (RCON) register contains the IPEN bit which is used to enable prioritized interrupts. The functions of the other bits in this register are discussed in more detail in **Section 4.14** "**RCON Register**".

#### REGISTER 8-13: RCON: RESET CONTROL REGISTER

R/W-0	U-0	U-0	R/W-1	R-1	R-1	R/W-0	R/W-0	
IPEN	_	_	RI	TO	PD	POR	BOR	
bit 7							bit 0	

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (PIC16CXXX Compatibility mode)

bit 6-5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

For details of bit operation, see Register 4-3.

bit 3 TO: Watchdog Time-out Flag bit

For details of bit operation, see Register 4-3.

bit 2 PD: Power-down Detection Flag bit

For details of bit operation, see Register 4-3.

bit 1 POR: Power-on Reset Status bit

For details of bit operation, see Register 4-3.

bit 0 BOR: Brown-out Reset Status bit

For details of bit operation, see Register 4-3.

	a	0	n	•

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 8.6 INT Interrupts

External interrupts on the RB0/INT0, RB1/INT1 and RB2/CANTX/INT2 pins are edge triggered: either rising if the corresponding INTEDGx bit is set in the INTCON2 register, or falling if the INTEDGx bit is clear. When a valid edge appears on the RBx/INTx pin, the corresponding flag bit INTxIF is set. This interrupt can be disabled by clearing the corresponding enable bit INTxIE. Flag bit INTxIF must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt. All external interrupts (INT0, INT1 and INT2) can wake-up the processor from Sleep if bit INTxIE was set prior to going into Sleep. If the Global Interrupt Enable bit, GIE, is set, the processor will branch to the interrupt vector following wake-up.

Interrupt priority for INT1 and INT2 is determined by the value contained in the interrupt priority bits INT1IP (INTCON3<6>) and INT2IP (INTCON3<7>). There is no priority bit associated with INT0; it is always a high priority interrupt source.

#### 8.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow (FFh  $\rightarrow$  00h) in the TMR0 register will set flag bit TMR0IF. In 16-bit mode, an overflow (FFFFh  $\rightarrow$  0000h) in the TMR0H:TMR0L registers will set flag bit TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit TMR0IE (INTCON register). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit TMR0IP (INTCON2 register). See Section 11.0 "Timer0 Module" for further details.

#### 8.8 PORTB Interrupt-on-Change

An input change on PORTB<7:4> sets flag bit RBIF (INTCON register). The interrupt can be enabled/disabled by setting/clearing enable bit RBIE (INTCON register). Interrupt priority for PORTB interrupt-on-change is determined by the value contained in the interrupt priority bit RBIP (INTCON2 register).

#### 8.9 Context Saving During Interrupts

During an interrupt, the return PC value is saved on the stack. Additionally, the WREG, Status and BSR registers are saved on the fast return stack. If a fast return from interrupt is not used (see **Section 4.3 "Fast Register Stack"**), the user may need to save the WREG, Status and BSR registers in software. Depending on the user's application, other registers may also need to be saved. Example 8-1 saves and restores the WREG, Status and BSR registers during an Interrupt Service Routine.

#### EXAMPLE 8-1: SAVING STATUS, WREG AND BSR REGISTERS IN RAM

```
; W TEMP is in Low Access bank
MOVWF
           W TEMP
MOVEE
           STATUS, STATUS TEMP
                                       ; STATUS TEMP located anywhere
MOVFF
           BSR, BSR TEMP
                                       ; BSR located anywhere
; USER ISR CODE
MOVFF
           BSR TEMP, BSR
                                       : Restore BSR
MOVF
           W TEMP, W
                                       : Restore WREG
MOVFF
           STATUS_TEMP, STATUS
                                       ; Restore STATUS
```

#### 9.0 I/O PORTS

Depending on the device selected, there are up to five general purpose I/O ports available on PIC18FXX8 devices. Some pins of the I/O ports are multiplexed with an alternate function from the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.

Each port has three registers for its operation:

- TRIS register (Data Direction register)
- PORT register (reads the levels on the pins of the device)
- LAT register (output latch)

The data latch (LAT register) is useful for read-modify-write operations on the value that the I/O pins are driving.

## 9.1 PORTA, TRISA and LATA Registers

PORTA is a 7-bit wide, bidirectional port. The corresponding Data Direction register is TRISA. Setting a TRISA bit (=1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISA bit (=0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin). On a Power-on Reset, these pins are configured as inputs and read as '0'.

Reading the PORTA register reads the status of the pins, whereas writing to it will write to the port latch.

Read-modify-write operations on the LATA register read and write the latched output value for PORTA.

The RA4 pin is multiplexed with the Timer0 module clock input to become the RA4/T0CKI pin. The RA4/T0CKI pin is a Schmitt Trigger input and an open-drain output. All other RA port pins have TTL input levels and full CMOS output drivers.

The other PORTA pins are multiplexed with analog inputs and the analog VREF+ and VREF- inputs. The operation of each pin is selected by clearing/setting the control bits in the ADCON1 register (A/D Control Register 1). On a Power-on Reset, these pins are configured as analog inputs and read as '0'.

Note: On a Power-on Reset, RA5 and RA3:RA0 are configured as analog inputs and read as '0'. RA6 and RA4 are configured as digital inputs.

The TRISA register controls the direction of the RA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set, when using them as analog inputs.

#### **EXAMPLE 9-1: INITIALIZING PORTA**

```
CLRF
       PORTA ; Initialize PORTA by
             ; clearing output data latches
CLRF
             ; Alternate method to clear
             ; output data latches
MOVLW
      07h
             ; Configure A/D
MOVWF
      ADCON1; for digital inputs
            ; Value used to initialize
      0CFh
MOVLW
             ; data direction
MOVWF TRISA ; Set RA3:RA0 as inputs,
             ; RA5:RA4 as outputs
```

FIGURE 9-1: RA3:RA0 AND RA5 PINS BLOCK DIAGRAM




FIGURE 9-2: RA4/T0CKI PIN BLOCK DIAGRAM




FIGURE 9-3: OSC2/CLKO/RA6 PIN BLOCK DIAGRAM




TABLE 9-1: PORTA FUNCTIONS

Name	Bit#	Buffer	Function
RA0/AN0/CVREF	bit 0	TTL	Input/output, analog input or analog comparator voltage reference output.
RA1/AN1	bit 1	TTL	Input/output or analog input.
RA2/AN2/VREF-	bit 2	TTL	Input/output, analog input or VREF
RA3/AN3/VREF+	bit 3	TTL	Input/output, analog input or VREF+.
RA4/T0CKI	bit 4	ST/OD	Input/output, external clock input for Timer0, output is open-drain type.
RA5/AN4/SS/LVDIN	bit 5	TTL	Input/output, analog input, slave select input for synchronous serial port or Low-Voltage Detect input.
OSC2/CLKO/RA6	bit 6	TTL	Oscillator clock output or input/output.

**Legend:** TTL = TTL input, ST = Schmitt Trigger input, OD = Open-Drain

TABLE 9-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTA	_	RA6	RA5	RA4	RA3	RA2	RA1	RA0	-00x 0000	-uuu uuuu
LATA	_	Latch A	Data Out	out Regist		-xxx xxxx	-uuu uuuu			
TRISA	_	PORTA	PORTA Data Direction Register							-111 1111
ADCON1	ADFM	ADCS2	_	1	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	uu uuuu

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

## 9.2 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATB register, read and write the latched output value for PORTB.

#### **EXAMPLE 9-2: INITIALIZING PORTB**

	LL J 2.	INTIALIZATO I OTTI
CLRF	PORTB	; Initialize PORTB by
		; clearing output
		; data latches
CLRF	LATB	; Alternate method
		; to clear output
		; data latches
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISB	; Set RB3:RB0 as inputs
		; RB5:RB4 as outputs
		; RB7:RB6 as inputs

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit RBPU (INTCON2 register). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

Four of the PORTB pins (RB7:RB4) have an interrupton-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB7:RB4 pin configured as an output is excluded from the interrupton-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are ORed together to generate the RB Port Change Interrupt with Flag bit RBIF (INTCON register). This interrupt can wake the device from Sleep. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:


- a) Any read or write of PORTB (except with the MOVFF instruction). This will end the mismatch condition.
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.


- Note 1: While in Low-Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin and should not be held low during normal operation to protect against inadvertent ICSP mode entry.
  - 2: When using Low-Voltage ICSP Programming (LVP), the pull-up on RB5 becomes disabled. If TRISB bit 5 is cleared, thereby setting RB5 as an output, LATB bit 5 must also be cleared for proper operation.

FIGURE 9-4: **RB7:RB4 PINS BLOCK DIAGRAM** 




Note 1: I/O pins have diode protection to VDD and Vss.
2: To enable weak pull-ups, set the appropriate TRIS bit(s) and clear the RBPU bit (INTCON2 register).

#### FIGURE 9-5: **RB1:RB0 PINS BLOCK DIAGRAM**




Note 1: I/O pins have diode protection to VDD and Vss.
2: To enable weak pull-ups, set the appropriate TRIS bit(s) and clear the RBPU bit (INTCON2 register).

FIGURE 9-6: RB2/CANTX/INT2 PIN BLOCK DIAGRAM



#### FIGURE 9-7: RB3/CANRX PIN BLOCK DIAGRAM



**TABLE 9-3: PORTB FUNCTIONS** 

Name	Bit#	Buffer	Function
RB0/INT0	bit 0	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt 0 input. Internal software programmable weak pull-up.
RB1/INT1	bit 1	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt 1 input. Internal software programmable weak pull-up.
RB2/CANTX/ INT2	bit 2	TTL/ST <sup>(1)</sup>	Input/output pin, CAN bus transmit pin or external interrupt 2 input. Internal software programmable weak pull-up.
RB3/CANRX	bit 3	TTL	Input/output pin or CAN bus receive pin. Internal software programmable weak pull-up.
RB4	bit 4	TTL	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up.
RB5/PGM	bit 5	TTL	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Low-voltage serial programming enable.
RB6/PGC	bit 6	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming clock.
RB7/PGD	bit 7	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming data.

**Legend:** TTL = TTL input, ST = Schmitt Trigger input

Note 1: This buffer is a Schmitt Trigger input when configured as the external interrupt.2: This buffer is a Schmitt Trigger input when used in Serial Programming mode.

TABLE 9-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	uuuu uuuu
LATB	LATB Data	Output Re		xxxx xxxx	uuuu uuuu					
TRISB	PORTB Da	ata Direction	Register						1111 1111	1111 1111
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
INTCON2	RBPU	INTEDG0	INTEDG1	_	_	TMR0IP	_	RBIP	1111-1	1111-1
INTCON3	INT2IP	INT1IP	_	INT2IE	INT1IE	_	INT2IF	INT1IF	11-0 0-00	11-1 0-00

 $\textbf{Legend:} \quad \ x = \text{unknown}, \ u = \text{unchanged}. \ \ \text{Shaded cells are not used by PORTB}.$ 

#### 9.3 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATC register, read and write the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (Table 9-5). PORTC pins have Schmitt Trigger input buffers.


When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

The pin override value is not loaded into the TRIS register. This allows read-modify-write of the TRIS register, without concern due to peripheral overrides.

**EXAMPLE 9-3:** INITIALIZING PORTC

CLRF	PORTC	; Initialize PORTC by
		; clearing output
		; data latches
CLRF	LATC	; Alternate method
		; to clear output
		; data latches
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISC	; Set RC3:RC0 as inputs
		; RC5:RC4 as outputs
		; RC7:RC6 as inputs

**FIGURE 9-8:** PORTC BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



**TABLE 9-5: PORTC FUNCTIONS** 

Name	Bit#	Buffer Type	Function
RC0/T1OSO/T1CKI	bit 0	ST	Input/output port pin, Timer1 oscillator output or Timer1/Timer3 clock input.
RC1/T1OSI	bit 1	ST	Input/output port pin or Timer1 oscillator input.
RC2/CCP1	bit 2	ST	Input/output port pin or Capture 1 input/Compare 1 output/PWM1 output.
RC3/SCK/SCL	bit 3	ST	Input/output port pin or synchronous serial clock for SPI™/I <sup>2</sup> C™.
RC4/SDI/SDA	bit 4	ST	Input/output port pin or SPI data in (SPI mode) or data I/O (I <sup>2</sup> C mode).
RC5/SDO	bit 5	ST	Input/output port pin or synchronous serial port data output.
RC6/TX/CK	bit 6	ST	Input/output port pin, addressable USART asynchronous transmit or addressable USART synchronous clock.
RC7/RX/DT	bit 7	ST	Input/output port pin, addressable USART asynchronous receive or addressable USART synchronous data.

**Legend:** ST = Schmitt Trigger input

TABLE 9-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	xxxx xxxx	uuuu uuuu
LATC	LATC D	LATC Data Output Register								uuuu uuuu
TRISC	PORTC	ORTC Data Direction Register								1111 1111

**Legend:** x = unknown, u = unchanged

## 9.4 PORTD, TRISD and LATD Registers

**Note:** This port is only available on the PIC18F448 and PIC18F458.

PORTD is an 8-bit wide, bidirectional port. The corresponding Data Direction register for the port is TRISD. Setting a TRISD bit (=1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISD bit (=0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATD register read and write the latched output value for PORTD.

PORTD uses Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.

PORTD can be configured as an 8-bit wide, microprocessor port (Parallel Slave Port or PSP) by setting the control bit PSPMODE (TRISE<4>). In this mode, the input buffers are TTL. See **Section 10.0 "Parallel Slave Port"** for additional information.

PORTD is also multiplexed with the analog comparator module and the ECCP module.

**EXAMPLE 9-4: INITIALIZING PORTD** 

	_	
CLRF	PORTD	; Initialize PORTD by
		; clearing output
		; data latches
CLRF	LATD	; Alternate method
		; to clear output
		; data latches
MOVLW	07h	; comparator off
MOVWF	CMCON	
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISD	; Set RD3:RD0 as inputs
		; RD5:RD4 as outputs
		; RD7:RD6 as inputs
1		

#### FIGURE 9-9: PORTD BLOCK DIAGRAM IN I/O PORT MODE




TABLE 9-7: PORTD FUNCTIONS

Name	Bit#	Buffer Type	Function
RD0/PSP0/C1IN+	bit 0	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 0 or C1IN+ comparator input.
RD1/PSP1/C1IN-	bit 1	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 1 or C1IN- comparator input.
RD2/PSP2/C2IN+	bit 2	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 2 or C2IN+ comparator input.
RD3/PSP3/C2IN-	bit 3	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 3 or C2IN- comparator input.
RD4/PSP4/ECCP1/P1A	bit 4	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 4 or ECCP1/P1A pin.
RD5/PSP5/P1B	bit 5	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 5 or P1B pin.
RD6/PSP6/P1C	bit 6	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 6 or P1C pin.
RD7/PSP7/P1D	bit 7	ST/TTL <sup>(1)</sup>	Input/output port pin, Parallel Slave Port bit 7 or P1D pin.

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in Parallel Slave Port mode.

TABLE 9-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTD	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	xxxx xxxx	uuuu uuuu
LATD	LATD [	Data Out	tput Regi		xxxx xxxx	uuuu uuuu				
TRISD	PORTD Data Direction Register								1111 1111	1111 1111
TRISE	IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0	0000 -111	0000 -111

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTD.

## 9.5 PORTE, TRISE and LATE Registers

**Note:** This port is only available on the PIC18F448 and PIC18F458.

PORTE is a 3-bit wide, bidirectional port. PORTE has three pins (RE0/AN5/RD, RE1/AN6/WR/C1OUT and RE2/AN7/CS/C2OUT) which are individually configurable as inputs or outputs. These pins have Schmitt Trigger input buffers.

Read-modify-write operations on the LATE register, read and write the latched output value for PORTE.

The corresponding Data Direction register for the port is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

The TRISE register also controls the operation of the Parallel Slave Port through the control bits in the upper half of the register. These are shown in Register 9-1.


When the Parallel Slave Port is active, the PORTE pins function as its control inputs. For additional details, refer to Section 10.0 "Parallel Slave Port".

PORTE pins are also multiplexed with inputs for the A/D converter and outputs for the analog comparators. When selected as an analog input, these pins will read as '0's. Direction bits TRISE<2:0> control the direction of the RE pins, even when they are being used as analog inputs. The user must make sure to keep the pins configured as inputs when using them as analog inputs.

#### **EXAMPLE 9-5: INITIALIZING PORTE**

<b>—</b> /\/\\	0 0.	IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII
CLRF	PORTE	; Initialize PORTE by
		; clearing output
		; data latches
CLRF	LATE	; Alternate method
		; to clear output
		; data latches
MOVLW	03h	; Value used to
		; initialize data
		; direction
MOVWF	TRISE	; Set RE1:RE0 as inputs
		; RE2 as an output
		; (RE4=0 - PSPMODE Off)

#### FIGURE 9-10: PORTE BLOCK DIAGRAM



#### REGISTER 9-1: TRISE REGISTER

R-0	R-0	R/W-0	R/W-0	U-0	R/W-1	R/W-1	R/W-1
IBF	OBF	IBOV	PSPMODE	1	TRISE2	TRISE1	TRISE0

bit 7 bit 0

bit 7 IBF: Input Buffer Full Status bit

1 = A word has been received and waiting to be read by the CPU

0 = No word has been received

bit 6 **OBF**: Output Buffer Full Status bit

1 = The output buffer still holds a previously written word

0 = The output buffer has been read

bit 5 **IBOV**: Input Buffer Overflow Detect bit (in Microprocessor mode)

1 = A write occurred when a previously input word has not been read (must be cleared in software)

0 = No overflow occurred

bit 4 **PSPMODE**: Parallel Slave Port Mode Select bit

1 = Parallel Slave Port mode

0 = General Purpose I/O mode

bit 3 **Unimplemented:** Read as '0'

bit 2 TRISE2: RE2 Direction Control bit

1 = Input

0 = Output

bit 1 TRISE1: RE1 Direction Control bit

1 = Input

0 = Output

bit 0 TRISE0: RE0 Direction Control bit

1 = Input

0 = Output

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### www.DataPIC18FXX8

TABLE 9-9: PORTE FUNCTIONS

Name	Bit# Buffer Typ		Function			
RE0/AN5/RD	bit 0	ST/TTL <sup>(1)</sup>	Input/output port pin, analog input or read control input in Parallel Slave Port mode.			
RE1/AN6/WR/C1OUT	bit 1	ST/TTL <sup>(1)</sup>	Input/output port pin, analog input, write control input in Parallel Slave Port mode or Comparator 1 output.			
RE2/AN7/CS/C2OUT	bit 2	ST/TTL <sup>(1)</sup>	Input/output port pin, analog input, chip select control input in Parallel Slave Port mode or Comparator 2 output.			

**Legend:** ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in Parallel Slave Port mode.

TABLE 9-10: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
TRISE	IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0	0000 -111	0000 -111
PORTE	_	1	_			Read PORTE pin/ Write PORTE Data Latch			xxx	uuu
LATE	_	_	_	_	-	Read PORTE Data Latch/ Write PORTE Data Latch			xxx	uuu
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTE.

## 10.0 PARALLEL SLAVE PORT

**Note:** The Parallel Slave Port is only available on PIC18F4X8 devices.

In addition to its function as a general I/O port, PORTD can also operate as an 8-bit wide Parallel Slave Port (PSP) or microprocessor port. PSP operation is controlled by the 4 upper bits of the TRISE register (Register 9-1). Setting control bit PSPMODE (TRISE<4>) enables PSP operation. In Slave mode, the port is asynchronously readable and writable by the external world.

The PSP can directly interface to an 8-bit microprocessor data bus. The external microprocessor can read or write the PORTD latch as an 8-bit latch. Setting the control bit PSPMODE enables the PORTE I/O pins to become control inputs for the microprocessor port. When set, port pin RE0 is the  $\overline{\text{RD}}$  input, RE1 is the  $\overline{\text{WR}}$  input and RE2 is the  $\overline{\text{CS}}$  (chip select) input. For this functionality, the corresponding data direction bits of the TRISE register (TRISE<2:0>) must be configured as inputs (set).

A write to the PSP occurs when both the  $\overline{CS}$  and  $\overline{WR}$  lines are first detected low. A read from the PSP occurs when both the  $\overline{CS}$  and  $\overline{RD}$  lines are first detected low. The timing for the control signals in Write and Read modes is shown in Figure 10-2 and Figure 10-3, respectively.

FIGURE 10-1: PORTD AND PORTE BLOCK DIAGRAM (PARALLEL SLAVE PORT)




FIGURE 10-2: PARALLEL SLAVE PORT WRITE WAVEFORMS




FIGURE 10-3: PARALLEL SLAVE PORT READ WAVEFORMS




TABLE 10-1: REGISTERS ASSOCIATED WITH PARALLEL SLAVE PORT

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		Value on POR, BOR		ue on other sets	
PORTD	Port Data L	atch when v	vritten; Poi	t pins when r	ead				xxxx	xxxx	uuuu	uuuu	
LATD	LATD Data	Output bits							xxxx	xxxx	uuuu	uuuu	
TRISD	PORTD Da	ta Direction	bits					1111	1111	1111	1111		
PORTE	_	_	_	_	_	RE2	RE1	RE0		-xxx		-000	
LATE	LATE Data	Output bits								-xxx		-uuu	
TRISE	IBF	OBF	IBOV	PSPMODE	_	PORTE D	Data Direc	tion bits	0000	-111	0000	-111	
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u	
PIR1	PSPIF	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000	
PIE1	PSPIE	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000	
IPR1	PSPIP	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111	

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Parallel Slave Port.

## PIC18FXX8

## 11.0 TIMERO MODULE

The Timer0 module has the following features:

- Software selectable as an 8-bit or 16-bit timer/counter
- · Readable and writable
- Dedicated 8-bit software programmable prescaler
- · Clock source selectable to be external or internal
- Interrupt-on-overflow from FFh to 00h in 8-bit mode and FFFFh to 0000h in 16-bit mode
- · Edge select for external clock

Register 11-1 shows the Timer0 Control register (T0CON).

Figure 11-1 shows a simplified block diagram of the Timer0 module in 8-bit mode and Figure 11-2 shows a simplified block diagram of the Timer0 module in 16-bit mode.

The T0CON register is a readable and writable register that controls all the aspects of Timer0, including the prescale selection.

Note: Timer0 is enabled on POR.

## REGISTER 11-1: TOCON: TIMERO CONTROL REGISTER


R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
TMR00N	T08BIT	T0CS	T0SE	PSA	T0PS2	T0PS1	T0PS0
bit 7							bit 0

- bit 7 TMR0ON: Timer0 On/Off Control bit
  - 1 = Enables Timer0
  - 0 = Stops Timer0
- bit 6 T08BIT: Timer0 8-bit/16-bit Control bit
  - 1 = Timer0 is configured as an 8-bit timer/counter
  - 0 = Timer0 is configured as a 16-bit timer/counter
- bit 5 TOCS: Timer0 Clock Source Select bit
  - 1 = Transition on T0CKI pin
  - 0 = Internal instruction cycle clock (CLKO)
- bit 4 T0SE: Timer0 Source Edge Select bit
  - 1 = Increment on high-to-low transition on TOCKI pin
  - 0 = Increment on low-to-high transition on TOCKI pin
- bit 3 **PSA**: Timer0 Prescaler Assignment bit
  - 1 = TImer0 prescaler is not assigned. Timer0 clock input bypasses prescaler.
  - 0 = Timer0 prescaler is assigned. Timer0 clock input comes from prescaler output.
- bit 2-0 T0PS2:T0PS0: Timer0 Prescaler Select bits
  - 111 = 1:256 Prescale value
  - 110 = 1:128 Prescale value
  - 101 = 1:64 Prescale value
  - 100 = 1:32 Prescale value
  - 011 = 1:16 Prescale value
  - 010 = 1:8 Prescale value
  - 001 = 1:4 Prescale value
  - 000 = 1:2 Prescale value


## Legend:

R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

## FIGURE 11-1: TIMERO BLOCK DIAGRAM IN 8-BIT MODE



## FIGURE 11-2: TIMERO BLOCK DIAGRAM IN 16-BIT MODE



## 11.1 Timer0 Operation

Timer0 can operate as a timer or as a counter.

Timer mode is selected by clearing the T0CS bit. In Timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If the TMR0L register is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0L register.

Counter mode is selected by setting the ToCS bit. In Counter mode, Timer0 will increment either on every rising or falling edge of pin RA4/ToCKI. The incrementing edge is determined by the Timer0 Source Edge Select bit (ToSE). Clearing the ToSE bit selects the rising edge. Restrictions on the external clock input are discussed below.

When an external clock input is used for Timer0, it must meet certain requirements. The requirements ensure the external clock can be synchronized with the internal phase clock (Tosc). Also, there is a delay in the actual incrementing of Timer0 after synchronization.

#### 11.2 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not readable or writable.

The PSA and T0PS2:T0PS0 bits determine the prescaler assignment and prescale ratio.

Clearing bit PSA will assign the prescaler to the Timer0 module. When the prescaler is assigned to the Timer0 module, prescale values of 1:2, 1:4, ..., 1:256 are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF TMR0, MOVWF TMR0, BSF TMR0, x.... etc.) will clear the prescaler count.

Note: Writing to TMR0 when the prescaler is assigned to Timer0 will clear the prescaler count but will not change the prescaler assignment.

## 11.2.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control (i.e., it can be changed "on-the-fly" during program execution).

## 11.3 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode or FFFFh to 0000h in 16-bit mode. This overflow sets the TMR0IF bit. The interrupt can be masked by clearing the TMR0IE bit. The TMR0IF bit must be cleared in software by the Timer0 module Interrupt Service Routine before re-enabling this interrupt. The TMR0 interrupt cannot awaken the processor from Sleep since the timer is shut-off during Sleep.

## 11.4 16-Bit Mode Timer Reads and Writes

Timer0 can be set in 16-bit mode by clearing the T08BIT in T0CON. Registers TMR0H and TMR0L are used to access the 16-bit timer value.

TMR0H is not the high byte of the timer/counter in 16-bit mode, but is actually a buffered version of the high byte of Timer0 (refer to Figure 11-1). The high byte of the Timer0 timer/counter is not directly readable nor writable. TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte were valid, due to a rollover between successive reads of the high and low byte.

A write to the high byte of Timer0 must also take place through the TMR0H Buffer register. Timer0 high byte is updated with the contents of the buffered value of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

## TABLE 11-1: REGISTERS ASSOCIATED WITH TIMERO

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
TMR0L	Timer0 Modu	ule Low Byte F		xxxx xxxx	uuuu uuuu					
TMR0H	Timer0 Modu	ule High Byte I	Register						0000 0000	0000 0000
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INTOIF	RBIF	0000 000x	0000 000u
T0CON	TMR00N	T08BIT T0CS T0SE PSA T0PS2 T0PS1 T0PS0							1111 1111	1111 1111
TRISA	_	PORTA Data	PORTA Data Direction Register <sup>(1)</sup>							-111 1111

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by Timer0.

Note 1: Bit 6 of PORTA, LATA and TRISA is enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, it is disabled and reads as '0'.

# www.DataPIC18FXX8

NOTES:

## 12.0 TIMER1 MODULE

The Timer1 module timer/counter has the following features:

- 16-bit timer/counter
  - (two 8-bit registers: TMR1H and TMR1L)
- Readable and writable (both registers)
- · Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- · Reset from CCP module special event trigger

Register 12-1 shows the Timer1 Control register. This register controls the operating mode of the Timer1 module, as well as contains the Timer1 Oscillator Enable bit (T1OSCEN). Timer1 can be enabled/disabled by setting/clearing control bit, TMR1ON (T1CON register).

Figure 12-1 is a simplified block diagram of the Timer1 module.

<b>Note:</b> Timer1 is disabled on POR.	
---	--

## REGISTER 12-1: T1CON: TIMER1 CONTROL REGISTER

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N
bit 7							bit 0

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Timer1 in one 16-bit operation
  - 0 = Enables register read/write of Timer1 in two 8-bit operations
- bit 6 Unimplemented: Read as '0'
- bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 3 T10SCEN: Timer1 Oscillator Enable bit
  - 1 = Timer1 oscillator is enabled
  - 0 = Timer1 oscillator is shut-off

The oscillator inverter and feedback resistor are turned off to eliminate power drain.

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Select bit

#### When TMR1CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

## When TMR1CS = 0:

This bit is ignored. Timer1 uses the internal clock when TMR1CS = 0.

- bit 1 TMR1CS: Timer1 Clock Source Select bit
  - 1 = External clock from pin RC0/T1OSO/T1CKI (on the rising edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR10N: Timer1 On bit
  - 1 = Enables Timer1
  - 0 = Stops Timer1

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 12.1 Timer1 Operation

Timer1 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The operating mode is determined by the clock select bit, TMR1CS (T1CON register).

When TMR1CS is clear, Timer1 increments every instruction cycle. When TMR1CS is set, Timer1 increments on every rising edge of the external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored.

Timer1 also has an internal "Reset input". This Reset can be generated by the CCP module (Section 15.1 "CCP1 Module").

## FIGURE 12-1: TIMER1 BLOCK DIAGRAM



## FIGURE 12-2: TIMER1 BLOCK DIAGRAM: 16-BIT READ/WRITE MODE



### 12.2 Timer1 Oscillator

A crystal oscillator circuit is built in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON register). The oscillator is a low-power oscillator rated up to 50 kHz. It will continue to run during Sleep. It is primarily intended for a 32 kHz crystal. Table 12-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

TABLE 12-1: CAPACITOR SELECTION FOR THE ALTERNATE OSCILLATOR

Osc Type	Freq	C1	C2							
LP	32 kHz	TBD <sup>(1)</sup>	TBD <sup>(1)</sup>							
	Crystal to be Tested:									
32.768 kHz   Epson C-001R32.768K-A   ±20 PPM										

- **Note 1:** Microchip suggests 33 pF as a starting point in validating the oscillator circuit.
  - 2: Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **4:** Capacitor values are for design guidance only.

## 12.3 Timer1 Interrupt

The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR1 Interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit, TMR1IF (PIR registers). This interrupt can be enabled/disabled by setting/clearing TMR1 Interrupt Enable bit, TMR1IE (PIE registers).

## 12.4 Resetting Timer1 Using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer1 and start an A/D conversion (if the A/D module is enabled).

Note: The special event triggers from the CCP1 module will not set interrupt flag bit, TMR1IF (PIR registers).

Timer1 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from CCP1, the write will take precedence.

In this mode of operation, the CCPR1H:CCPR1L register pair effectively becomes the period register for Timer1.

## 12.5 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes (see Figure 12-2). When the RD16 control bit (T1CON register) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L will load the contents of the high byte of Timer1 into the Timer1 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, is valid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.

The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

## TABLE 12-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Valu POR,		Valu all c	ther
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111
TMR1L	Holding Re	gister for the	Least Signif	t Significant Byte of the 16-bit TMR1 Register						xxxx	uuuu	uuuu
TMR1H	Holding Register for the Most Significant Byte of the 16-bit TMR1 Register								xxxx	xxxx	uuuu	uuuu
T1CON	RD16	ı	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	0 - 0 0	0000	u-uu	uuuu

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

## 13.0 TIMER2 MODULE

The Timer2 module timer has the following features:

- 8-bit timer (TMR2 register)
- 8-bit period register (PR2)
- · Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- · Interrupt on TMR2 match of PR2
- SSP module optional use of TMR2 output to generate clock shift

Register 13-1 shows the Timer2 Control register. Timer2 can be shut-off by clearing control bit TMR2ON (T2CON register) to minimize power consumption. Figure 13-1 is a simplified block diagram of the Timer2 module. The prescaler and postscaler selection of Timer2 are controlled by this register.

## 13.1 Timer2 Operation

Timer2 can be used as the PWM time base for the PWM mode of the CCP module. The TMR2 register is readable and writable and is cleared on any device Reset. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON register). The match output of TMR2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR2 interrupt (latched in flag bit TMR2IF, PIR registers).

The prescaler and postscaler counters are cleared when any of the following occurs:

- · A write to the TMR2 register
- · A write to the T2CON register
- Any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

Note: Timer2 is disabled on POR.

#### REGISTER 13-1: T2CON: TIMER2 CONTROL REGISTER

	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0
ŀ	oit 7							bit 0

bit 7 **Unimplemented:** Read as '0'

bit 6-3 TOUTPS3:TOUTPS0: Timer2 Output Postscale Select bits

0000 = 1:1 Postscale 0001 = 1:2 Postscale

•

٠

1111 = 1:16 Postscale

bit 2 TMR2ON: Timer2 On bit

1 = Timer2 is on

0 = Timer2 is off

bit 1-0 T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits

00 = Prescaler is 1

01 = Prescaler is 4

1x = Prescaler is 16

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 13.2 Timer2 Interrupt

The Timer2 module has an 8-bit period register, PR2. Timer2 increments from 00h until it matches PR2 and then resets to 00h on the next increment cycle. PR2 is a readable and writable register. The PR2 register is initialized to FFh upon Reset.

## 13.3 Output of TMR2

The output of TMR2 (before the postscaler) is a clock input to the Synchronous Serial Port module which optionally uses it to generate the shift clock.

FIGURE 13-1: TIMER2 BLOCK DIAGRAM




TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
TMR2	Timer2 Mod	dule Register							0000 0000	0000 0000
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	-000 0000
PR2	Timer2 Period Register								1111 1111	1111 1111

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

## 14.0 TIMER3 MODULE

The Timer3 module timer/counter has the following features:

- 16-bit timer/counter
  - (two 8-bit registers: TMR3H and TMR3L)
- Readable and writable (both registers)
- · Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- · Reset from CCP1/ECCP1 module trigger

Figure 14-1 is a simplified block diagram of the Timer3 module.

Register 14-1 shows the Timer3 Control register. This register controls the operating mode of the Timer3 module and sets the CCP1 and ECCP1 clock source.

Register 12-1 shows the Timer1 Control register. This register controls the operating mode of the Timer1 module, as well as contains the Timer1 Oscillator Enable bit (T1OSCEN) which can be a clock source for Timer3.

**Note:** Timer3 is disabled on POR.

### REGISTER 14-1: T3CON:TIMER3 CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON
bit 7							bit 0

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Timer3 in one 16-bit operation
  - 0 = Enables register read/write of Timer3 in two 8-bit operations
- bit 6.3 T3ECCP1: Timer3 and Timer1 to CCP1/ECCP1 Enable bits
  - 1x = Timer3 is the clock source for compare/capture CCP1 and ECCP1 modules
  - 01 = Timer3 is the clock source for compare/capture of ECCP1, Timer1 is the clock source for compare/capture of CCP1
  - 00 = Timer1 is the clock source for compare/capture CCP1 and ECCP1 modules
- bit 5-4 T3CKPS1:T3CKPS0: Timer3 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 2 T3SYNC: Timer3 External Clock Input Synchronization Control bit

(Not usable if the system clock comes from Timer1/Timer3.)

## When TMR3CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

## When TMR3CS = 0:

This bit is ignored. Timer3 uses the internal clock when TMR3CS = 0.

- bit 1 TMR3CS: Timer3 Clock Source Select bit
  - 1 = External clock input from Timer 1 oscillator or T1CKI (on the rising edge after the first falling edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR3ON: Timer3 On bit
  - 1 = Enables Timer3
  - 0 = Stops Timer3

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 14.1 Timer3 Operation

Timer3 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter


The operating mode is determined by the clock select bit, TMR3CS (T3CON register).

When TMR3CS = 0, Timer3 increments every instruction cycle. When TMR3CS = 1, Timer3 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored.

Timer3 also has an internal "Reset input". This Reset can be generated by the CCP module (Section 15.1 "CCP1 Module").

## FIGURE 14-1: TIMER3 BLOCK DIAGRAM



### FIGURE 14-2: TIMER3 BLOCK DIAGRAM CONFIGURED IN 16-BIT READ/WRITE MODE



#### 14.2 Timer1 Oscillator

The Timer1 oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN bit (T1CON register). The oscillator is a low-power oscillator rated up to 50 kHz. Refer to **Section 12.0 "Timer1 Module"** for Timer1 oscillator details.

## 14.3 Timer3 Interrupt

The TMR3 register pair (TMR3H:TMR3L) increments from 0000h to 0FFFFh and rolls over to 0000h. The TMR3 interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit TMR3IF (PIR registers). This interrupt can be enabled/disabled by setting/clearing TMR3 Interrupt Enable bit, TMR3IE (PIE registers).

## 14.4 Resetting Timer3 Using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer3.

**Note:** The special event triggers from the CCP module will not set interrupt flag bit TMR3IF (PIR registers).

Timer3 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer3 is running in Asynchronous Counter mode, this Reset operation may not work. In the event that a write to Timer3 coincides with a special event trigger from CCP1, the write will take precedence. In this mode of operation, the CCPR1H:CCPR1L register pair becomes the period register for Timer3. Refer to Section 15.0 "Capture/Compare/PWM (CCP) Modules" for CCP details.

TABLE 14-1: REGISTERS ASSOCIATED WITH TIMER3 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR,		Valu all o Res	ther
INTCON	GIE/ GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR2	_	CMIF	-	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0	0000	-0-0	0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0	0000	-0-0	0000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1	1111	-1-1	1111
TMR3L	Holding Reg	gister for the I	_east Signifi	cant Byte o	f the 16-bit T	MR3 Regis	ter		xxxx	xxxx	uuuu	uuuu
TMR3H	Holding Reg	olding Register for the Most Significant Byte of the 16-bit TMR3 Register					xxxx	xxxx	uuuu	uuuu		
T1CON	RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00	0000	u-uu	uuuu
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000	0000	uuuu	uuuu

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

# www.DataPIC18FXX8

NOTES:

# 15.0 CAPTURE/COMPARE/PWM (CCP) MODULES

The CCP (Capture/Compare/PWM) module contains a 16-bit register that can operate as a 16-bit Capture register, as a 16-bit Compare register or as a PWM Duty Cycle register.

The operation of the CCP module is identical to that of the ECCP module (discussed in detail in Section 16.0 "Enhanced Capture/Compare/PWM (ECCP) Module") with two exceptions. The CCP

module has a Capture special event trigger that can be used as a message received time-stamp for the CAN module (refer to **Section 19.0 "CAN Module"** for CAN operation) which the ECCP module does not. The ECCP module, on the other hand, has Enhanced PWM functionality and auto-shutdown capability. Aside from these, the operation of the module described in this section is the same as the ECCP.

The control register for the CCP module is shown in Register 15-1. Table 15-2 (following page) details the interactions of the CCP and ECCP modules.

#### REGISTER 15-1: CCP1CON: CCP1 CONTROL REGISTER

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0
bit 7							bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5-4 DCxB1:DCxB0: PWM Duty Cycle bit 1 and bit 0

Capture mode:

Unused.

Compare mode:

Unused.

PWM mode:

These bits are the two LSbs (bit 1 and bit 0) of the 10-bit PWM duty cycle. The upper eight bits (DCx9:DCx2) of the duty cycle are found in CCPRxL.

bit 3-0 CCPxM3:CCPxM0: CCPx Mode Select bits

0000 = Capture/Compare/PWM off (resets CCPx module)

0001 = Reserved

0010 = Compare mode, toggle output on match (CCPxIF bit is set)

0011 = Capture mode, CAN message received (CCP1 only)

0100 = Capture mode, every falling edge

0101 = Capture mode, every rising edge

0110 = Capture mode, every 4th rising edge

0111 = Capture mode, every 16th rising edge

1000 = Compare mode, initialize CCP pin low, on compare match force CCP pin high (CCPIF bit is set)

1001 = Compare mode, initialize CCP pin high, on compare match force CCP pin low (CCPIF bit is set)

1010 = Compare mode, CCP pin is unaffected (CCPIF bit is set)

1011 = Compare mode, trigger special event (CCP1IF bit is set; CCP resets TMR1 or TMR3 and starts an A/D conversion if the A/D module is enabled)

11xx = PWM mode

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 15.1 CCP1 Module

Capture/Compare/PWM Register1 (CCPR1) is comprised of two 8-bit registers: CCPR1L (low byte) and CCPR1H (high byte). The CCP1CON register controls the operation of CCP1. All are readable and writable.

Table 15-1 shows the timer resources of the CCP module modes.

TABLE 15-1: CCP1 MODE – TIMER RESOURCE

CCP1 Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2

## 15.2 Capture Mode

In Capture mode, CCPR1H:CCPR1L captures the 16-bit value of the TMR1 or TMR3 register when an event occurs on pin RC2/CCP1. An event is defined as:

- · every falling edge
- · every rising edge
- · every 4th rising edge
- every 16th rising edge

An event is selected by control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). When a capture is made, the interrupt request flag bit, CCP1IF (PIR registers), is set. It must be cleared in software. If another capture occurs before the value in register CCPR1 is read, the old captured value will be lost.

## 15.2.1 CCP PIN CONFIGURATION

In Capture mode, the RC2/CCP1 pin should be configured as an input by setting the TRISC<2> bit.

Note:	If the RC2/CCP1 is configured as an out-
	put, a write to the port can cause a capture
	condition.

## 15.2.2 TIMER1/TIMER3 MODE SELECTION

The timers used with the capture feature (either Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation may not work. The timer used with each CCP module is selected in the T3CON register.

## TABLE 15-2: INTERACTION OF CCP1 AND ECCP1 MODULES

CCP1 Mode	ECCP1 Mode	Interaction
Capture	Capture	TMR1 or TMR3 time base. Time base can be different for each CCP.
Capture	Compare	The compare could be configured for the special event trigger which clears either TMR1 or TMR3, depending upon which time base is used.
Compare	Compare	The compare(s) could be configured for the special event trigger which clears TMR1 or TMR3, depending upon which time base is used.
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).
PWM	Capture	None.
PWM	Compare	None.

#### 15.2.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep bit CCP1IE (PIE registers) clear to avoid false interrupts and should clear the flag bit CCP1IF, following any such change in operating mode.

## 15.2.4 CCP1 PRESCALER

There are four prescaler settings specified by bits CCP1M3:CCP1M0. Whenever the CCP1 module is turned off, or the CCP1 module is not in Capture mode, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared; therefore, the first capture may be from a non-zero prescaler. Example 15-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

#### 15.2.5 CAN MESSAGE TIME-STAMP

The CAN capture event occurs when a message is received in either of the receive buffers. The CAN module provides a rising edge to the CCP1 module to cause a capture event. This feature is provided to time-stamp the received CAN messages.

This feature is enabled by setting the CANCAP bit of the CAN I/O control register (CIOCON<4>). The message receive signal from the CAN module then takes the place of the events on RC2/CCP1.


## EXAMPLE 15-1: CHANGING BETWEEN CAPTURE PRESCALERS

```
CLRF CCP1CON, F ; Turn CCP module off

MOVLW NEW_CAPT_PS ; Load WREG with the
; new prescaler mode
; value and CCP ON

MOVWF CCP1CON ; Load CCP1CON with
; this value
```

#### FIGURE 15-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



## 15.3 Compare Mode

In Compare mode, the 16-bit CCPR1 and ECCPR1 register value is constantly compared against either the TMR1 register pair value or the TMR3 register pair value. When a match occurs, the CCP1 pin can have one of the following actions:

- · Driven high
- · Driven low
- Toggle output (high-to-low or low-to-high)
- · Remains unchanged

The action on the pin is based on the value of control bits CCP1M3:CCP1M0. At the same time, interrupt flag bit CCP1IF is set.

#### 15.3.1 CCP1 PIN CONFIGURATION

The user must configure the CCP1 pin as an output by clearing the appropriate TRISC bit.

Note: Clearing the CCP1CON register will force the CCP1 compare output latch to the default low level. This is not the data latch.

#### 15.3.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode, or Synchronized Counter mode, if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

#### 15.3.3 SOFTWARE INTERRUPT MODE

When generate software interrupt is chosen, the CCP1 pin is not affected. Only a CCP interrupt is generated (if enabled).

## 15.3.4 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated, which may be used to initiate an action.

The special event trigger output of CCP1 resets either the TMR1 or TMR3 register pair. Additionally, the ECCP1 special event trigger will start an A/D conversion if the A/D module is enabled.

Note: The special event trigger from the ECCP1 module will not set the Timer1 or Timer3 interrupt flag bits.

#### FIGURE 15-2: COMPARE MODE OPERATION BLOCK DIAGRAM




TABLE 15-3: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, TIMER1 AND TIMER3

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
TRISD	PORTD Da	ata Direction	Register						1111 1111	1111 1111
TMR1L	Holding Register for the Least Significant Byte of the 16-bit TMR1 Register									uuuu uuuu
TMR1H	Holding Re	gister for the	e Most Sign	ificant Byte	of the 16-bit	TMR1 Regi	ister		xxxx xxxx	uuuu uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00 0000	u-uu uuuu
CCPR1L	Capture/Co	mpare/PWN	/I Register 1	(LSB)					xxxx xxxx	uuuu uuuu
CCPR1H	Capture/Co	mpare/PWN	// Register 1	(MSB)					xxxx xxxx	uuuu uuuu
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	00 0000
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0 0000	-0-0 0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0 0000	-0-0 0000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 1111	-1-1 1111
TMR3L	Holding Re	gister for the	e Least Sigr	nificant Byte	of the 16-bi	t TMR3 Reg	gister		xxxx xxxx	uuuu uuuu
TMR3H	Holding Re	gister for the	e Most Sign	ificant Byte	of the 16-bit	TMR3 Regi	ister		xxxx xxxx	uuuu uuuu
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	uuuu uuuu

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by Capture and Timer1.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

#### 15.4 PWM Mode


In Pulse-Width Modulation (PWM) mode, the CCP1 pin produces up to a 10-bit resolution PWM output. Since the CCP1 pin is multiplexed with the PORTC data latch, the TRISC<2> bit must be cleared to make the CCP1 pin an output.

Note: Clearing the CCP1CON register will force the CCP1 PWM output latch to the default low level. This is not the PORTC I/O data latch.

Figure 15-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up the CCP module for PWM operation, see **Section 15.4.3** "**Setup for PWM Operation**".

## FIGURE 15-3: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 15-4) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

## FIGURE 15-4: PWM OUTPUT



#### 15.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula.

#### **EQUATION 15-1:**

PWM frequency is defined as 1/[PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- · TMR2 is cleared
- The CCP1 pin is set (exception: if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is latched from CCPR1L into CCPR1H

Note: The Timer2 postscaler (see Section 13.0 "Timer2 Module") is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### 15.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. The CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The following equation is used to calculate the PWM duty cycle in time.

## **EQUATION 15-2:**

PWM Duty Cycle = (CCPR1L:CCP1CON<5:4>) • Tosc • (TMR2 Prescale Value)

CCPR1L and CCP1CON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPR1H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPR1H register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation.

When the CCPR1H and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP1 pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by the following equation.

## **EQUATION 15-3:**

PWM Resolution (max) = 
$$\frac{\log\left(\frac{FOSC}{FPWM}\right)}{\log(2)}$$
 bits

**Note:** If the PWM duty cycle value is longer than the PWM period, the CCP1 pin will not be cleared.

#### 15.4.3 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- Set the PWM period by writing to the PR2 register.
- 2. Set the PWM duty cycle by writing to the CCPR1L register and CCP1CON<5:4> bits.
- 3. Make the CCP1 pin an output by clearing the TRISC<2> bit.
- 4. Set the TMR2 prescale value and enable Timer2 by writing to T2CON.
- 5. Configure the CCP1 module for PWM operation.

#### TABLE 15-4: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

PWM Frequency	2.44 kHz	9.76 kHz	39.06 kHz	156.3 kHz	312.5 kHz	416.6 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	0FFh	0FFh	0FFh	3Fh	1Fh	17h
Maximum Resolution (bits)	10	10	10	8	7	5.5

## TABLE 15-5: REGISTERS ASSOCIATED WITH PWM AND TIMER2

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on BOR	all o	e on ther sets
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111
TRISD	PORTD Da	ata Direction	Register						1111	1111	1111	1111
TMR2	Timer2 Mo	dule Registe	er						0000	0000	0000	0000
PR2	Timer2 Mo	dule Period	Register						1111	1111	1111	1111
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
CCPR1L	Capture/Compare/PWM Register1 (LSB)								xxxx	xxxx	uuuu	uuuu
CCPR1H	Capture/Co	ompare/PW	M Register1	I (MSB)					xxxx	xxxx	uuuu	uuuu
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00	0000	00	0000

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PWM and Timer2.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

# www.DataPIC18FXX8

NOTES:

## 16.0 ENHANCED CAPTURE/ COMPARE/PWM (ECCP) MODULE

Note: The ECCP (Enhanced Capture/Compare/PWM) module is only available on PIC18F448 and PIC18F458 devices.

This module contains a 16-bit register which can operate as a 16-bit Capture register, a 16-bit Compare register or a PWM Master/Slave Duty Cycle register.

The operation of the ECCP module differs from the CCP (discussed in detail in **Section 15.0 "Capture/Compare/PWM (CCP) Modules"**) with the addition of an Enhanced PWM module which allows for up to 4 output channels and user selectable polarity. These features are discussed in detail in **Section 16.5 "Enhanced PWM Mode"**. The module can also be programmed for automatic shutdown in response to various analog or digital events.

The control register for ECCP1 is shown in Register 16-1.

## REGISTER 16-1: ECCP1CON: ECCP1 CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0
bit 7			•	•	•	•	bit 0

#### bit 7-6 **EPWM1M<1:0>:** PWM Output Configuration bits

If ECCP1M<3:2> = 00, 01, 10:

xx = P1A assigned as Capture/Compare input; P1B, P1C, P1D assigned as port pins

#### If ECCP1M<3:2> = 11:

- 00 = Single output; P1A modulated; P1B, P1C, P1D assigned as port pins
- 01 = Full-bridge output forward; P1D modulated; P1A active; P1B, P1C inactive
- 10 = Half-bridge output; P1A, P1B modulated with deadband control; P1C, P1D assigned as port pins
- 11 = Full-bridge output reverse; P1B modulated; P1C active; P1A, P1D inactive

## bit 5-4 EDC1B<1:0>: PWM Duty Cycle Least Significant bits

## Capture mode:

Unused.

## Compare mode:

Unused.

#### PWM mode:

These bits are the two LSbs of the PWM duty cycle. The eight MSbs are found in ECCPR1L.

## bit 3-0 **ECCP1M<3:0>:** ECCP1 Mode Select bits

- 0000 = Capture/Compare/PWM off (resets ECCP module)
- 0001 = Unused (reserved)
- 0010 = Compare mode, toggle output on match (ECCP1IF bit is set)
- 0011 = Unused (reserved)
- 0100 = Capture mode, every falling edge
- 0101 = Capture mode, every rising edge
- 0110 = Capture mode, every 4th rising edge
- 0111 = Capture mode, every 16th rising edge
- 1000 = Compare mode, set output on match (ECCP1IF bit is set)
- 1001 = Compare mode, clear output on match (ECCP1IF bit is set)
- 1010 = Compare mode, ECCP1 pin is unaffected (ECCP1IF bit is set)
- 1011 = Compare mode, trigger special event (ECCP1IF bit is set; ECCP resets TMR1or TMR3 and starts an A/D conversion if the A/D module is enabled)
- 1100 = PWM mode; P1A, P1C active-high; P1B, P1D active-high
- 1101 = PWM mode; P1A, P1C active-high; P1B, P1D active-low
- 1110 = PWM mode; P1A, P1C active-low; P1B, P1D active-high
- 1111 = PWM mode; P1A, P1C active-low; P1B, P1D active-low

### Legend:

R = Readable bit	= Readable bit W = Writable bit		U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown				

## 16.1 ECCP1 Module

Enhanced Capture/Compare/PWM Register 1 (ECCPR1) is comprised of two 8-bit registers: ECCPR1L (low byte) and ECCPR1H (high byte). The ECCP1CON register controls the operation of ECCP1; the additional registers, ECCPAS and ECCP1DEL, control Enhanced PWM specific features. All registers are readable and writable.

Table 16-1 shows the timer resources for the ECCP module modes. Table 16-2 describes the interactions of the ECCP module with the standard CCP module.

In PWM mode, the ECCP module can have up to four available outputs, depending on which operating mode is selected. These outputs are multiplexed with PORTD and the Parallel Slave Port. Both the operating mode and the output pin assignments are configured by setting PWM output configuration bits, EPWM1M1:EPWM1M0 (ECCP1CON<7:6>). The specific pin assignments for the various output modes are shown in Table 16-3.

TABLE 16-1: ECCP1 MODE – TIMER RESOURCE

ECCP1 Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2

TABLE 16-2: INTERACTION OF CCP1 AND ECCP1 MODULES

ECCP1 Mode	CCP1 Mode	Interaction
Capture	Capture	TMR1 or TMR3 time base. Time base can be different for each CCP.
Capture	Compare	The compare could be configured for the special event trigger which clears either TMR1 or TMR3 depending upon which time base is used.
Compare	Compare	The compare(s) could be configured for the special event trigger which clears TMR1 or TMR3 depending upon which time base is used.
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).
PWM	Capture	None
PWM	Compare	None

TABLE 16-3: PIN ASSIGNMENTS FOR VARIOUS ECCP MODES

ECCP Mode <sup>(1)</sup>	ECCP1CON Configuration	RD4	RD5	RD6	RD7
Conventional CCP Compatible	00xx11xx	ECCP1	RD<5>, PSP<5>	RD<6>, PSP<6>	RD<7>, PSP<7>
Dual Output PWM <sup>(2)</sup>	10xx11xx	P1A	P1B	RD<6>, PSP<6>	RD<7>, PSP<7>
Quad Output PWM <sup>(2)</sup>	x1xx11xx	P1A	P1B	P1C	P1D

**Legend:** x = Don't care. Shaded cells indicate pin assignments not used by ECCP in a given mode.

Note 1: In all cases, the appropriate TRISD bits must be cleared to make the corresponding pin an output.

2: In these modes, the PSP I/O control for PORTD is overridden by P1B, P1C and P1D.

## 16.2 Capture Mode

The Capture mode of the ECCP module is virtually identical in operation to that of the standard CCP module as discussed in **Section 15.1 "CCP1 Module**". The differences are in the registers and port pins involved:

- The 16-bit Capture register is ECCPR1 (ECCPR1H and ECCPR1L);
- The capture event is selected by control bits ECCP1M3:ECCP1M0 (ECCP1CON<3:0>);
- The interrupt bits are ECCP1IE (PIE2<0>) and ECCP1IF (PIR2<0>); and
- The capture input pin is RD4 and its corresponding direction control bit is TRISD<4>.

Other operational details, including timer selection, output pin configuration and software interrupts, are exactly the same as the standard CCP module.

#### 16.2.1 CAN MESSAGE TIME-STAMP

The special capture event for the reception of CAN messages (Section 15.2.5 "CAN Message Time-Stamp") is not available with the ECCP module.

## 16.3 Compare Mode

The Compare mode of the ECCP module is virtually identical in operation to that of the standard CCP module as discussed in **Section 15.2 "Capture Mode**". The differences are in the registers and port pins as described in **Section 16.2 "Capture Mode**". All other details are exactly the same.

## 16.3.1 SPECIAL EVENT TRIGGER

Except as noted below, the special event trigger output of ECCP1 functions identically to that of the standard CCP module. It may be used to start an A/D conversion if the A/D module is enabled.

Note: The special event trigger from the ECCP1 module will not set the Timer1 or Timer3 interrupt flag bits.

TABLE 16-4: REGISTERS ASSOCIATED WITH ENHANCED CAPTURE, COMPARE, TIMER1 AND TIMER3

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR,	e on BOR	all c	e on other sets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0	0000	-0-0	0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0	0000	-0-0	0000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1	1111	-1-1	1111
TMR1L	Holding Register for the Least Significant Byte of the 16-bit TMR1 Register								xxxx	xxxx	uuuu	uuuu
TMR1H	Holding Register for the Most Significant Byte of the 16-bit TMR1 Register								xxxx	xxxx	uuuu	uuuu
T1CON	RD16	1	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00	0000	u-uu	uuuu
TMR3L	Holding Register for the Least Significant Byte of the 16-bit TMR3 Register							xxxx	xxxx	uuuu	uuuu	
TMR3H	Holding Register for the Most Significant Byte of the 16-bit TMR3 Register							xxxx	xxxx	uuuu	uuuu	
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000	0000	uuuu	uuuu
TRISD	PORTD Data Direction Register							1111	1111	1111	1111	
ECCPR1L	Capture/Compare/PWM Register1 (LSB)							xxxx	xxxx	uuuu	uuuu	
ECCPR1H	Capture/Compare/PWM Register1 (MSB)								xxxx	xxxx	uuuu	uuuu
ECCP1CON	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000	0000	0000	0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the ECCP module and Timer1.

#### 16.4 Standard PWM Mode

When configured in Single Output mode, the ECCP module functions identically to the standard CCP module in PWM mode as described in **Section 15.4** "**PWM Mode**". The differences in registers and ports are as described in **Section 16.2** "**Capture Mode**". In addition, the two Least Significant bits of the 10-bit PWM duty cycle value are represented by ECCP1CON<5:4>.

Note: When setting up single output PWM operations, users are free to use either of the processes described in Section 15.4.3 "Setup for PWM Operation" or Section 16.5.8 "Setup for PWM Operation". The latter is more generic, but will work for either single or multi-output PWM.

### 16.5 Enhanced PWM Mode

The Enhanced PWM mode provides additional PWM output options for a broader range of control applications. The module is an upwardly compatible version of the standard CCP module and is modified to provide up to four outputs, designated P1A through P1D. Users are also able to select the polarity of the signal (either active-high or active-low). The module's output mode and polarity are configured by setting the EPWM1M1:EPWM1M0 and ECCP1M3:ECCP1M0 bits of the ECCP1CON register (ECCP1CON<7:6> and ECCP1CON<3:0>, respectively).

Figure 16-1 shows a simplified block diagram of PWM operation. All control registers are double-buffered and are loaded at the beginning of a new PWM cycle (the period boundary when the assigned timer resets) in order to prevent glitches on any of the outputs. The exception is the PWM Delay register, ECCP1DEL, which is loaded at either the duty cycle boundary or the boundary period (whichever comes first). Because of the buffering, the module waits until the assigned timer resets instead of starting immediately. This means that Enhanced PWM waveforms do not exactly match the standard PWM waveforms, but are instead offset by one full instruction cycle (4 Tosc).

As before, the user must manually configure the appropriate TRISD bits for output.

### 16.5.1 PWM OUTPUT CONFIGURATIONS


The EPWM1M<1:0> bits in the ECCP1CON register allow one of four configurations:


- · Single Output
- Half-Bridge Output
- Full-Bridge Output, Forward mode
- Full-Bridge Output, Reverse mode

The Single Output mode is the standard PWM mode discussed in **Section 15.4 "PWM Mode"**. The Half-Bridge and Full-Bridge Output modes are covered in detail in the sections that follow.

The general relationship of the outputs in all configurations is summarized in Figure 16-2.

FIGURE 16-1: SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODULE





## FIGURE 16-2: PWM OUTPUT RELATIONSHIPS

## Relationships:

- Period = 4 \* Tosc \* (PR2 + 1) \* (TMR2 Prescale Value)
- Duty Cycle = Tosc \* (CCPR1L<7:0>:CCP1CON<5:4>) \* (TMR2 Prescale Value)
- Delay = 4 \* Tosc \* ECCP1DEL


#### 16.5.2 HALF-BRIDGE MODE

In the Half-Bridge Output mode, two pins are used as outputs to drive push-pull loads. The RD4/PSP4/ ECCP1/P1A pin has the PWM output signal, while the RD5/PSP5/P1B pin has the complementary PWM output signal (Figure 16-3). This mode can be used for half-bridge applications, as shown in Figure 16-4, or for full-bridge applications where four power switches are being modulated with two PWM signals.

In Half-Bridge Output mode, the programmable deadband delay can be used to prevent shoot-through current in bridge power devices. The value of register ECCP1DEL dictates the number of clock cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See Section 16.5.4 "Programmable Dead-Band Delay" for more details of the dead-band delay operations.

Since the P1A and P1B outputs are multiplexed with the PORTD<4> and PORTD<5> data latches, the TRISD<4> and TRISD<5> bits must be cleared to configure P1A and P1B as outputs.


**FIGURE 16-3:** HALF-BRIDGE PWM **OUTPUT** 



PR2 register.

2: Output signals are shown as asserted high.

**FIGURE 16-4: EXAMPLES OF HALF-BRIDGE OUTPUT MODE APPLICATIONS** 





#### **FULL-BRIDGE MODE** 16.5.3

In Full-Bridge Output mode, four pins are used as outputs; however, only two outputs are active at a time. In the Forward mode, pin RD4/PSP4/ECCP1/P1A is continuously active and pin RD7/PSP7/P1D is modulated. In the Reverse mode, RD6/PSP6/P1C pin is continuously active and RD5/PSP5/P1B pin is modulated. These are illustrated in Figure 16-5.

P1A, P1B, P1C and P1D outputs are multiplexed with the PORTD<4:7> data latches. The TRISD<4:7> bits must be cleared to make the P1A, P1B, P1C and P1D pins output.

**FIGURE 16-5: FULL-BRIDGE PWM OUTPUT** 





**FIGURE 16-6: EXAMPLE OF FULL-BRIDGE APPLICATION** 

#### 16.5.3.1 Direction Change in Full-Bridge Mode

In the Full-Bridge Output mode, the EPWM1M1 bit in the ECCP1CON register allows the user to control the forward/reverse direction. When the application firmware changes this direction control bit, the ECCP1 module will assume the new direction on the next PWM cycle. The current PWM cycle still continues, however, the non-modulated outputs, P1A and P1C signals, will transition to the new direction Tosc, 4 Tosc or 16 Tosc earlier (for T2CKRS<1:0> = 00, 01 or 1x, respectively) before the end of the period. During this transition cycle, the modulated outputs, P1B and P1D, will go to the inactive state (Figure 16-7).

Note that in the Full-Bridge Output mode, the ECCP module does not provide any dead-band delay. In general, since only one output is modulated at all times, dead-band delay is not required. However, there is a situation where a dead-band delay might be required. This situation occurs when all of the following conditions are true:


- The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- The turn-off time of the power switch, including the power device and driver circuit, is greater than turn-on time.

Figure 16-8 shows an example where the PWM direction changes from forward to reverse at a near 100% duty cycle. At time t1, the outputs P1A and P1D become inactive, while output P1C becomes active. In this example, since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current flows through power devices QB and QD (see Figure 16-6) for the duration of 't'. The same phenomenon will occur to power devices QA and QC for PWM direction change from reverse to forward.

If changing PWM direction at high duty cycle is required for an application, one of the following requirements must be met:


- Avoid changing PWM output direction at or near 100% duty cycle.
- Use switch drivers that compensate the slow turn off of the power devices. The total turn-off time (toff) of the power device and the driver must be less than the turn-on time (ton).

FIGURE 16-7: PWM DIRECTION CHANGE



- Note 1: The direction bit in the ECCP1 Control Register (ECCP1CON.EPWM1M1) is written any time during the PWM cycle.
  - 2: The P1A and P1C signals switch at intervals of Tosc, 4 Tosc or 16 Tosc, depending on the Timer2 prescaler value earlier when changing direction. The modulated P1B and P1D signals are inactive at this time.

FIGURE 16-8: PWM DIRECTION CHANGE AT NEAR 100% DUTY CYCLE



## 16.5.4 PROGRAMMABLE DEAD-BAND DELAY

In half-bridge or full-bridge applications, where all power switches are modulated at the PWM frequency at all times, the power switches normally require longer time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on and the other turned off), both switches will be on for a short period of time until one switch completely turns off. During this time, a very high current (*shoot-through current*) flows through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on the power switch is normally delayed to allow the other switch to completely turn off.

In the Half-Bridge Output mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 16-3 for illustration. The ECCP1DEL register (Register 16-2) sets the amount of delay.

#### 16.5.5 SYSTEM IMPLEMENTATION

When the ECCP module is used in the PWM mode, the application hardware must use the proper external pull-up and/or pull-down resistors on the PWM output pins. When the microcontroller powers up, all of the I/O pins are in the high-impedance state. The external pull-up and pull-down resistors must keep the power switch

devices in the off state until the microcontroller drives the I/O pins with the proper signal levels, or activates the PWM output(s).

#### 16.5.6 START-UP CONSIDERATIONS

Prior to enabling the PWM outputs, the P1A, P1B, P1C and P1D latches may not be in the proper states. Enabling the TRISD bits for output at the same time with the ECCP1 module may cause damage to the power switch devices. The ECCP1 module must be enabled in the proper output mode with the TRISD bits enabled as inputs. Once the ECCP1 completes a full PWM cycle, the P1A, P1B, P1C and P1D output latches are properly initialized. At this time, the TRISD bits can be enabled for outputs to start driving the power switch devices. The completion of a full PWM cycle is indicated by the TMR2IF bit going from a '0' to a '1'.

## 16.5.7 OUTPUT POLARITY CONFIGURATION

The ECCP1M<1:0> bits in the ECCP1CON register allow user to choose the logic conventions (asserted high/low) for each of the outputs.

The PWM output polarities must be selected before the PWM outputs are enabled. Charging the polarity configuration while the PWM outputs are active is not recommended since it may result in unpredictable operation.

#### REGISTER 16-2: ECCP1DEL: PWM DELAY REGISTER

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EPDC7 | EPDC6 | EPDC5 | EPDC4 | EPDC3 | EPDC2 | EPDC1 | EPDC0 |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 **EPDC<7:0>:** PWM Delay Count for Half-Bridge Output Mode bits Number of Fosc/4 (Tosc \* 4) cycles between the P1A transition and the P1B transition.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 16.5.8 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the ECCP1 module for PWM operation:

- 1. Configure the PWM module:
  - a) Disable the ECCP1/P1A, P1B, P1C and/or P1D outputs by setting the respective TRISD bits.
  - b) Set the PWM period by loading the PR2 register.
  - Set the PWM duty cycle by loading the ECCPR1L register and ECCP1CON<5:4> bits
  - d) Configure the ECCP1 module for the desired PWM operation by loading the ECCP1CON register with the appropriate value. With the ECCP1M<3:0> bits, select the active-high/low levels for each PWM output. With the EPWM1M<1:0> bits, select one of the available output modes.
  - e) For Half-Bridge Output mode, set the deadband delay by loading the ECCP1DEL register with the appropriate value.

- 2. Configure and start TMR2:
  - a) Clear the TMR2 interrupt flag bit by clearing the TMR2IF bit in the PIR1 register.
  - b) Set the TMR2 prescale value by loading the T2CKPS bits (T2CON<1:0>).
  - c) Enable Timer2 by setting the TMR2ON bit (T2CON<2>) register.
- 3. Enable PWM outputs after a new cycle has started:
  - Wait until TMR2 overflows (TMR2IF bit becomes a '1'). The new PWM cycle begins here
  - Enable the ECCP1/P1A, P1B, P1C and/or P1D pin outputs by clearing the respective TRISD bits.

#### TABLE 16-5: REGISTERS ASSOCIATED WITH ENHANCED PWM AND TIMER2

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR, B		all c	e on other sets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 0	000x	0000	000u
RCON	IPEN	_	_	RI	TO	PD	POR	BOR	01 1	.10q	0 0	011q
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 1	.111	-1-1	1111
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0 0	000	-0-0	0000
PIE2	_	CMIE	-	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0 0	000	-0-0	0000
TMR2	Timer2 Module Register								0000 0	000	0000	0000
PR2	Timer2 Module Period Register								1111 1	.111	1111	1111
T2CON	- TOUTPS3 TOUTPS2 TOUTPS1 TOUTPS0 TMR2ON T2CKPS1 T2CKPS0						-000 0	000	-000	0000		
TRISD	PORTD Data Direction Register							1111 1	.111	1111	1111	
ECCPR1H	Enhanced Capture/Compare/PWM Register 1 High Byte							xxxx x	xxx	uuuu	uuuu	
ECCPR1L	Enhanced Capture/Compare/PWM Register 1 Low Byte							xxxx x	xxx	uuuu	uuuu	
ECCP1CON	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000 0	000	0000	0000
ECCPAS	ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0	0000 0	000	0000	0000
ECCP1DEL	EPDC7	EPDC6	EPDC5	EPDC4	EPDC3	EPDC2	EPDC1	EPDC0	0000 0	0000	uuuu	uuuu

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the ECCP module.

## 16.6 Enhanced CCP Auto-Shutdown

When the ECCP is programmed for any of the PWM modes, the output pins associated with its function may be configured for auto-shutdown.

Auto-shutdown allows the internal output of either of the two comparator modules, or the external interrupt 0, to asynchronously disable the ECCP output pins. Thus, an external analog or digital event can discontinue an ECCP sequence. The comparator output(s) to be used is selected by setting the proper mode bits in the ECCPAS register. To use external interrupt INTO as a shutdown event, INTOIE must be set. To use either of the comparator module outputs as a shutdown event, corresponding comparators must be enabled. When a shutdown occurs, the selected output values (PSSACn, PSSBDn) are written to the ECCP port pins.

The internal shutdown signal is gated with the outputs and will immediately and asynchronously disable the outputs. If the internal shutdown is still in effect at the time a new cycle begins, that entire cycle is suppressed, thus eliminating narrow, glitchy pulses.

The ECCPASE bit is set by hardware upon a comparator event and can only be cleared in software. The ECCP outputs can be re-enabled only by clearing the ECCPASE bit.

The Auto-Shutdown mode can be manually entered by writing a '1' to the ECCPASE bit.

## REGISTER 16-3: ECCPAS: ENHANCED CAPTURE/COMPARE/PWM AUTO-SHUTDOWN CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0
bit 7							bit 0

bit 7 **ECCPASE:** ECCP Auto-Shutdown Event Status bit

0 = ECCP outputs enabled, no shutdown event

1 = A shutdown event has occurred, must be reset in software to re-enable ECCP

bit 6-4 ECCPAS<2:0>: ECCP Auto-Shutdown bits

000 = No auto-shutdown enabled, comparators have no effect on ECCP

001 = Comparator 1 output will cause shutdown

010 = Comparator 2 output will cause shutdown

011 = Either Comparator 1 or 2 can cause shutdown

100 = INTO

101 = INTO or Comparator 1 output

110 = INT0 or Comparator 2 output

111 = INT0 or Comparator 1 or Comparator 2 output

bit 3-2 **PSSACn:** Pins A and C Shutdown State Control bits

00 = Drive Pins A and C to '0'

01 = Drive Pins A and C to '1'

1x = Pins A and C tri-state

bit 1-0 PSSBDn: Pins B and D Shutdown State Control bits

00 = Drive Pins B and D to '0'

01 = Drive Pins B and D to '1'

1x = Pins B and D tri-state

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 17.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

# 17.1 Master SSP (MSSP) Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)
  - Full Master mode
  - Slave mode (with general address call)

The I<sup>2</sup>C interface supports the following modes in hardware:

- · Master mode
- Multi-Master mode
- · Slave mode

# 17.2 Control Registers

The MSSP module has three associated registers. These include a status register (SSPSTAT) and two control registers (SSPCON1 and SSPCON2). The use of these registers and their individual configuration bits differ significantly, depending on whether the MSSP module is operated in SPI or  $I^2C$  mode.

Additional details are provided under the individual sections.

#### 17.3 SPI Mode

The SPI mode allows 8 bits of data to be synchronously transmitted and received simultaneously. All four modes of SPI are supported. To accomplish communication, typically three pins are used:


- Serial Data Out (SDO) RC5/SDO
- Serial Data In (SDI) RC4/SDI/SDA
- Serial Clock (SCK) RC3/SCK/SCL

Additionally, a fourth pin may be used when in a Slave mode of operation:

Slave Select (SS) – RA5/AN4/SS/LVDIN

Figure 17-1 shows the block diagram of the MSSP module when operating in SPI mode.

# FIGURE 17-1: MSSP BLOCK DIAGRAM (SPI<sup>TM</sup> MODE)



#### 17.3.1 REGISTERS

The MSSP module has four registers for SPI mode operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible

SSPCON1 and SSPSTAT are the control and status registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

# REGISTER 17-1: SSPSTAT: MSSP STATUS REGISTER (SPI MODE)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/A	Р	S	R/W	UA	BF
bit 7							bit 0

#### bit 7 SMP: Sample bit

#### SPI Master mode:

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

#### SPI Slave mode:

SMP must be cleared when SPI is used in Slave mode.

- bit 6 CKE: SPI Clock Edge Select bit
  - 1 = Transmit occurs on transition from active to Idle clock state
  - 0 = Transmit occurs on transition from Idle to active clock state

**Note:** Polarity of clock state is set by the CKP bit (SSPCON1<4>).

bit 5 D/A: Data/Address bit

Used in I<sup>2</sup>C mode only.

bit 4 P: Stop bit

Used in  $I^2C$  mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.

bit 3 S: Start bit

Used in I<sup>2</sup>C mode only.

bit 2 R/W: Read/Write Information bit

Used in I<sup>2</sup>C mode only.

bit 1 UA: Update Address bit

Used in I<sup>2</sup>C mode only.

bit 0 BF: Buffer Full Status bit (Receive mode only)

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 17-2: SSPCON1: MSSP CONTROL REGISTER 1 (SPI MODE)

hit 7	I		I.	1		I.	bit 0
WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0
R/W-0							

- bit 7 WCOL: Write Collision Detect bit (Transmit mode only)
  - 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
  - 0 = No collision
- bit 6 SSPOV: Receive Overflow Indicator bit

#### SPI Slave mode:

- 1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. The user must read the SSPBUF even if only transmitting data to avoid setting overflow (must be cleared in software).
- 0 = No overflow

**Note:** In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

- bit 5 SSPEN: Synchronous Serial Port Enable bit
  - 1 = Enables serial port and configures SCK, SDO, SDI and SS as serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

Note: When enabled, these pins must be properly configured as input or output.

- bit 4 **CKP:** Clock Polarity Select bit
  - 1 = Idle state for clock is a high level
  - 0 = Idle state for clock is a low level
- bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits
  - 0101 = SPI Slave mode, clock = SCK pin, SS pin control disabled, SS can be used as I/O pin
  - 0100 = SPI Slave mode, clock = SCK pin, SS pin control enabled
  - 0011 = SPI Master mode, clock = TMR2 output/2
  - 0010 = SPI Master mode, clock = Fosc/64
  - 0001 = SPI Master mode, clock = Fosc/16
  - 0000 = SPI Master mode, clock = Fosc/4

**Note:** Bit combinations not specifically listed here are either reserved or implemented in I<sup>2</sup>C mode only.

#### 

#### 17.3.2 OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0> and SSPSTAT<7:6>). These control bits allow the following to be specified:

- · Master mode (SCK is the clock output)
- Slave mode (SCK is the clock input)
- · Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- Slave Select mode (Slave mode only)

The MSSP consists of a transmit/receive shift register (SSPSR) and a buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then, the Buffer Full detect bit BF (SSPSTAT<0>) and the interrupt flag bit SSPIF are set. This double-buffering of the received data (SSPBUF) allows the next byte to start reception before reading the data that was just received. Any write to the

SSPBUF register during transmission/reception of data will be ignored and the Write Collision detect bit, WCOL (SSPCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPBUF register completed successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. Buffer Full bit, BF (SSPSTAT<0>), indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. The SSPBUF must be read and/or written. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur. Example 17-1 shows the loading of the SSPBUF (SSPSR) for data transmission.

The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPBUF register. Additionally, the MSSP Status register (SSPSTAT) indicates the various status conditions.

# **EXAMPLE 17-1: LOADING THE SSPBUF (SSPSR) REGISTER**

		, ,
LOOP BTF	SS SSPSTAT, BF	;Has data been received(transmit complete)?
BRA	LOOP	;No
VOM	F SSPBUF, W	;WREG reg = contents of SSPBUF
MOV	WF RXDATA	;Save in user RAM, if data is meaningful
VOM	F TXDATA, W	;W reg = contents of TXDATA
VOM	WF SSPBUF	;New data to xmit

#### 17.3.3 ENABLING SPI I/O

To enable the serial port, SSP Enable bit, SSPEN (SSPCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, reinitialize the SSPCON registers and then, set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- SDI is automatically controlled by the SPI module
- · SDO must have TRISC<5> bit cleared
- SCK (Master mode) must have TRISC<3> bit cleared
- SCK (Slave mode) must have TRISC<3> bit set
- SS must have TRISA<5> bit set


Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

#### 17.3.4 TYPICAL CONNECTION

Figure 17-2 shows a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCK signal. Data is shifted out of both shift registers on their programmed clock edge and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends data Slave sends dummy data
- Master sends data Slave sends data
- Master sends dummy data Slave sends data

FIGURE 17-2: SPI™ MASTER/SLAVE CONNECTION



# 17.3.5 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK. The master determines when the slave (Processor 2, Figure 17-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode.


The clock polarity is selected by appropriately programming the CKP bit (SSPCON1<4>). This then, would give waveforms for SPI communication as shown in Figure 17-3, Figure 17-5 and Figure 17-6, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- Timer2 output/2

This allows a maximum data rate (at 40 MHz) of 10.00 Mbps.

Figure 17-3 shows the waveforms for Master mode. When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPBUF is loaded with the received data is shown.





#### 17.3.6 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the slave can transmit/receive data. When a byte is received, the device will wake-up from Sleep. Before enabling the module in SPI Slave mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit (SSPCON1<4>).

# 17.3.7 SLAVE SELECT SYNCHRONIZATION

The  $\overline{SS}$  pin allows a Synchronous Slave mode. The SPI must be in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON1<3:0> = 04h). The pin must not be driven low for the  $\overline{SS}$  pin to function as an input. The data latch


must be high. When the  $\overline{SS}$  pin is low, transmission and reception are enabled and the SDO pin is driven. When the  $\overline{SS}$  pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.

- Note 1: When the SPI is in Slave mode with SS pin control enabled (SSPCON1<3:0> = 0100), the SPI module will reset if the SS pin is set to VDD.
  - 2: If the SPI is used in Slave mode with CKE set, then the SS pin control must be enabled.


When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SS pin to a high level or clearing the SSPEN bit.

To emulate two-wire communication, the SDO pin can be connected to the SDI pin. When the SPI needs to operate as a receiver, the SDO pin can be configured as an input. This disables transmissions from the SDO. The SDI can always be left as an input (SDI function) since it cannot create a bus conflict.










# FIGURE 17-6: SPI™ MODE WAVEFORM (SLAVE MODE WITH CKE = 1)



#### 17.3.8 SLEEP OPERATION

In Master mode, all module clocks are halted and the transmission/reception will remain in that state until the device wakes from Sleep. After the device returns to normal mode, the module will continue to transmit/receive data.

In Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device from Sleep.

#### 17.3.9 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 17.3.10 BUS MODE COMPATIBILITY

Table 17-1 shows the compatibility between the standard SPI modes and the states of the CKP and CKE control bits.

TABLE 17-1: SPI™ BUS MODES

Standard SPI Mode	Control Bits State			
Terminology	CKP	CKE		
0, 0	0	1		
0, 1	0	0		
1, 0	1	1		
1, 1	1	0		

There is also an SMP bit which controls when the data is sampled.

TABLE 17-2: REGISTERS ASSOCIATED WITH SPI™ OPERATION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
TRISC	PORTC Date	ta Direction F	Register						1111 1111	1111 1111
TRISA	_	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	-111 1111	-111 1111
SSPBUF	Synchronou	ıs Serial Port	Receive B	uffer/Trans	mit Registe	r			xxxx xxxx	uuuu uuuu
SSPCON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
SSPSTAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	0000 0000	0000 0000

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the MSSP in SPI™ mode.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

# 17.4 I<sup>2</sup>C Mode


The MSSP module in I<sup>2</sup>C mode fully implements all master and slave functions (including general call support) and provides interrupts on Start and Stop bits in hardware to determine a free bus (multi-master function). The MSSP module implements the standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- Serial clock (SCL) RC3/SCK/SCL
- Serial data (SDA) RC4/SDI/SDA

The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

FIGURE 17-7: MSSP BLOCK DIAGRAM (I<sup>2</sup>CTM MODE)



#### 17.4.1 REGISTERS

The MSSP module has six registers for I<sup>2</sup>C operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Control Register 2 (SSPCON2)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible
- MSSP Address Register (SSPADD)

SSPCON1, SSPCON2 and SSPSTAT are the control and status registers in  $I^2C$  mode operation. The SSPCON1 and SSPCON2 registers are readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

SSPADD register holds the slave device address when the SSP is configured in I<sup>2</sup>C Slave mode. When the SSP is configured in Master mode, the lower seven bits of SSPADD act as the Baud Rate Generator reload value.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

# REGISTER 17-3: SSPSTAT: MSSP STATUS REGISTER (I<sup>2</sup>C MODE)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/A	Р	S	R/W	UA	BF
bit 7							bit 0

bit 7 SMP: Slew Rate Control bit

#### In Master or Slave mode:

- 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz)
- 0 = Slew rate control enabled for High-Speed mode (400 kHz)
- bit 6 CKE: SMBus Select bit

#### In Master or Slave mode:

- 1 = Enable SMBus specific inputs
- 0 = Disable SMBus specific inputs
- bit 5 D/A: Data/Address bit

#### In Master mode:

Reserved.

### In Slave mode:

- 1 = Indicates that the last byte received or transmitted was data
- 0 = Indicates that the last byte received or transmitted was address
- bit 4 P: Stop bit
  - 1 = Indicates that a Stop bit has been detected last
  - 0 = Stop bit was not detected last

**Note:** This bit is cleared on Reset and when SSPEN is cleared.

- bit 3 S: Start bit
  - 1 = Indicates that a Start bit has been detected last
  - 0 = Start bit was not detected last

Note: This bit is cleared on Reset and when SSPEN is cleared.

bit 2 R/W: Read/Write Information bit (I<sup>2</sup>C mode only)

#### In Slave mode:

- 1 = Read
- 0 = Write

**Note:** This bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next Start bit, Stop bit or not ACK bit.

# In Master mode:

- 1 = Transmit is in progress
- 0 = Transmit is not in progress

**Note:** ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Idle mode.

- bit 1 **UA:** Update Address bit (10-bit Slave mode only)
  - 1 = Indicates that the user needs to update the address in the SSPADD register
  - 0 = Address does not need to be updated
- bit 0 BF: Buffer Full Status bit

#### In Transmit mode:

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

#### <u>In Receive mode:</u>

- 1 = Data transmit in progress (does not include the ACK and Stop bits), SSPBUF is full
- 0 = Data transmit complete (does not include the ACK and Stop bits), SSPBUF is empty

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# REGISTER 17-4: SSPCON1: MSSP CONTROL REGISTER 1 (I<sup>2</sup>C MODE)

	R/W-0							
Γ	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0
ŀ	oit 7							bit 0

#### bit 7 WCOL: Write Collision Detect bit

# In Master Transmit mode:

- 1 = A write to the SSPBUF register was attempted while the I<sup>2</sup>C conditions were not valid for a transmission to be started (must be cleared in software)
- 0 = No collision

#### In Slave Transmit mode:

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision

### In Receive mode (Master or Slave modes):

This is a "don't care" bit.

#### bit 6 SSPOV: Receive Overflow Indicator bit

#### In Receive mode:

- 1 = A byte is received while the SSPBUF register is still holding the previous byte (must be cleared in software)
- 0 = No overflow

#### In Transmit mode:

This is a "don't care" bit in Transmit mode.

#### bit 5 SSPEN: Synchronous Serial Port Enable bit

- 1 = Enables the serial port and configures the SDA and SCL pins as the serial port pins
- 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, the SDA and SCL pins must be properly configured as input or output.

# bit 4 **CKP:** SCK Release Control bit

# In Slave mode:

- 1 = Release clock
- 0 = Holds clock low (clock stretch), used to ensure data setup time

#### In Master mode:

Unused in this mode.

#### bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits

- $1111 = I^2C$  Slave mode, 10-bit address with Start and Stop bit interrupts enabled
- $1110 = I^2C$  Slave mode, 7-bit address with Start and Stop bit interrupts enabled
- 1011 = I<sup>2</sup>C Firmware Controlled Master mode (Slave Idle)
- 1000 = I<sup>2</sup>C Master mode, clock = Fosc/(4 \* (SSPADD + 1))
- $0111 = I^2C$  Slave mode, 10-bit address
- $0110 = I^2C$  Slave mode, 7-bit address

**Note:** Bit combinations not specifically listed here are either reserved or implemented in SPI mode only.

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

#### SSPCON2: MSSP CONTROL REGISTER 2 (I<sup>2</sup>C MODE) REGISTER 17-5:

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
bit 7							bit 0

bit 0

- bit 7 **GCEN:** General Call Enable bit (Slave mode only)
  - 1 = Enable interrupt when a general call address (0000h) is received in the SSPSR
  - 0 = General call address disabled
- bit 6 ACKSTAT: Acknowledge Status bit (Master Transmit mode only)
  - 1 = Acknowledge was not received from slave
  - 0 = Acknowledge was received from slave
- **ACKDT:** Acknowledge Data bit (Master Receive mode only) bit 5
  - 1 = Not Acknowledge
  - 0 = Acknowledge

Note: Value that will be transmitted when the user initiates an Acknowledge sequence at the end of a receive.

- bit 4 **ACKEN:** Acknowledge Sequence Enable bit (Master Receive mode only)
  - 1 = Initiate Acknowledge sequence on SDA and SCL pins and transmit ACKDT data bit. Automatically cleared by hardware.
  - 0 = Acknowledge sequence Idle
- bit 3 **RCEN:** Receive Enable bit (Master Mode only)
  - 1 = Enables Receive mode for I<sup>2</sup>C
  - 0 = Receive Idle
- bit 2 **PEN:** Stop Condition Enable bit (Master mode only)
  - 1 = Initiate Stop condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Stop condition Idle
- bit 1 **RSEN:** Repeated Start Condition Enable bit (Master mode only)
  - 1 = Initiate Repeated Start condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Repeated Start condition Idle
- bit 0 SEN: Start Condition Enable/Stretch Enable bit

#### In Master mode:

- 1 = Initiate Start condition on SDA and SCL pins. Automatically cleared by hardware.
- 0 = Start condition Idle

#### In Slave mode:

- 1 = Clock stretching is enabled for both slave transmit and slave receive (stretch enabled)
- 0 = Clock stretching is enabled for slave transmit only (Legacy mode)

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the Idle mode, Note: this bit may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

#### 17.4.2 OPERATION

The MSSP module functions are enabled by setting MSSP Enable bit, SSPEN (SSPCON1<5>).

The SSPCON1 register allows control of the I<sup>2</sup>C operation. Four mode selection bits (SSPCON1<3:0>) allow one of the following I<sup>2</sup>C modes to be selected:

- I<sup>2</sup>C Master mode, clock = OSC/4 (SSPADD +1)
- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Slave mode (10-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Firmware Controlled Master mode, slave is Idle

Selection of any I<sup>2</sup>C mode with the SSPEN bit set forces the SCL and SDA pins to be open-drain, provided these pins are programmed to inputs by setting the appropriate TRISC bits. To ensure proper operation of the module, pull-up resistors must be provided externally to the SCL and SDA pins.

#### 17.4.3 SLAVE MODE

In Slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The I<sup>2</sup>C Slave mode hardware will always generate an interrupt on an address match. Through the mode select bits, the user can also choose to interrupt on Start and Stop bits.

When an address is matched, or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge (ACK) pulse and load the SSPBUF register with the received value currently in the SSPSR register.

Any combination of the following conditions will cause the MSSP module not to give this ACK pulse:

- The Buffer Full bit, BF (SSPSTAT<0>), was set before the transfer was received.
- The overflow bit, SSPOV (SSPCON1<6>), was set before the transfer was received.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. The BF bit is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the  $I^2C$  specification, as well as the requirement of the MSSP module, are shown in timing parameter #100 and parameter #101.

#### 17.4.3.1 Addressing

Once the MSSP module has been enabled, it waits for a Start condition to occur. Following the Start condition, the 8 bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- The SSPSR register value is loaded into the SSPBUF register.
- 2. The Buffer Full bit BF is set.
- 3. An ACK pulse is generated.
- MSSP Interrupt Flag bit, SSPIF (PIR1<3>), is set (interrupt is generated if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit Address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit  $R/\overline{W}$  (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7 through 9 for the slave-transmitter:

- Receive first (high) byte of address (bits SSPIF, BF and bit UA (SSPSTAT<1>) are set).
- Update the SSPADD register with second (low) byte of address (clears bit UA and releases the SCL line).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- Receive second (low) byte of address (bits SSPIF, BF and UA are set).
- Update the SSPADD register with the first (high) byte of address. If match releases SCL line, this will clear bit UA.
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive Repeated Start condition.
- Receive first (high) byte of address (bits SSPIF and BF are set).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

#### 17.4.3.2 Reception

When the  $R/\overline{W}$  bit of the address byte is clear and an address match occurs, the  $R/\overline{W}$  bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and the SDA line is held low ( $\overline{ACK}$ ).

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set or bit SSPOV (SSPCON1<6>) is set.

An MSSP interrupt is generated for each data transfer byte. Flag bit SSPIF (PIR1<3>) must be cleared in software. The SSPSTAT register is used to determine the status of the byte.


If SEN is enabled (SSPCON2<0> = 1), RC3/SCK/SCL will be held low (clock stretch) following each data transfer. The clock must be released by setting bit CKP (SSPCON1<4>). See **Section 17.4.4** "Clock **Stretching**" for more detail.


#### 17.4.3.3 Transmission


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and pin RC3/SCK/SCL is held low regardless of SEN (see Section 17.4.4 "Clock Stretching" for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPBUF register, which also loads the SSPSR register. Then, pin RC3/ SCK/SCL should be enabled by setting bit CKP (SSPCON1<4>). The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 17-9).


The  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line is high (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave monitors for another occurrence of the Start bit. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPBUF register. Again, pin RC3/SCK/SCL must be enabled by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared in software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.









#### 17.4.4 CLOCK STRETCHING

Both 7 and 10-bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCL pin to be held low at the end of each data receive sequence.

# 17.4.4.1 Clock Stretching for 7-bit Slave Receive Mode (SEN = 1)

In 7-bit Slave Receive mode, on the falling edge of the ninth clock at the end of the  $\overline{ACK}$  sequence, if the BF bit is set, the CKP bit in the SSPCON1 register is automatically cleared, forcing the SCL output to be held low. The CKP being cleared to '0' will assert the SCL line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the SSPBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring.

- Note 1: If the user reads the contents of the SSPBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
  - 2: The CKP bit can be set in software regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

# 17.4.4.2 Clock Stretching for 10-bit Slave Receive Mode (SEN = 1)

In 10-bit Slave Receive mode, during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address and following the receive of the second byte of the 10-bit address with the  $R/\overline{W}$  bit cleared to 'o'. The release of the clock line occurs upon updating SSPADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

Note: If the user polls the UA bit and clears it by updating the SSPADD register before the falling edge of the ninth clock occurs and if the user hasn't cleared the BF bit by reading the SSPBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

# 17.4.4.3 Clock Stretching for 7-bit Slave Transmit Mode

7-bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock if the BF bit is clear. This occurs regardless of the state of the SEN bit.

The user's ISR must set the CKP bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the SSPBUF before the master device can initiate another transmit sequence (see Figure 17-9).

- Note 1: If the user loads the contents of SSPBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
  - **2:** The CKP bit can be set in software regardless of the state of the BF bit.

# 17.4.4.4 Clock Stretching for 10-bit Slave Transmit Mode


In 10-bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-bit Slave Receive mode. The first two addresses are followed by a third address sequence which contains the high-order bits of the 10-bit address and the  $R/\overline{W}$  bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode and clock stretching is controlled by the BF flag as in 7-bit Slave Transmit mode (see Figure 17-11).


# 17.4.4.5 Clock Synchronization and the CKP bit


If a user clears the CKP bit, the SCL output is forced to '0'. Setting the CKP bit will not assert the SCL output low until the SCL output is already sampled low. If the user attempts to drive SCL low, the CKP bit will not

assert the SCL line until an external I<sup>2</sup>C master device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have deasserted SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 17-12).

FIGURE 17-12: CLOCK SYNCHRONIZATION TIMING







# 17.4.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the  $I^2C$  protocol. It consists of all '0's with  $R/\overline{W}=0$ .


The general call address is recognized when the General Call Enable bit (GCEN) is enabled (SSPCON2<7> set). Following a Start bit detect, 8 bits are shifted into the SSPSR and the address is compared against the SSPADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPSR is transferred to the SSPBUF, the BF flag bit is set (eighth bit) and on the falling edge of the ninth bit (ACK bit), the SSPIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPBUF. The value can be used to determine if the address was device specific or a general call address.

In 10-bit mode, the SSPADD is required to be updated for the second half of the address to match and the UA bit is set (SSPSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-bit Address mode, then the second half of the address is not necessary, the UA bit will not be set and the slave will begin receiving data after the Acknowledge (Figure 17-15).

FIGURE 17-15: SLAVE MODE GENERAL CALL ADDRESS SEQUENCE (7 OR 10-BIT ADDRESS MODE)



#### 17.4.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPCON1 and by setting the SSPEN bit. In Master mode, the SCL and SDA lines are manipulated by the MSSP hardware.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set or the bus is Idle, with both the S and P bits clear.

In Firmware Controlled Master mode, user code conducts all  $I^2C$  bus operations based on Start and Stop bit conditions.

Once Master mode is enabled, the user has six options.


- Assert a Start condition on SDA and SCL.
- Assert a Repeated Start condition on SDA and SCL.
- 3. Write to the SSPBUF register initiating transmission of data/address.
- 4. Configure the I<sup>2</sup>C port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a Stop condition on SDA and SCL.

Note: The MSSP module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPBUF register to initiate transmission before the Start condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur.

The following events will cause SSP Interrupt Flag bit, SSPIF, to be set (SSP interrupt if enabled):

- · Start condition
- Stop condition
- Data transfer byte transmitted/received
- · Acknowledge transmit
- Repeated Start

FIGURE 17-16: MSSP BLOCK DIAGRAM (I<sup>2</sup>C™ MASTER MODE)



# 17.4.6.1 I<sup>2</sup>C Master Mode Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition, or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Master Transmitter mode, serial data is output through SDA while SCL outputs the serial clock. The first byte transmitted contains the slave <u>address</u> of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the R/W bit. In this case, the R/W bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate receive bit. Serial data is received via SDA while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

The Baud Rate Generator used for the SPI mode operation is used to set the SCL clock frequency for either 100 kHz, 400 kHz or 1 MHz I<sup>2</sup>C operation. See **Section 17.4.7** "**Baud Rate Generator**" for more details.

A typical transmit sequence would go as follows:

- 1. The user generates a Start condition by setting the Start Enable bit, SEN (SSPCON2<0>).
- SSPIF is set. The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPBUF with the slave address to transmit.
- Address is shifted out the SDA pin until all 8 bits are transmitted.
- 5. The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- The user loads the SSPBUF with eight bits of data.
- Data is shifted out the SDA pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit
- 11. The user generates a Stop condition by setting the Stop Enable bit PEN (SSPCON2<2>).
- 12. Interrupt is generated once the Stop condition is complete.

#### 17.4.7 BAUD RATE GENERATOR

In I<sup>2</sup>C Master mode, the Baud Rate Generator (BRG) reload value is placed in the lower 7 bits of the SSPADD register (Figure 17-17). When a write occurs to SSPBUF, the Baud Rate Generator will automatically begin counting. The BRG counts down to 0 and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (TCY) on the Q2 and Q4 clocks. In I<sup>2</sup>C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by ACK), the internal clock will automatically stop counting and the SCL pin will remain in its last state.

Table 17-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

FIGURE 17-17: BAUD RATE GENERATOR BLOCK DIAGRAM




TABLE 17-3: I<sup>2</sup>C™ CLOCK RATE w/BRG

Fosc	Fcy	Fcy * 2	BRG Value	FSCL (2 Rollovers of BRG)
40 MHz	10 MHz	20 MHz	18h	400 kHz <sup>(1)</sup>
40 MHz	10 MHz	20 MHz	1Fh	312.5 kHz
40 MHz	10 MHz	20 MHz	63h	100 kHz
16 MHz	4 MHz	8 MHz	09h	400 kHz <sup>(1)</sup>
16 MHz	4 MHz	8 MHz	0Ch	308 kHz
16 MHz	4 MHz	8 MHz	27h	100 kHz
4 MHz	1 MHz	2 MHz	02h	333 kHz <sup>(1)</sup>
4 MHz	1 MHz	2 MHz	09h	100kHz
4 MHz	1 MHz	2 MHz	00h	1 MHz <sup>(1)</sup>


**Note 1:** The I<sup>2</sup>C<sup>™</sup> interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.

#### 17.4.7.1 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, deasserts the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the

SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 17-18).

#### FIGURE 17-18: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



# 17.4.8 I<sup>2</sup>C MASTER MODE START CONDITION TIMING

To initiate a Start condition, the user sets the Start condition enable bit, SEN (SSPCON2<0>). If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low, while SCL is high, is the Start condition and causes the S bit (SSPSTAT<3>) to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit (SSPCON2<0>) will be automatically cleared by hardware, the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.

Note:


If, at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs; the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.

### 17.4.8.1 WCOL Status Flag

If the user writes the SSPBUF when a Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Note: Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the Start condition is complete.

# FIGURE 17-19: FIRST START BIT TIMING



# 17.4.9 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit (SSPCON2<1>) is programmed high and the I<sup>2</sup>C logic module is in the Idle state. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded with the contents of SSPADD<5:0> and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. Following this, the RSEN bit (SSPCON2<1>) will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit (SSPSTAT<3>) will be set. The SSPIF bit will not be set until the Baud Rate Generator has timed out.

- **Note 1:** If RSEN is programmed while any other event is in progress, it will not take effect.
  - **2:** A bus collision during the Repeated Start condition occurs if:
    - SDA is sampled low when SCL goes from low-to-high.
    - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data '1'.


Immediately following the SSPIF bit getting set, the user may write the SSPBUF with the 7-bit address in 7-bit mode, or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional eight bits of address (10-bit mode) or eight bits of data (7-bit mode).

# 17.4.9.1 WCOL Status Flag

If the user writes the SSPBUF when a Repeated Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Note: Because queueing of events is not allowed, writing of the lower 5 bits of SSPCON2 is disabled until the Repeated Start condition is complete.

#### FIGURE 17-20: REPEATED START CONDITION WAVEFORM



# 17.4.10 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the Buffer Full flag bit BF and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted (see data hold time specification parameter #106). SCL is held low for one Baud Rate Generator rollover count (TBRG). Data should be valid before SCL is released high (see data setup time specification parameter #107). When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time, if an address match occurred, or if data was received properly. The status of  $\overline{ACK}$  is written into the ACKDT bit on the falling edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 17-21).

After the write to the SSPBUF, each bit of address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will deassert the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPIF bit is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

### 17.4.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPSTAT<0>) is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

### 17.4.10.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

WCOL must be cleared in software.

### 17.4.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPCON2<6>) is cleared when the slave has sent an Acknowledge  $(\overline{ACK}=0)$  and is set when the slave does not Acknowledge  $(\overline{ACK}=1)$ . A slave sends an Acknowledge when it has recognized its address (including a general call) or when the slave has properly received its data.

# 17.4.11 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN (SSPCON2<3>).

Note: The RCEN bit should be set after the ACK sequence is complete or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge Sequence Enable bit, ACKEN (SSPCON2<4>).

### 17.4.11.1 BF Status Flag


In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.

#### 17.4.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

# 17.4.11.3 WCOL Status Flag

If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).



I<sup>2</sup>C™ MASTER MODE WAVEFORM (RECEPTION, 7-BIT ADDRESS) FIGURE 17-22: Set SSPIF interrupt at end of Acknow-ledge sequence Bus master terminates transfer Set P bit (SSPSTAT<4>) and SSPIF PEN bit = 1 written here Set ACKEN, start Acknowledge sequence SDA = ACKDT = 1 ₫. ACK is not sent SSPOV is set because SSPBUF is still full Set SSPIF at end of receive 6 RCEN cleared automatically 72/3/4/55/6/7/8 D7\D6\D5\D4\D3\D2\D1 Data shifted in on falling edge of CLK Receiving Data from Slave Set SSPIF interrupt
at end of Acknowledge
sequence Cleared in software Last bit is shifted into SSPSR and contents are unloaded into SSPBUF Write to SSPCON2<4> to start Acknowledge sequence SDA = ACKDT (SSPCON2<5>) = 0 RCEN = 1, start next receive ACK from master SDA = ACKDT = 0 ACK 6 Cleared in software RCEN cleared automatically 00 71\2\3\4\5\6\7\8 Master configured as a receiver by programming SSPCON2<3> (RCEN = 1) Set SSPIF interrupt at end of receive Receiving Data from Slave D6 D5 D4 D3 D2 D1 Cleared in software 6 ACK from Slave ACK 72/3/4/5/6/7/8/9 Write to SSPBUF occurs here, start XMIT Transmit Address to Slave Cleared in software Write to SSPCON2<0> (SEN = 1), begin Start Condition SEN = 0  $\subseteq$ SDA = 0, SCL = 1 while CPU responds to SSPIF BF (SSPSTAT<0>) S SSPOV ACKEN SSPIF SDA SCL

# 17.4.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit. **ACKEN** (SSPCON2<4>). When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 17-23).

### 17.4.12.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).


#### 17.4.13 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN (SSPCON2<2>). At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to 0. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit (SSPSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 17-24).


# 17.4.13.1 WCOL Status Flag

If the user writes the SSPBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

#### FIGURE 17-23: ACKNOWLEDGE SEQUENCE WAVEFORM



# FIGURE 17-24: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 17.4.14 SLEEP OPERATION

While in Sleep mode, the I<sup>2</sup>C module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

#### 17.4.15 EFFECT OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 17.4.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the  $I^2C$  bus may be taken when the P bit (SSPSTAT<4>) is set, or the bus is Idle, with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed in hardware with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- Data Transfer
- · A Start Condition
- · A Repeated Start Condition
- An Acknowledge Condition

# 17.4.17 MULTI -MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = 0, then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag BCLIF and reset the I $^2$ C port to its Idle state (Figure 17-25).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the  $\rm I^2C$  bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the  $I^2C$  bus is free, the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the  $I^2C$  bus can be taken when the P bit is set in the SSPSTAT register or the bus is Idle and the S and P bits are cleared.





# 17.4.17.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the Start condition (Figure 17-26).
- SCL is sampled low before SDA is asserted low (Figure 17-27).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the Start condition is aborted,
- · the BCLIF flag is set and
- the MSSP module is reset to its Idle state (Figure 17-26).


The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded from SSPADD<6:0> and counts down to 0. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 17-28). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to 0 and during this time, if the SCL pins are sampled as '0', a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.


Note:

The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.










#### FIGURE 17-28: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



### 17.4.17.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- A low level is sampled on SDA when SCL goes from low level to high level.
- SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user deasserts SDA and the pin is allowed to float high, the BRG is loaded with SSPADD<6:0> and counts down to 0. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.


If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 17-29). If SDA is sampled high, the BRG is reloaded and begins

counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.


If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition (Figure 17-30).

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.





#### FIGURE 17-30: BUS COLLISION DURING A REPEATED START CONDITION (CASE 2)



### 17.4.17.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- b) After the SCL pin is deasserted, SCL is sampled low before SDA goes high.

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPADD<6:0> and counts down to 0. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 17-31). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 17-32).

FIGURE 17-31: BUS COLLISION DURING A STOP CONDITION (CASE 1)





FIGURE 17-32: BUS COLLISION DURING A STOP CONDITION (CASE 2)



NOTES:

# 18.0 ADDRESSABLE UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (USART)

The Universal Synchronous Asynchronous Receiver Transmitter (USART) module is one of the three serial I/O modules incorporated into PIC18FXX8 devices. (USART is also known as a Serial Communications Interface or SCI.) The USART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers, or it can be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs, etc.

The USART can be configured in the following modes:

- Asynchronous (full-duplex)
- Synchronous Master (half-duplex)
- Synchronous Slave (half-duplex).

The SPEN (RCSTA register) and the TRISC<7> bits have to be set and the TRISC<6> bit must be cleared in order to configure pins RC6/TX/CK and RC7/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter.

Register 18-1 shows the Transmit Status and Control register (TXSTA) and Register 18-2 shows the Receive Status and Control register (RCSTA).

#### REGISTER 18-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R-1	R/W-0
CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D
bit 7							bit 0

bit 7 CSRC: Clock Source Select bit

Asynchronous mode:

Don't care.

Synchronous mode:

- 1 = Master mode (clock generated internally from BRG)
- 0 = Slave mode (clock from external source)

bit 6 TX9: 9-bit Transmit Enable bit

1 = Selects 9-bit transmission

0 = Selects 8-bit transmission

bit 5 **TXEN**: Transmit Enable bit

1 = Transmit enabled

0 = Transmit disabled

**Note:** SREN/CREN overrides TXEN in Sync mode.

bit 4 SYNC: USART Mode Select bit

1 = Synchronous mode

0 = Asynchronous mode

bit 3 Unimplemented: Read as '0'

bit 2 BRGH: High Baud Rate Select bit

Asynchronous mode:

1 = High speed

0 = Low speed

Synchronous mode:

Unused in this mode.

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty

0 = TSR full

bit 0 **TX9D:** 9th bit of Transmit Data

Can be address/data bit or a parity bit.

#### Legend:

_0g0u.				
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

#### **REGISTER 18-2:** RCSTA: RECEIVE STATUS AND CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-x
SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
bit 7							bit 0

bit 0

bit 7 SPEN: Serial Port Enable bit

1 = Serial port enabled (configures RX/DT and TX/CK pins as serial port pins)

0 = Serial port disabled

bit 6 RX9: 9-bit Receive Enable bit

1 = Selects 9-bit reception

0 = Selects 8-bit reception

SREN: Single Receive Enable bit bit 5

Asynchronous mode:

Don't care.

Synchronous mode – Master:

1 = Enables single receive

0 = Disables single receive (this bit is cleared after reception is complete)

Synchronous mode - Slave:

Unused in this mode.

bit 4 CREN: Continuous Receive Enable bit

Asynchronous mode:

1 = Enables continuous receive

0 = Disables continuous receive

Synchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)

0 = Disables continuous receive

bit 3 ADDEN: Address Detect Enable bit

Asynchronous mode 9-bit (RX9 = 1):

1 = Enables address detection, enables interrupt and load of the receive buffer when RSR<8>

0 = Disables address detection, all bytes are received and ninth bit can be used as parity bit

bit 2 FERR: Framing Error bit

1 = Framing error (can be updated by reading RCREG register and receive next valid byte)

0 = No framing error

bit 1 **OERR**: Overrun Error bit

1 = Overrun error (can be cleared by clearing bit CREN)

0 = No overrun error

bit 0 RX9D: 9th bit of Received Data

Can be address/data bit or a parity bit.

Legend:

W = Writable bit R = Readable bit U = Unimplemented bit, read as '0'

n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 18.1 USART Baud Rate Generator (BRG)

The BRG supports both the Asynchronous and Synchronous modes of the USART. It is a dedicated 8-bit Baud Rate Generator. The SPBRG register controls the period of a free running, 8-bit timer. In Asynchronous mode, bit BRGH (TXSTA register) also controls the baud rate. In Synchronous mode, bit BRGH is ignored. Table 18-1 shows the formula for computation of the baud rate for different USART modes which only apply in Master mode (internal clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRG register can be calculated using the formula in Table 18-1. From this, the error in baud rate can be determined.

Example 18-1 shows the calculation of the baud rate error for the following conditions:

Fosc = 16 MHz
Desired Baud Rate = 9600
BRGH = 0
SYNC = 0

It may be advantageous to use the high baud rate (BRGH = 1) even for slower baud clocks. This is because the Fosc/(16(X + 1)) equation can reduce the baud rate error in some cases.

Writing a new value to the SPBRG register causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

#### 18.1.1 SAMPLING

The data on the RC7/RX/DT pin is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RX pin.

#### **EXAMPLE 18-1: CALCULATING BAUD RATE ERROR**

Desired Baud Rate = Fosc/(64 (X + 1))Solving for X: X = ((Fosc/Desired Baud Rate)/64) - 1 X = ((16000000/9600)/64) - 1 X = [25.042] = 25Calculated Baud Rate = 16000000/(64 (25 + 1)) = 9615Error = (Calculated Baud Rate - Desired Baud Rate)Desired Baud Rate = (9615 - 9600)/9600= 0.16%

#### **TABLE 18-1: BAUD RATE FORMULA**

SYNC	BRGH = 0 (Low Speed)	BRGH = 1 (High Speed)
0	(Asynchronous) Baud Rate = Fosc/(64 (X + 1))	Baud Rate = Fosc/(16 (X + 1))
1	(Synchronous) Baud Rate = Fosc/(4 (X + 1))	NA

**Legend:** X = value in SPBRG (0 to 255)

#### TABLE 18-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
SPBRG	Baud Rat	e Genera	ator Regis	ster				•	0000 0000	0000 0000

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used by the BRG.

TABLE 18-3: BAUD RATES FOR SYNCHRONOUS MODE

BAUD	Fosc =	40 MHz	SPBRG	33 1	ИНz	SPBRG	25 [	ИHz	SPBRG	20	MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)									
0.3	NA	-	-									
1.2	NA	-	-									
2.4	NA	-	-									
9.6	NA	-	-									
19.2	NA	-	-									
76.8	76.92	+0.16	129	77.10	+0.39	106	77.16	+0.47	80	76.92	+0.16	64
96	96.15	+0.16	103	95.93	-0.07	85	96.15	+0.16	64	96.15	+0.16	51
300	303.03	+1.01	32	294.64	-1.79	27	297.62	-0.79	20	294.12	-1.96	16
500	500	0	19	485.30	-2.94	16	480.77	-3.85	12	500	0	9
HIGH	10000	-	0	8250	-	0	6250	-	0	5000	-	0
LOW	39.06	-	255	32.23	-	255	24.41	-	255	19.53	-	255

BAUD	Fosc =	16 MHz	SPBRG	10 MHz		SPBRG	7.1590	9 MHz	SPBRG	5.0688 MHz		SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	NA	-	-	9.62	+0.23	185	9.60	0	131
19.2	19.23	+0.16	207	19.23	+0.16	129	19.24	+0.23	92	19.20	0	65
76.8	76.92	+0.16	51	75.76	-1.36	32	77.82	+1.32	22	74.54	-2.94	16
96	95.24	-0.79	41	96.15	+0.16	25	94.20	-1.88	18	97.48	+1.54	12
300	307.70	+2.56	12	312.50	+4.17	7	298.35	-0.57	5	316.80	+5.60	3
500	500	0	7	500	0	4	447.44	-10.51	3	422.40	-15.52	2
HIGH	4000	-	0	2500	-	0	1789.80	-	0	1267.20	-	0
LOW	15.63	-	255	9.77	-	255	6.99	-	255	4.95	-	255

BAUD	Fosc =	4 MHz	SPBRG	3.5795	45 MHz	SPBRG	1 N	1Hz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	0.30	+1.14	26
1.2	NA	-	-	NA	-	-	1.20	+0.16	207	1.17	-2.48	6
2.4	NA	-	-	NA	-	-	2.40	+0.16	103	2.73	+13.78	2
9.6	9.62	+0.16	103	9.62	+0.23	92	9.62	+0.16	25	8.20	-14.67	0
19.2	19.23	+0.16	51	19.04	-0.83	46	19.23	+0.16	12	NA	-	-
76.8	76.92	+0.16	12	74.57	-2.90	11	83.33	+8.51	2	NA	-	-
96	1000	+4.17	9	99.43	+3.57	8	83.33	-13.19	2	NA	-	-
300	333.33	+11.11	2	298.30	-0.57	2	250	-16.67	0	NA	-	-
500	500	0	1	447.44	-10.51	1	NA	-	-	NA	-	-
HIGH	1000	-	0	894.89	-	0	250	-	0	8.20	-	0
LOW	3.91	-	255	3.50	-	255	0.98	-	255	0.03	-	255

TABLE 18-4: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 0)

BAUD	Fosc =	40 MHz	SPBRG	33	ИНz	SPBRG	25	MHz	SPBRG	20 [	ИHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)									
0.3	NA	-	=	NA	-	=	NA	-	-	NA	-	-
1.2	NA	-	-									
2.4	NA	-	-	2.40	-0.07	214	2.40	-0.15	162	2.40	+0.16	129
9.6	9.62	+0.16	64	9.55	-0.54	53	9.53	-0.76	40	9.47	-1.36	32
19.2	18.94	-1.36	32	19.10	-0.54	26	19.53	+1.73	19	19.53	+1.73	15
76.8	78.13	+1.73	7	73.66	-4.09	6	78.13	+1.73	4	78.13	+1.73	3
96	89.29	-6.99	6	103.13	+7.42	4	97.66	+1.73	3	104.17	+8.51	2
300	312.50	+4.17	1	257.81	-14.06	1	NA	-	-	312.50	+4.17	0
500	625	+25.00	0	NA	-	-	NA	-	-	NA	-	-
HIGH	625	-	0	515.63	-	0	390.63	-	0	312.50	-	0
LOW	2.44	-	255	2.01	-	255	1.53	-	255	1.22	-	255

BAUD	Fosc =	16 MHz	SPBRG	10	MHz	SPBRG	7.1590	09 MHz	SPBRG	5.068	8 MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	1.20	+0.16	207	1.20	+0.16	129	1.20	+0.23	92	1.20	0	65
2.4	2.40	+0.16	103	2.40	+0.16	64	2.38	-0.83	46	2.40	0	32
9.6	9.62	+0.16	25	9.77	+1.73	15	9.32	-2.90	11	9.90	+3.13	7
19.2	19.23	+0.16	12	19.53	+1.73	7	18.64	-2.90	5	19.80	+3.13	3
76.8	83.33	+8.51	2	78.13	+1.73	1	111.86	+45.65	0	79.20	+3.13	0
96	83.33	-13.19	2	78.13	-18.62	1	NA	-	-	NA	-	-
300	250	-16.67	0	156.25	-47.92	0	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	250	-	0	156.25	-	0	111.86	-	0	79.20	-	0
LOW	0.98	-	255	0.61	-	255	0.44	-	255	0.31	-	255

BAUD	Fosc =	4 MHz	SPBRG	3.5795	45 MHz	SPBRG	1 1	ИНz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	0.30	-0.16	207	0.30	+0.23	185	0.30	+0.16	51	0.26	-14.67	1
1.2	1.20	+1.67	51	1.19	-0.83	46	1.20	+0.16	12	NA	-	-
2.4	2.40	+1.67	25	2.43	+1.32	22	2.23	-6.99	6	NA	-	-
9.6	8.93	-6.99	6	9.32	-2.90	5	7.81	-18.62	1	NA	-	-
19.2	20.83	+8.51	2	18.64	-2.90	2	15.63	-18.62	0	NA	-	-
76.8	62.50	-18.62	0	55.93	-27.17	0	NA	-	-	NA	-	-
96	NA	-	-	NA	-	-	NA	-	-	NA	-	-
300	NA	-	-	NA	-	-	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	62.50	-	0	55.93	-	0	15.63	-	0	0.51	-	0
LOW	0.24	-	255	0.22	-	255	0.06	-	255	0.002	-	255

TABLE 18-5: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 1)

BAUD	Fosc =	Fosc = 40 MHz SPBF		33 1	ИНz	SPBRG	25 I	ИНz	SPBRG	20 1	ИНz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	9.60	-0.07	214	9.59	-0.15	162	9.62	+0.16	129
19.2	19.23	+0.16	129	19.28	+0.39	106	19.30	+0.47	80	19.23	+0.16	64
76.8	75.76	-1.36	32	76.39	-0.54	26	78.13	+1.73	19	78.13	+1.73	15
96	96.15	+0.16	25	98.21	+2.31	20	97.66	+1.73	15	96.15	+0.16	12
300	312.50	+4.17	7	294.64	-1.79	6	312.50	+4.17	4	312.50	+4.17	3
500	500	0	4	515.63	+3.13	3	520.83	+4.17	2	416.67	-16.67	2
HIGH	2500	-	0	2062.50	-	0	1562.50	-	0	1250	-	0
LOW	9.77	-	255	8,06	-	255	6.10	-	255	4.88	-	255

BAUD	Fosc =	16 MHz	SPBRG	10 [	ИНz	SPBRG	7.1590	9 MHz	SPBRG	5.068	8 MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)									
0.3	NA	-	-									
1.2	NA	-	-									
2.4	NA	-	-	NA	-	-	2.41	+0.23	185	2.40	0	131
9.6	9.62	+0.16	103	9.62	+0.16	64	9.52	-0.83	46	9.60	0	32
19.2	19.23	+0.16	51	18.94	-1.36	32	19.45	+1.32	22	18.64	-2.94	16
76.8	76.92	+0.16	12	78.13	+1.73	7	74.57	-2.90	5	79.20	+3.13	3
96	100	+4.17	9	89.29	-6.99	6	89.49	-6.78	4	105.60	+10.00	2
300	333.33	+11.11	2	312.50	+4.17	1	447.44	+49.15	0	316.80	+5.60	0
500	500	0	1	625	+25.00	0	447.44	-10.51	0	NA	-	-
HIGH	1000	-	0	625	-	0	447.44	-	0	316.80	-	0
LOW	3.91	-	255	2.44	-	255	1.75	-	255	1.24	-	255

BAUD	Fosc =	4 MHz	SPBRG	3.5795	45 MHz	SPBRG	1 M	ЛНz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	0.30	+0.16	207	0.29	-2.48	6
1.2	1.20	+0.16	207	1.20	+0.23	185	1.20	+0.16	51	1.02	-14.67	1
2.4	2.40	+0.16	103	2.41	+0.23	92	2.40	+0.16	25	2.05	-14.67	0
9.6	9.62	+0.16	25	9.73	+1.32	22	8.93	-6.99	6	NA	-	-
19.2	19.23	+0.16	12	18.64	-2.90	11	20.83	+8.51	2	NA	-	-
76.8	NA	-	-	74.57	-2.90	2	62.50	-18.62	0	NA	-	-
96	NA	-	-	111.86	+16.52	1	NA	-	-	NA	-	-
300	NA	-	-	223.72	-25.43	0	NA	-	-	NA	-	-
500	NA	-	-	NA	-	_	NA	-	-	NA	-	-
HIGH	250	-	0	55.93	-	0	62.50	-	0	2.05	-	0
LOW	0.98	-	255	0.22	-	255	0.24	-	255	0.008	-	255

#### 18.2 USART Asynchronous Mode

In this mode, the USART uses standard Non-Returnto-Zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8 bits. An on-chip dedicated 8-bit Baud Rate Generator can be used to derive standard baud rate frequencies from the oscillator. The USART transmits and receives the LSb first. The USART's transmitter and receiver are functionally independent but use the same data format and baud rate. The Baud Rate Generator produces a clock, either x16 or x64 of the bit shift rate, depending on the BRGH bit (TXSTA register). Parity is not supported by the hardware but can be implemented in software (and stored as the ninth data bit). Asynchronous mode is stopped during Sleep.

Asynchronous mode is selected by clearing the SYNC bit (TXSTA register).

The USART Asynchronous module consists of the following important elements:

- · Baud Rate Generator
- Sampling Circuit
- · Asynchronous Transmitter
- · Asynchronous Receiver.

### 18.2.1 USART ASYNCHRONOUS TRANSMITTER

The USART transmitter block diagram is shown in Figure 18-1. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The TSR register obtains its data from the Read/Write Transmit Buffer register (TXREG). The TXREG register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREG register (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG register is empty and flag bit TXIF (PIR1 register) is set. This

interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1 register). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in software. It will reset only when new data is loaded into the TXREG register. While flag bit, TXIF, indicated the status of the TXREG register, another bit, TRMT (TXSTA register), shows the status of the TSR register. Status bit TRMT is a read-only bit which is set when the TSR register is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty.

- **Note 1:** The TSR register is not mapped in data memory, so it is not available to the user.
  - **2:** Flag bit TXIF is set when enable bit TXEN is set.

Steps to follow when setting up an Asynchronous Transmission:

- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH (Section 18.1 "USART Baud Rate Generator (BRG)").
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set transmit bit TX9. Can be used as address/data bit.
- 5. Enable the transmission by setting bit TXEN which will also set bit TXIF.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Load data to the TXREG register (starts transmission).

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG. The flag bit becomes valid in the second instruction cycle following the load instruction.

#### FIGURE 18-1: USART TRANSMIT BLOCK DIAGRAM





FIGURE 18-2: ASYNCHRONOUS TRANSMISSION



#### FIGURE 18-3: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)




TABLE 18-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value or POR, BO		Value all o	ther
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000 000	)x	0000	000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 000	0 (	0000	0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 000	0 (	0000	0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 111	.1	1111	1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000	)x	0000	000u
TXREG	USART Tra	ansmit Regis	ter						0000 000	0 0	0000	0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -01	.0	0000	-010
SPBRG	Baud Rate	Generator F	Register						0000 000	0 0	0000	0000

 $\textbf{Legend:} \quad \textbf{x} = \text{unknown, -= unimplemented locations read as `0'}. \label{eq:continuous} \textbf{Shaded cells are not used for asynchronous transmission.}$ 

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

### 18.2.2 USART ASYNCHRONOUS RECEIVER

The receiver block diagram is shown in Figure 18-4. The data is received on the RC7/RX/DT pin and drives the data recovery block. The data recovery block is actually a high-speed shifter, operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

Steps to follow when setting up an Asynchronous Reception:

- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH (Section 18.1 "USART Baud Rate Generator (BRG)").
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit RCIE.
- 4. If 9-bit reception is desired, set bit RX9.
- 5. Enable the reception by setting bit CREN.
- Flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing enable bit CREN.

### 18.2.3 SETTING UP 9-BIT MODE WITH ADDRESS DETECT

This mode would typically be used in RS-485 systems. Steps to follow when setting up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is required, set the BRGH bit.
- Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If interrupts are required, set the RCEN bit and select the desired priority level with the RCIP bit.
- 4. Set the RX9 bit to enable 9-bit reception.
- 5. Set the ADDEN bit to enable address detect.
- 6. Enable reception by setting the CREN bit.
- 7. The RCIF bit will be set when reception is complete. The interrupt will be Acknowledged if the RCIE and GIE bits are set.
- 8. Read the RCSTA register to determine if any error occurred during reception, as well as read bit 9 of data (if applicable).
- Read RCREG to determine if the device is being addressed.
- 10. If any error occurred, clear the CREN bit.
- 11. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.

#### FIGURE 18-4: USART RECEIVE BLOCK DIAGRAM




FIGURE 18-5: ASYNCHRONOUS RECEPTION




TABLE 18-7: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
RCREG	USART Rec	eive Register	•						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate C	Generator Re	gister						0000 0000	0000 0000

**Legend:** x = unknown, - = unimplemented locations read as '0'. Shaded cells are not used for asynchronous reception.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

### 18.3 USART Synchronous Master Mode

In Synchronous Master mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTA register). In addition, enable bit SPEN (RCSTA register) is set in order to configure the RC6/TX/CK and RC7/RX/DT I/O pins to CK (clock) and DT (data) lines, respectively. The Master mode indicates that the processor transmits the master clock on the CK line. The Master mode is entered by setting bit CSRC (TXSTA register).

### 18.3.1 USART SYNCHRONOUS MASTER TRANSMISSION

The USART transmitter block diagram is shown in Figure 18-1. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The shift register obtains its data from the Read/Write Transmit Buffer register (TXREG). The TXREG register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREG (if available). Once the TXREG register transfers the data to the TSR register (occurs in one Tcy), the TXREG is empty and interrupt bit TXIF (PIR1 register) is set. The interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1 register). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in

software. It will reset only when new data is loaded into the TXREG register. While flag bit, TXIF, indicates the status of the TXREG register, another bit, TRMT (TXSTA register), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory, so it is not available to the user.

Steps to follow when setting up a Synchronous Master Transmission:

- Initialize the SPBRG register for the appropriate baud rate (Section 18.1 "USART Baud Rate Generator (BRG)").
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- 5. Enable the transmission by setting bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Start transmission by loading data to the TXREG register.

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG. The flag bit becomes valid in the second instruction cycle following the load instruction.


TABLE 18-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
TXREG	USART Trai	nsmit Registe	er						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate (	Generator Re	gister					•	0000 0000	0000 0000


Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master transmission.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

#### FIGURE 18-6: SYNCHRONOUS TRANSMISSION



#### FIGURE 18-7: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)



### 18.3.2 USART SYNCHRONOUS MASTER RECEPTION

Once Synchronous Master mode is selected, reception is enabled by setting either enable bit SREN (RCSTA register) or enable bit CREN (RCSTA register). Data is sampled on the RC7/RX/DT pin on the falling edge of the clock. If enable bit SREN is set, only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence.

Steps to follow when setting up a Synchronous Master Reception:

- 1. Initialize the SPBRG register for the appropriate baud rate (Section 18.1 "USART Baud Rate Generator (BRG)").
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. Ensure bits CREN and SREN are clear.
- 4. If interrupts are desired, set enable bit RCIE.
- 5. If 9-bit reception is desired, set bit RX9.
- 6. If a single reception is required, set bit SREN. For continuous reception, set bit CREN.
- 7. Interrupt flag bit RCIF will be set when reception is complete and an interrupt will be generated if the enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.


TABLE 18-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
RCREG	USART Red	ceive Registe	r						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register							0000 0000	0000 0000	

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master reception.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

FIGURE 18-8: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)



#### 18.4 USART Synchronous Slave Mode

Synchronous Slave mode differs from the Master mode in that the shift clock is supplied externally at the RC6/TX/CK pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in Sleep mode. Slave mode is entered by clearing bit CSRC (TXSTA register).

### 18.4.1 USART SYNCHRONOUS SLAVE TRANSMIT

The operation of the Synchronous Master and Slave modes are identical, except in the case of the Sleep mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- The first word will immediately transfer to the TSR register and transmit.
- b) The second word will remain in TXREG register.
- c) Flag bit TXIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREG register will transfer the second word to the TSR and flag bit TXIF will be set.
- e) If enable bit TXIE is set, the interrupt will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

Steps to follow when setting up a Synchronous Slave Transmission:

- Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. Clear bits CREN and SREN.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- Enable the transmission by setting enable bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Start transmission by loading data to the TXREG register.

### 18.4.2 USART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical, except in the case of the Sleep mode and bit SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting bit CREN prior to the SLEEP instruction, then a word may be received during Sleep. On completely receiving the word, the RSR register will transfer the data to the RCREG register and if enable bit RCIE bit is set, the interrupt generated will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

Steps to follow when setting up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. If interrupts are desired, set enable bit RCIE.
- 3. If 9-bit reception is desired, set bit RX9.
- 4. To enable reception, set enable bit CREN.
- Flag bit RCIF will be set when reception is complete. An interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 7. Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.

TABLE 18-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
TXREG	USART Trai	nsmit Registe	er						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate (	Generator Re	gister		•	•		•	0000 0000	0000 0000

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous slave transmission.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

TABLE 18-11: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
RCREG	USART Red	ceive Registe	r						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register								0000 0000	0000 0000

 $\textbf{Legend:} \quad \textbf{x} = \text{unknown, -= unimplemented, read as `0'}. Shaded cells are not used for synchronous slave reception.$ 

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

NOTES:

#### 19.0 CAN MODULE

#### 19.1 Overview

The Controller Area Network (CAN) module is a serial interface, useful for communicating with other peripherals or microcontroller devices. This interface/protocol was designed to allow communications within noisy environments.

The CAN module is a communication controller, implementing the CAN 2.0 A/B protocol as defined in the BOSCH specification. The module will support CAN 1.2, CAN 2.0A, CAN 2.0B Passive and CAN 2.0B Active versions of the protocol. The module implementation is a full CAN system. The CAN specification is not covered within this data sheet. The reader may refer to the BOSCH CAN specification for further details.

The module features are as follows:

- Complies with ISO CAN Conformance Test
- Implementation of the CAN protocol CAN 1.2, CAN 2.0A and CAN 2.0B
- · Standard and extended data frames
- · 0-8 bytes data length
- Programmable bit rate up to 1 Mbit/sec
- Support for remote frames
- Double-buffered receiver with two prioritized received message storage buffers
- 6 full (standard/extended identifier) acceptance filters, 2 associated with the high priority receive buffer and 4 associated with the low priority receive buffer
- 2 full acceptance filter masks, one each associated with the high and low priority receive buffers
- Three transmit buffers with application specified prioritization and abort capability
- Programmable wake-up functionality with integrated low-pass filter
- Programmable Loopback mode supports self-test operation
- Signaling via interrupt capabilities for all CAN receiver and transmitter error states
- · Programmable clock source
- Programmable link to timer module for time-stamping and network synchronization
- · Low-power Sleep mode

#### 19.1.1 OVERVIEW OF THE MODULE

The CAN bus module consists of a protocol engine and message buffering and control. The CAN protocol engine handles all functions for receiving and transmitting messages on the CAN bus. Messages are transmitted by first loading the appropriate data registers. Status and errors can be checked by reading the appropriate registers. Any message detected on the CAN bus is checked for errors and then matched against filters to see if it should be received and stored in one of the 2 receive registers.

The CAN module supports the following frame types:


- · Standard Data Frame
- · Extended Data Frame
- Remote Frame
- Error Frame
- · Overload Frame Reception
- · Interframe Space

CAN module uses RB3/CANRX and RB2/CANTX/INT2 pins to interface with CAN bus. In order to configure CANRX and CANTX as CAN interface:

- bit TRISB<3> must be set;
- bit TRISB<2> must be cleared.

#### 19.1.2 TRANSMIT/RECEIVE BUFFERS

The PIC18FXX8 has three transmit and two receive buffers, two acceptance masks (one for each receive buffer) and a total of six acceptance filters. Figure 19-1 is a block diagram of these buffers and their connection to the protocol engine.



#### 19.2 CAN Module Registers

**Note:** Not all CAN registers are available in the Access Bank.

There are many control and data registers associated with the CAN module. For convenience, their descriptions have been grouped into the following sections:

- · Control and Status Registers
- Transmit Buffer Registers (Data and Control)
- Receive Buffer Registers (Data and Control)
- · Baud Rate Control Registers
- I/O Control Register
- · Interrupt Status and Control Registers

### 19.2.1 CAN CONTROL AND STATUS REGISTERS

The registers described in this section control the overall operation of the CAN module and show its operational status.

#### REGISTER 19-1: CANCON: CAN CONTROL REGISTER

R/W-1	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0
REQOP2	REQOP1	REQOP0	ABAT	WIN2	WIN1	WIN0	_
bit 7							bit 0

#### bit 7-5 **REQOP2:REQOP0:** Request CAN Operation Mode bits

1xx = Request Configuration mode

011 = Request Listen Only mode

010 = Request Loopback mode

001 = Request Disable mode

000 = Request Normal mode

#### bit 4 ABAT: Abort All Pending Transmissions bit

1 = Abort all pending transmissions (in all transmit buffers)

0 = Transmissions proceeding as normal

#### bit 3-1 WIN2:WIN0: Window Address bits

This selects which of the CAN buffers to switch into the Access Bank area. This allows access to the buffer registers from any data memory bank. After a frame has caused an interrupt, the ICODE2:ICODE0 bits can be copied to the WIN2:WIN0 bits to select the correct buffer. See Example 19-1 for code example.

111 = Receive Buffer 0

110 = Receive Buffer 0

101 = Receive Buffer 1

100 = Transmit Buffer 0

011 = Transmit Buffer 1

010 = Transmit Buffer 2

001 = Receive Buffer 0 000 = Receive Buffer 0

bit 0 **Unimplemented:** Read as '0'

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-2: CANSTAT: CAN STATUS REGISTER

R-1	R-0	R-0	U-0	R-0	R-0	R-0	U-0
OPMODE2	OPMODE1	OPMODE0	-	ICODE2	ICODE1	ICODE0	
bit 7							bit 0

#### bit 7-5 **OPMODE2:OPMODE0:** Operation Mode Status bits

111 = Reserved

110 = Reserved

101 = Reserved

100 = Configuration mode 011 = Listen Only mode

010 = Loopback mode

001 = Disable mode

000 = Normal mode

Note: Before the device goes into Sleep mode, select Disable mode.

#### bit 4 **Unimplemented:** Read as '0'

#### bit 3-1 ICODE2:ICODE0: Interrupt Code bits

When an interrupt occurs, a prioritized coded interrupt value will be present in the ICODE2:ICODE0 bits. These codes indicate the source of the interrupt. The ICODE2:ICODE0 bits can be copied to the WIN2:WIN0 bits to select the correct buffer to map into the Access Bank area. See Example 19-1 for code example.

111 = Wake-up on interrupt

110 = RXB0 interrupt

101 = RXB1 interrupt

100 = TXB0 interrupt

011 = TXB1 interrupt

010 = TXB2 interrupt

001 = Error interrupt

000 = No interrupt

bit 0 Unimplemented: Read as '0'

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### EXAMPLE 19-1: WIN AND ICODE BITS USAGE IN INTERRUPT SERVICE ROUTINE TO ACCESS TX/RX BUFFERS

```
; Save application required context.
   ; Poll interrupt flags and determine source of interrupt
   ; This was found to be CAN interrupt
   ; TempCANCON and TempCANSTAT are variables defined in Access Bank low
   MOVFF CANCON, TempCANCON
                                       ; Save CANCON.WIN bits
                                        ; This is required to prevent CANCON
                                        ; from corrupting CAN buffer access
                                        ; in-progress while this interrupt
                                        ; occurred
   MOVFF CANSTAT, TempCANSTAT
                                        ; Save CANSTAT register
                                        ; This is required to make sure that
                                        ; we use same CANSTAT value rather
                                        ; than one changed by another CAN
                                        ; interrupt.
   MOVF
          TempCANSTAT, W
                                       ; Retrieve ICODE bits
   ANDLW b'00001110'
   ADDWF PCL, F
                                       ; Perform computed GOTO
                                       ; to corresponding interrupt cause
   BRA
          NoInterrupt
                                       ; 000 = No interrupt
   BRA
        ErrorInterrupt
                                      ; 001 = Error interrupt
                                      ; 010 = TXB2 interrupt
          TXB2Interrupt
   BRA
                                       ; 011 = TXB1 interrupt
   BRA
          TXB1Interrupt
                                       ; 100 = TXB0 interrupt
   BRA
          TXB0Interrupt
   BRA
          RXB1Interrupt
                                       ; 101 = RXB1 interrupt
                                       ; 110 = RXB0 interrupt
   BRA
          RXB0Interrupt
                                        ; 111 = Wake-up on interrupt
WakeupInterrupt
   BCF
          PIR3, WAKIF
                                       ; Clear the interrupt flag
   ; User code to handle wake-up procedure
   ; Continue checking for other interrupt source or return from here
NoInterrupt
                                        ; PC should never vector here. User may
                                        ; place a trap such as infinite loop or pin/port
                                        ; indication to catch this error.
ErrorInterrupt
   BCF PIR3, ERRIF
                                       ; Clear the interrupt flag
                                        ; Handle error.
   RETFIE
TXB2Interrupt
   BCF PIR3, TXB2IF
                                       ; Clear the interrupt flag
   GOTO AccessBuffer
TXB1Interrupt
   BCF PIR3, TXB1IF
                                       ; Clear the interrupt flag
   GOTO AccessBuffer
TXB0Interrupt
   BCF
          PIR3, TXB0IF
                                       ; Clear the interrupt flag
         AccessBuffer
   GOTO
RXB1Interrupt
   BCF PIR3, RXB1IF
                                       ; Clear the interrupt flag
   GOTO Accessbuffer
```

# EXAMPLE 19-1: WIN AND ICODE BITS USAGE IN INTERRUPT SERVICE ROUTINE TO ACCESS TX/RX BUFFERS (CONTINUED)

```
RXB0Interrupt
   BCF
         PIR3, RXB0IF
                                        ; Clear the interrupt flag
   GOTO
         AccessBuffer
AccessBuffer
                                        ; This is either TX or RX interrupt
   ; Copy CANCON.ICODE bits to CANSTAT.WIN bits
          CANCON, W
                                        ; Clear CANCON.WIN bits before copying
   MOVF
                                        ; new ones.
   ANDLW b'11110001'
                                        ; Use previously saved CANCON value to
                                        ; make sure same value.
   MOVWF CANCON
                                        ; Copy masked value back to TempCANCON
          TempCANSTAT, W
                                       ; Retrieve ICODE bits
   MOVF
                                        ; Use previously saved CANSTAT value
   ANDLW b'00001110'
                                        ; to make sure same value.
   IORWF CANCON
                                        ; Copy ICODE bits to WIN bits.
                                        ; Copy the result to actual CANCON
   ; Access current buffer ...
   ; User code
   ; Restore CANCON.WIN bits
   MOVF CANCON, W
                                        ; Preserve current non WIN bits
   ANDLW b'11110001'
   IORWF TempCANCON, W
                                        ; Restore original WIN bits
   MOVWF CANCON
   ; Do not need to restore CANSTAT - it is read-only register.
   ; Return from interrupt or check for another module interrupt source
```

#### REGISTER 19-3: COMSTAT: COMMUNICATION STATUS REGISTER

R/C-0	R/C-0	R-0	R-0	R-0	R-0	R-0	R-0
RXB0OVFL	RXB10VFL	TXBO	TXBP	RXBP	TXWARN	RXWARN	EWARN
bit 7							bit 0

bit 7 RXB0OVFL: Receive Buffer 0 Overflow bit

1 = Receive Buffer 0 overflowed

0 = Receive Buffer 0 has not overflowed

bit 6 RXB1OVFL: Receive Buffer 1 Overflow bit

1 = Receive Buffer 1 overflowed

0 = Receive Buffer 1 has not overflowed

bit 5 **TXBO:** Transmitter Bus-Off bit

1 = Transmit Error Counter > 255

0 = Transmit Error Counter ≤ 255

bit 4 **TXBP:** Transmitter Bus Passive bit

1 = Transmission Error Counter > 127

0 = Transmission Error Counter ≤ 127

bit 3 RXBP: Receiver Bus Passive bit

1 = Receive Error Counter > 127

0 = Receive Error Counter ≤ 127

bit 2 TXWARN: Transmitter Warning bit

1 = 127 ≥ Transmit Error Counter > 95

0 = Transmit Error Counter ≤ 95

bit 1 RXWARN: Receiver Warning bit

1 = 127 ≥ Receive Error Counter > 95

0 = Receive Error Counter ≤ 95

bit 0 **EWARN:** Error Warning bit

This bit is a flag of the RXWARN and TXWARN bits.

1 = The RXWARN or the TXWARN bits are set

0 = Neither the RXWARN or the TXWARN bits are set

#### Legend:

R = Readable bit W = Writable bit C = Clearable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 19.2.2 CAN TRANSMIT BUFFER REGISTERS

This section describes the CAN Transmit Buffer registers and their associated control registers.

#### REGISTER 19-4: TXBnCON: TRANSMIT BUFFER n CONTROL REGISTERS

U-0	R-0	R-0	R-0	R/W-0	U-0	R/W-0	R/W-0
_	TXABT	TXLARB	TXERR	TXREQ	_	TXPRI1	TXPRI0
bit 7							bit 0

bit 7 Unimplemented: Read as '0'

bit 6 TXABT: Transmission Aborted Status bit

1 = Message was aborted0 = Message was not aborted

bit 5 **TXLARB:** Transmission Lost Arbitration Status bit

1 = Message lost arbitration while being sent

0 = Message did not lose arbitration while being sent

bit 4 TXERR: Transmission Error Detected Status bit

1 = A bus error occurred while the message was being sent

0 = A bus error did not occur while the message was being sent

bit 3 TXREQ: Transmit Request Status bit

1 = Requests sending a message. Clears the TXABT, TXLARB and TXERR bits.

0 = Automatically cleared when the message is successfully sent

**Note:** Clearing this bit in software while the bit is set will request a message abort.

bit 2 **Unimplemented:** Read as '0'

bit 1-0 TXPRI1:TXPRI0: Transmit Priority bits

11 = Priority Level 3 (highest priority)

10 = Priority Level 2

01 = Priority Level 1

00 = Priority Level 0 (lowest priority)

**Note:** These bits set the order in which the Transmit Buffer will be transferred. They do not alter the CAN message identifier.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-5: TXBnSIDH: TRANSMIT BUFFER n STANDARD IDENTIFIER, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| SID10 | SID9  | SID8  | SID7  | SID6  | SID5  | SID4  | SID3  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 0

bit 7-0 SID10:SID3: Standard Identifier bits if EXIDE = 0 (TXBnSID Register) or Extended Identifier bits EID28:EID21 if EXIDE = 1

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-6: TXBnSIDL: TRANSMIT BUFFER n STANDARD IDENTIFIER. **LOW BYTE REGISTERS**

- · · · -							
SID2	SID1	SID0	_	EXIDE	-	EID17	EID16
R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x

bit 7 bit 0

bit 7-5 SID2:SID0: Standard Identifier bits if EXIDE = 0 or

Extended Identifier bits EID20:EID18 if EXIDE = 1

bit 4 Unimplemented: Read as '0'

bit 3 **EXIDE:** Extended Identifier enable bit

1 = Message will transmit extended ID, SID10:SID0 becomes EID28:EID18

0 = Message will transmit standard ID, EID17:EID0 are ignored

bit 2 Unimplemented: Read as '0'

bit 1-0 EID17:EID16: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-7: TXBnEIDH: TRANSMIT BUFFER n EXTENDED IDENTIFIER, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID15 | EID14 | EID13 | EID12 | EID11 | EID10 | EID9  | EID8  |

bit 7 bit 0

bit 7-0 EID15:EID8: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' '1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown **REGISTER 19-8:** TXBnEIDL: TRANSMIT BUFFER n EXTENDED IDENTIFIER,

**LOW BYTE REGISTERS** 

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID7  | EID6  | EID5  | EID4  | EID3  | EID2  | EID1  | EID0  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 0

bit 7-0 EID7:EID0: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

REGISTER 19-9: TXBnDm: TRANSMIT BUFFER n DATA FIELD BYTE m REGISTERS

> R/W-x R/W-x R/W-x R/W-x R/W-x R/W-x R/W-x R/W-x TXBnDm7 TXBnDm6 TXBnDm5 TXBnDm4 TXBnDm3 TXBnDm2 TXBnDm1 TXBnDm0 bit 7 bit 0

bit 7-0 **TXBnDm7:TXBnDm0:** Transmit Buffer n Data Field Byte m bits (where  $0 \le n < 3$  and 0 < m < 8) Each Transmit Buffer has an array of registers. For example, Transmit Buffer 0 has 7 registers: TXB0D0 to TXB0D7.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' '1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-10: TXBnDLC: TRANSMIT BUFFER n DATA LENGTH CODE REGISTERS

	U-0	R/W-x	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x
	_	TXRTR	_	_	DLC3	DLC2	DLC1	DLC0
b	it 7							bit 0

bit 0

bit 7 Unimplemented: Read as '0'

bit 6 TXRTR: Transmission Frame Remote Transmission Request bit

1 = Transmitted message will have TXRTR bit set

0 = Transmitted message will have TXRTR bit cleared

bit 5-4 Unimplemented: Read as '0'

bit 3-0 DLC3:DLC0: Data Length Code bits

1111 = Reserved

1110 = Reserved

1101 = Reserved

1100 = Reserved

1011 = Reserved

1010 = Reserved

1001 = Reserved

1000 = Data Length = 8 bytes

0111 = Data Length = 7 bytes

0110 = Data Length = 6 bytes

0101 = Data Length = 5 bytes

0100 = Data Length = 4 bytes

0011 = Data Length = 3 bytes

0010 = Data Length = 2 bytes

0001 = Data Length = 1 bytes

0000 = Data Length = 0 bytes

#### Leaend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-11: TXERRCNT: TRANSMIT ERROR COUNT REGISTER

R-0	R-0	H-0	R-0	H-0	H-0	H-0	H-0
TEC7	TEC6	TEC5	TEC4	TEC3	TEC2	TEC1	TEC0
bit 7							bit 0

#### bit 7-0 TEC7:TEC0: Transmit Error Counter bits

This register contains a value which is derived from the rate at which errors occur. When the error count overflows, the bus-off state occurs. When the bus has 128 occurrences of 11 consecutive recessive bits, the counter value is cleared.

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
-n = Value at POR	'1' = Bit is set	0' = Bit is cleared x = Bit is unknown

### 19.2.3 CAN RECEIVE BUFFER REGISTERS

This section shows the Receive Buffer registers with their associated control registers.

#### REGISTER 19-12: RXB0CON: RECEIVE BUFFER 0 CONTROL REGISTER

R/C-0	R/W-0	R/W-0	U-0	R-0	R/W-0	R-0	R-0
RXFUL <sup>(1)</sup>	RXM1 <sup>(1)</sup>	RXM0 <sup>(1)</sup>	_	RXRTRRO	RXB0DBEN	JTOFF	FILHIT0
bit 7							bit 0

bit 7 **RXFUL:** Receive Full Status bit<sup>(1)</sup>

1 = Receive buffer contains a received message

0 = Receive buffer is open to receive a new message

**Note:** This bit is set by the CAN module and must be cleared by software after the buffer is read.

bit 6-5 **RXM1:RXM0:** Receive Buffer Mode bits<sup>(1)</sup>

11 = Receive all messages (including those with errors)

10 = Receive only valid messages with extended identifier

01 = Receive only valid messages with standard identifier

00 = Receive all valid messages

bit 4 Unimplemented: Read as '0'

bit 3 RXRTRRO: Receive Remote Transfer Request Read-Only bit

1 = Remote transfer request

0 = No remote transfer request

bit 2 **RXB0DBEN:** Receive Buffer 0 Double-Buffer Enable bit

1 = Receive Buffer 0 overflow will write to Receive Buffer 1

0 = No Receive Buffer 0 overflow to Receive Buffer 1

bit 1 JTOFF: Jump Table Offset bit (read-only copy of RXB0DBEN)

1 = Allows jump table offset between 6 and 7

0 = Allows jump table offset between 1 and 0

**Note:** This bit allows same filter jump table for both RXB0CON and RXB1CON.

bit 0 FILHITO: Filter Hit bit

This bit indicates which acceptance filter enabled the message reception into Receive Buffer 0.

1 = Acceptance Filter 1 (RXF1)

0 = Acceptance Filter 0 (RXF0)

Note 1: Bits RXFUL, RXM1 and RXM0 of RXB0CON are not mirrored in RXB1CON.

#### Legend:

R = Readable bit W = Writable bit C = Clearable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared <math>x = Bit is unknown

#### REGISTER 19-13: RXB1CON: RECEIVE BUFFER 1 CONTROL REGISTER

R/C-0	R/W-0	R/W-0	U-0	R-0	R-0	R-0	R-0
RXFUL <sup>(1)</sup>	RXM1 <sup>(1)</sup>	RXM0 <sup>(1)</sup>	_	RXRTRRO	FILHIT2	FILHIT1	FILHIT0
bit 7							bit 0

- bit 7 **RXFUL:** Receive Full Status bit<sup>(1)</sup>
  - 1 = Receive buffer contains a received message
  - 0 = Receive buffer is open to receive a new message

**Note:** This bit is set by the CAN module and should be cleared by software after the buffer is read.

- bit 6-5 **RXM1:RXM0:** Receive Buffer Mode bits<sup>(1)</sup>
  - 11 = Receive all messages (including those with errors)
  - 10 = Receive only valid messages with extended identifier
  - 01 = Receive only valid messages with standard identifier
  - 00 = Receive all valid messages
- bit 4 **Unimplemented:** Read as '0'
- bit 3 RXRTRRO: Receive Remote Transfer Request bit (read-only)
  - 1 = Remote transfer request
  - 0 = No remote transfer request
- bit 2-0 FILHIT2:FILHIT0: Filter Hit bits

These bits indicate which acceptance filter enabled the last message reception into Receive Buffer 1.

- 111 = Reserved
- 110 = Reserved
- 101 = Acceptance Filter 5 (RXF5)
- 100 = Acceptance Filter 4 (RXF4)
- 011 = Acceptance Filter 3 (RXF3)
- 010 = Acceptance Filter 2 (RXF2)
- 001 = Acceptance Filter 1 (RXF1), only possible when RXB0DBEN bit is set
- 000 = Acceptance Filter 0 (RXF0), only possible when RXB0DBEN bit is set

Note 1: Bits RXFUL, RXM1 and RXM0 of RXB1CON are not mirrored in RXB0CON.

#### Legend:

R = Readable bit W = Writable bit C = Clearable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared <math>x = Bit is unknown

#### REGISTER 19-14: RXBnSIDH: RECEIVE BUFFER n STANDARD IDENTIFIER, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| SID10 | SID9  | SID8  | SID7  | SID6  | SID5  | SID4  | SID3  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 0

bit 7-0 SID10:SID3: Standard Identifier bits if EXID = 0 (RXBnSIDL Register) or Extended Identifier bits EID28:EID21 if EXID = 1

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-15: RXBnSIDL: RECEIVE BUFFER n STANDARD IDENTIFIER. **LOW BYTE REGISTERS**

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	U-0	R/W-x	R/W-x
SID2	SID1	SID0	SRR	EXID	_	EID17	EID16
bit 7							bit 0

bit 7-5 SID2:SID0: Standard Identifier bits if EXID = 0 or

Extended Identifier bits EID20:EID18 if EXID = 1

bit 4 SRR: Substitute Remote Request bit

This bit is always '0' when EXID = 1 or equal to the value of RXRTRRO (RXnBCON<3>)

when EXID = 0.

bit 3 **EXID:** Extended Identifier bit

1 = Received message is an extended data frame, SID10:SID0 are EID28:EID18

0 = Received message is a standard data frame

bit 2 Unimplemented: Read as '0'

bit 1-0 EID17:EID16: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-16: RXBnEIDH: RECEIVE BUFFER n EXTENDED IDENTIFIER, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID15 | EID14 | EID13 | EID12 | EID11 | EID10 | EID9  | EID8  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 EID15:EID8: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-17: RXBnEIDL: RECEIVE BUFFER n EXTENDED IDENTIFIER, **LOW BYTE REGISTERS**

	R/W-x							
	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0
bit 7 bit 0								

bit 0

bit 7-0 EID7:EID0: Extended Identifier bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' '1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-18: RXBnDLC: RECEIVE BUFFER n DATA LENGTH CODE REGISTERS

U-0	R/W-x						
_	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0

bit 7 bit 0

bit 7 Unimplemented: Read as '0'

bit 6 **RXRTR:** Receiver Remote Transmission Request bit

1 = Remote transfer request

0 = No remote transfer request

bit 5 RB1: Reserved bit 1

Reserved by CAN spec and read as '0'.

bit 4 RB0: Reserved bit 0

Reserved by CAN spec and read as '0'.

bit 3-0 DLC3:DLC0: Data Length Code bits

1111 = Invalid

1110 = Invalid

1101 = Invalid

1100 = Invalid

1011 = Invalid

1010 = Invalid

1001 = Invalid

1000 = Data Length = 8 bytes

0111 = Data Length = 7 bytes

0110 = Data Length = 6 bytes

0101 = Data Length = 5 bytes 0100 = Data Length = 4 bytes

0011 = Data Length = 3 bytes

0010 = Data Length = 2 bytes

0001 = Data Length = 1 bytes

0000 = Data Length = 0 bytes

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' '1' = Bit is set -n = Value at POR '0' = Bit is cleared x = Bit is unknown

#### REGISTER 19-19: RXBnDm: RECEIVE BUFFER n DATA FIELD BYTE m REGISTERS

	R/W-x							
	RXBnDm7	RXBnDm6	RXBnDm5	RXBnDm4	RXBnDm3	RXBnDm2	RXBnDm1	RXBnDm0
bit 7						bit 0		

bit 7-0 **RXBnDm7:RXBnDm0:** Receive Buffer n Data Field Byte m bits (where  $0 \le n < 1$  and 0 < m < 7) Each receive buffer has an array of registers. For example, Receive Buffer 0 has 8 registers: RXB0D0 to RXB0D7.

Legend:					
R = Readable bit W = Writable bit		U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared $x = Bit$ is unknown			

#### REGISTER 19-20: RXERRCNT: RECEIVE ERROR COUNT REGISTER

R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
REC7	REC6	REC5	REC4	REC3	REC2	REC1	REC0
bit 7 bit 0							

#### bit 7-0 **REC7:REC0:** Receive Error Counter bits

This register contains the receive error value as defined by the CAN specifications. When RXERRCNT > 127, the module will go into an error passive state. RXERRCNT does not have the ability to put the module in "Bus-Off" state.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared $x = Bit$ is unknown	

#### 19.2.3.1 Message Acceptance Filters and Masks

This subsection describes the message acceptance filters and masks for the CAN receive buffers.

### REGISTER 19-21: RXFnSIDH: RECEIVE ACCEPTANCE FILTER n STANDARD IDENTIFIER FILTER, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| SID10 | SID9  | SID8  | SID7  | SID6  | SID5  | SID4  | SID3  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 **SID10:SID3:** Standard Identifier Filter bits if EXIDEN = 0 or Extended Identifier Filter bits EID28:EID21 if EXIDEN = 1

> Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 19-22: RXFnSIDL: RECEIVE ACCEPTANCE FILTER n STANDARD IDENTIFIER FILTER. **LOW BYTE REGISTERS**

R/W-x	R/W-x	R/W-x	U-0	R/W-x	U-0	R/W-x	R/W-x
SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16
bit 7							bit 0

bit 7-5 SID2:SID0: Standard Identifier Filter bits if EXIDEN = 0 or

Extended Identifier Filter bits EID20:EID18 if EXIDEN = 1

bit 4 Unimplemented: Read as '0'

bit 3 **EXIDEN:** Extended Identifier Filter Enable bit

1 = Filter will only accept extended ID messages

0 = Filter will only accept standard ID messages

bit 2 Unimplemented: Read as '0'

bit 1-0 EID17:EID16: Extended Identifier Filter bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## REGISTER 19-23: RXFnEIDH: RECEIVE ACCEPTANCE FILTER n EXTENDED IDENTIFIER, HIGH BYTE REGISTERS

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID15 | EID14 | EID13 | EID12 | EID11 | EID10 | EID9  | EID8  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 **EID15:EID8:** Extended Identifier Filter bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## REGISTER 19-24: RXFnEIDL: RECEIVE ACCEPTANCE FILTER n EXTENDED IDENTIFIER, LOW BYTE REGISTERS

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID7  | EID6  | EID5  | EID4  | EID3  | EID2  | EID1  | EID0  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 **EID7:EID0:** Extended Identifier Filter bits

Legend:W = Writable bitU = Unimplemented bit, read as '0'U = Unimplemented bit, read as '0'<math>U = Unimplemented bit, read as '0'

# REGISTER 19-25: RXMnSIDH: RECEIVE ACCEPTANCE MASK n STANDARD IDENTIFIER MASK, HIGH BYTE REGISTERS

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| SID10 | SID9  | SID8  | SID7  | SID6  | SID5  | SID4  | SID3  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 SID10:SID3: Standard Identifier Mask bits or Extended Identifier Mask bits EID28:EID21

Legend:W = Writable bitU = Unimplemented bit, read as '0'U = Unimplemented bit, read as '0'<math>U = Unimplemented bit, read as '0'

### REGISTER 19-26: RXMnSIDL: RECEIVE ACCEPTANCE MASK n STANDARD IDENTIFIER MASK, **LOW BYTE REGISTERS**

R/W-x	R/W-x	R/W-x	U-0	U-0	U-0	R/W-x	R/W-x
SID2	SID1	SID0	_	_	_	EID17	EID16
bit 7							bit 0

bit 0

bit 7-5 SID2:SID0: Standard Identifier Mask bits or Extended Identifier Mask bits EID20:EID18

bit 4-2 Unimplemented: Read as '0'

bit 1-0 EID17:EID16: Extended Identifier Mask bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 19-27: RXMnEIDH: RECEIVE ACCEPTANCE MASK n EXTENDED IDENTIFIER MASK, **HIGH BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID15 | EID14 | EID13 | EID12 | EID11 | EID10 | EID9  | EID8  |

bit 7 bit 0

bit 7-0 EID15:EID8: Extended Identifier Mask bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '0' = Bit is cleared '1' = Bit is set x = Bit is unknown

### REGISTER 19-28: RXMnEIDL: RECEIVE ACCEPTANCE MASK n EXTENDED IDENTIFIER MASK, **LOW BYTE REGISTERS**

| R/W-x |
|-------|-------|-------|-------|-------|-------|-------|-------|
| EID7  | EID6  | EID5  | EID4  | EID3  | EID2  | EID1  | EID0  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7-0 EID7:EID0: Extended Identifier Mask bits

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 19.2.4 CAN BAUD RATE REGISTERS

This subsection describes the CAN Baud Rate registers.

### REGISTER 19-29: BRGCON1: BAUD RATE CONTROL REGISTER 1

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| SJW1  | SJW0  | BRP5  | BRP4  | BRP3  | BRP2  | BRP1  | BRP0  |
| bit 7 |       |       |       |       |       |       | bit 0 |

### bit 7-6 SJW1:SJW0: Synchronized Jump Width bits

11 = Synchronization Jump Width Time =  $4 \times TQ$ 10 = Synchronization Jump Width Time =  $3 \times TQ$ 01 = Synchronization Jump Width Time =  $2 \times TQ$ 00 = Synchronization Jump Width Time =  $1 \times TQ$ 

### bit 5-0 BRP5:BRP0: Baud Rate Prescaler bits

111111 = TQ = (2 x 64)/Fosc 111110 = TQ = (2 x 63)/Fosc : : 000001 = TQ = (2 x 2)/Fosc 000000 = TQ = (2 x 1)/Fosc

### Legend:

 $R = Readable \ bit$   $W = Writable \ bit$   $U = Unimplemented \ bit, read \ as '0'$   $-n = Value \ at \ POR$  '1' = Bit is set '0' = Bit is cleared  $x = Bit \ is \ unknown$ 

**Note:** This register is accessible in Configuration mode only.

### REGISTER 19-30: BRGCON2: BAUD RATE CONTROL REGISTER 2

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
SEG2PHTS	SAM	SEG1PH2	SEG1PH1	SEG1PH0	PRSEG2	PRSEG1	PRSEG0	J
bit 7							bit 0	

bit 7 SEG2PHTS: Phase Segment 2 Time Select bit

1 = Freely programmable

0 = Maximum of PHEG1 or Information Processing Time (IPT), whichever is greater

bit 6 SAM: Sample of the CAN bus Line bit

1 = Bus line is sampled three times prior to the sample point

0 = Bus line is sampled once at the sample point

bit 5-3 **SEG1PH2:SEG1PH0:** Phase Segment 1 bits

111 = Phase Segment 1 Time =  $8 \times TQ$ 

110 = Phase Segment 1 Time = 7 x TQ

101 = Phase Segment 1 Time = 6 x TQ

100 = Phase Segment 1 Time = 5 x TQ

 $011 = \text{Phase Segment 1 Time} = 3 \times 10^{\circ}$ 

010 = Phase Segment 1 Time = 3 x TQ

001 = Phase Segment 1 Time = 3 x TQ

000 = Phase Segment 1 Time = 1 x TQ

bit 2-0 PRSEG2:PRSEG0: Propagation Time Select bits

111 = Propagation Time = 8 x TQ

110 = Propagation Time = 7 x TQ

101 = Propagation Time = 6 x TQ

100 = Propagation Time =  $5 \times TQ$ 

011 = Propagation Time = 4 x TQ

010 = Propagation Time = 3 x TQ

001 = Propagation Time = 2 x TQ

000 = Propagation Time = 1 x TQ

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note: This register is accessible in Configuration mode only.

### www.DataPIC18FXX8

### REGISTER 19-31: BRGCON3: BAUD RATE CONTROL REGISTER 3

U-0	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
1	WAKFIL	_	_	_	SEG2PH2 <sup>(1)</sup>	SEG2PH1 <sup>(1)</sup>	SEG2PH0 <sup>(1)</sup>
bit 7							bit 0

bit 7 **Unimplemented:** Read as '0'

bit 6 WAKFIL: Selects CAN bus Line Filter for Wake-up bit

1 = Use CAN bus line filter for wake-up

0 = CAN bus line filter is not used for wake-up

bit 5-3 **Unimplemented:** Read as '0'

bit 2-0 SEG2PH2:SEG2PH0: Phase Segment 2 Time Select bits<sup>(1)</sup>

111 = Phase Segment 2 Time = 8 x TQ

110 = Phase Segment 2 Time =  $7 \times TQ$ 

101 = Phase Segment 2 Time = 6 x TQ

100 = Phase Segment 2 Time = 5 x TQ

011 = Phase Segment 2 Time = 4 x TQ

010 = Phase Segment 2 Time = 3 x TQ 001 = Phase Segment 2 Time = 2 x TQ

000 = Phase Segment 2 Time = 2 x TQ

Note 1: Ignored if SEG2PHTS bit (BRGCON2<7>) is clear.

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### CAN MODULE I/O CONTROL 19.2.5 REGISTER

This register controls the operation of the CAN module's I/O pins in relation to the rest of the microcontroller.

### **REGISTER 19-32: CIOCON: CAN I/O CONTROL REGISTER**

U-0	U-0	R/W-0	R/W-0	U-0	U-0	U-0	U-0
_	_	ENDRHI	CANCAP	_	_	_	_
bit 7							bit 0

bit 0

bit 7-6 Unimplemented: Read as '0' bit 5 **ENDRHI:** Enable Drive High bit

> 1 = CANTX pin will drive VDD when recessive 0 = CANTX pin will tri-state when recessive

bit 4 CANCAP: CAN Message Receive Capture Enable bit

1 = Enable CAN capture, CAN message receive signal replaces input on RC2/CCP1

0 = Disable CAN capture, RC2/CCP1 input to CCP1 module

bit 3-0 Unimplemented: Read as '0'

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

'0' = Bit is cleared -n = Value at POR '1' = Bit is set x = Bit is unknown

### 19.2.6 CAN INTERRUPT REGISTERS

The registers in this section are the same as described in **Section 8.0 "Interrupts"**. They are duplicated here for convenience.

### REGISTER 19-33: PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF
bit 7							bit 0

bit 7 **IRXIF:** CAN Invalid Received Message Interrupt Flag bit 1 = An invalid message has occurred on the CAN bus

0 = No invalid message on CAN bus

bit 6 WAKIF: CAN bus Activity Wake-up Interrupt Flag bit

1 = Activity on CAN bus has occurred

0 = No activity on CAN bus

bit 5 ERRIF: CAN bus Error Interrupt Flag bit

1 = An error has occurred in the CAN module (multiple sources)

0 = No CAN module errors

bit 4 TXB2IF: CAN Transmit Buffer 2 Interrupt Flag bit

1 = Transmit Buffer 2 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 2 has not completed transmission of a message

bit 3 TXB1IF: CAN Transmit Buffer 1 Interrupt Flag bit

1 = Transmit Buffer 1 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 1 has not completed transmission of a message

bit 2 TXB0IF: CAN Transmit Buffer 0 Interrupt Flag bit

1 = Transmit Buffer 0 has completed transmission of a message and may be reloaded

0 = Transmit Buffer 0 has not completed transmission of a message

bit 1 RXB1IF: CAN Receive Buffer 1 Interrupt Flag bit

1 = Receive Buffer 1 has received a new message

0 = Receive Buffer 1 has not received a new message

bit 0 RXB0IF: CAN Receive Buffer 0 Interrupt Flag bit

1 = Receive Buffer 0 has received a new message

0 = Receive Buffer 0 has not received a new message

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 19-34: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE
bit 7							bit 0

bit 0

bit 7 IRXIE: CAN Invalid Received Message Interrupt Enable bit

1 = Enable invalid message received interrupt

0 = Disable invalid message received interrupt

bit 6 WAKIE: CAN bus Activity Wake-up Interrupt Enable bit

1 = Enable bus activity wake-up interrupt

0 = Disable bus activity wake-up interrupt

ERRIE: CAN bus Error Interrupt Enable bit bit 5

1 = Enable CAN bus error interrupt

0 = Disable CAN bus error interrupt

bit 4 TXB2IE: CAN Transmit Buffer 2 Interrupt Enable bit

1 = Enable Transmit Buffer 2 interrupt

0 = Disable Transmit Buffer 2 interrupt

bit 3 TXB1IE: CAN Transmit Buffer 1 Interrupt Enable bit

1 = Enable Transmit Buffer 1 interrupt

0 = Disable Transmit Buffer 1 interrupt

bit 2 TXB0IE: CAN Transmit Buffer 0 Interrupt Enable bit

1 = Enable Transmit Buffer 0 interrupt

0 = Disable Transmit Buffer 0 interrupt

bit 1 RXB1IE: CAN Receive Buffer 1 Interrupt Enable bit

1 = Enable Receive Buffer 1 interrupt

0 = Disable Receive Buffer 1 interrupt

bit 0 RXB0IE: CAN Receive Buffer 0 Interrupt Enable bit

1 = Enable Receive Buffer 0 interrupt

0 = Disable Receive Buffer 0 interrupt

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### www.DataPIC18FXX8

### REGISTER 19-35: IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP
bit 7							bit 0

bit 7 IRXIP: CAN Invalid Received Message Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 WAKIP: CAN bus Activity Wake-up Interrupt Priority bit

1 = High priority0 = Low priority

bit 5 **ERRIP:** CAN bus Error Interrupt Priority bit

1 = High priority0 = Low priority

bit 4 TXB2IP: CAN Transmit Buffer 2 Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 **TXB1IP:** CAN Transmit Buffer 1 Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 **TXB0IP:** CAN Transmit Buffer 0 Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 RXB1IP: CAN Receive Buffer 1 Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 RXB0IP: CAN Receive Buffer 0 Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

TABLE 19-1: CAN CONTROLLER REGISTER MAP

Address	Name	Address	Name	Address	Name	Address	Name
F7Fh	_	F5Fh	_	F3Fh	_	F1Fh	RXM1EIDL
F7Eh	_	F5Eh	CANSTATRO1 <sup>(2)</sup>	F3Eh	CANSTATRO3 <sup>(2)</sup>	F1Eh	RXM1EIDH
F7Dh	_	F5Dh	RXB1D7	F3Dh	TXB1D7	F1Dh	RXM1SIDL
F7Ch	_	F5Ch	RXB1D6	F3Ch	TXB1D6	F1Ch	RXM1SIDH
F7Bh	_	F5Bh	RXB1D5	F3Bh	TXB1D5	F1Bh	RXM0EIDL
F7Ah	_	F5Ah	RXB1D4	F3Ah	TXB1D4	F1Ah	RXM0EIDH
F79h	_	F59h	RXB1D3	F39h	TXB1D3	F19h	RXM0SIDL
F78h	_	F58h	RXB1D2	F38h	TXB1D2	F18h	RXM0SIDH
F77h		F57h	RXB1D1	F37h	TXB1D1	F17h	RXF5EIDL
F76h	TXERRCNT	F56h	RXB1D0	F36h	TXB1D0	F16h	RXF5EIDH
F75h	RXERRCNT	F55h	RXB1DLC	F35h	TXB1DLC	F15h	RXF5SIDL
F74h	COMSTAT	F54h	RXB1EIDL	F34h	TXB1EIDL	F14h	RXF5SIDH
F73h	CIOCON	F53h	RXB1EIDH	F33h	TXB1EIDH	F13h	RXF4EIDL
F72h	BRGCON3	F52h	RXB1SIDL	F32h	TXB1SIDL	F12h	RXF4EIDH
F71h	BRGCON2	F51h	RXB1SIDH	F31h	TXB1SIDH	F11h	RXF4SIDL
F70h	BRGCON1	F50h	RXB1CON	F30h	TXB1CON	F10h	RXF4SIDH
F6Fh	CANCON	F4Fh	_	F2Fh	_	F0Fh	RXF3EIDL
F6Eh	CANSTAT	F4Eh	CANSTATRO2 <sup>(2)</sup>	F2Eh	CANSTATRO4 <sup>(2)</sup>	F0Eh	RXF3EIDH
F6Dh	RXB0D7	F4Dh	TXB0D7	F2Dh	TXB2D7	F0Dh	RXF3SIDL
F6Ch	RXB0D6	F4Ch	TXB0D6	F2Ch	TXB2D6	F0Ch	RXF3SIDH
F6Bh	RXB0D5	F4Bh	TXB0D5	F2Bh	TXB2D5	F0Bh	RXF2EIDL
F6Ah	RXB0D4	F4Ah	TXB0D4	F2Ah	TXB2D4	F0Ah	RXF2EIDH
F69h	RXB0D3	F49h	TXB0D3	F29h	TXB2D3	F09h	RXF2SIDL
F68h	RXB0D2	F48h	TXB0D2	F28h	TXB2D2	F08h	RXF2SIDH
F67h	RXB0D1	F47h	TXB0D1	F27h	TXB2D1	F07h	RXF1EIDL
F66h	RXB0D0	F46h	TXB0D0	F26h	TXB2D0	F06h	RXF1EIDH
F65h	RXB0DLC	F45h	TXB0DLC	F25h	TXB2DLC	F05h	RXF1SIDL
F64h	RXB0EIDL	F44h	TXB0EIDL	F24h	TXB2EIDL	F04h	RXF1SIDH
F63h	RXB0EIDH	F43h	TXB0EIDH	F23h	TXB2EIDH	F03h	RXF0EIDL
F62h	RXB0SIDL	F42h	TXB0SIDL	F22h	TXB2SIDL	F02h	RXF0EIDH
F61h	RXB0SIDH	F41h	TXB0SIDH	F21h	TXB2SIDH	F01h	RXF0SIDL
F60h	RXB0CON	F40h	TXB0CON	F20h	TXB2CON	F00h	RXF0SIDH

**Note 1:** Shaded registers are available in Access Bank low area while the rest are available in Bank 15.

**<sup>2:</sup>** CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip Header file requirement.

### 19.3 CAN Modes of Operation

The PIC18FXX8 has six main modes of operation:

- · Configuration mode
- · Disable mode
- · Normal Operation mode
- · Listen Only mode
- · Loopback mode
- Error Recognition mode

All modes, except Error Recognition, are requested by setting the REQOP bits (CANCON<7:5>); Error Recognition is requested through the RXM bits of the Receive Buffer register(s). Entry into a mode is Acknowledged by monitoring the OPMODE bits.

When changing modes, the mode will not actually change until all pending message transmissions are complete. Because of this, the user must verify that the device has actually changed into the requested mode before fUrther Operations Are Executed.

### 19.3.1 CONFIGURATION MODE

The CAN module has to be initialized before the activation. This is only possible if the module is in the Configuration mode. The Configuration mode is requested by setting the REQOP2 bit. Only when the OPMODE2 status bit has a high level can the initialization be performed. Afterwards, the Configuration registers, the Acceptance Mask registers and the Acceptance Filter registers can be written. The module is activated by setting the REQOP control bits to zero.

The module will protect the user from accidentally violating the CAN protocol through programming errors. All registers which control the configuration of the module can not be modified while the module is online. The CAN module will not be allowed to enter the Configuration mode while a transmission is taking place. The CONFIG bit serves as a lock to protect the following registers.

- Configuration registers
- · Bus Timing registers
- · Identifier Acceptance Filter registers
- Identifier Acceptance Mask registers

In the Configuration mode, the module will not transmit or receive. The error counters are cleared and the interrupt flags remain unchanged. The programmer will have access to Configuration registers that are access restricted in other modes.

### 19.3.2 DISABLE MODE

In Disable mode, the module will not transmit or receive. The module has the ability to set the WAKIF bit due to bus activity, however, any pending interrupts will remain and the error counters will retain their value.

If REQOP<2:0> is set to '001', the module will enter the Module Disable mode. This mode is similar to disabling other peripheral modules by turning off the module enables. This causes the module internal clock to stop unless the module is active (i.e., receiving or transmitting a message). If the module is active, the module will wait for 11 recessive bits on the CAN bus, detect that condition as an IDLE bus, then accept the module disable command. OPMODE<2:0> = 001 indicates whether the module successfully went into Module Disable mode.

The WAKIF interrupt is the only module interrupt that is still active in the Module Disable mode. If the WAKIE is set, the processor will receive an interrupt whenever the CAN bus detects a dominant state, as occurs with a SOF. If the processor receives an interrupt while it is sleeping, more than one message may get lost. User firmware must anticipate this condition and request retransmission. If the processor is running while it receives an interrupt, only the first message may get lost.

The I/O pins will revert to normal I/O function when the module is in the Module Disable mode.

### 19.3.3 NORMAL MODE

This is the standard operating mode of the PIC18FXX8. In this mode, the device actively monitors all bus messages and generates Acknowledge bits, error frames, etc. This is also the only mode in which the PIC18FXX8 will transmit messages over the CAN bus.

### 19.3.4 LISTEN ONLY MODE

Listen Only mode provides a means for the PIC18FXX8 to receive all messages, including messages with errors. This mode can be used for bus monitor applications or for detecting the baud rate in 'hot plugging' situations. For auto-baud detection, it is necessary that there are at least two other nodes which are communicating with each other. The baud rate can be detected empirically by testing different values until valid messages are received. The Listen Only mode is a silent mode, meaning no messages will be transmitted while in this state, including error flags or Acknowledge signals. The filters and masks can be used to allow only particular messages to be loaded into the receive registers, or the filter masks can be set to all zeros to allow a message with any identifier to pass. The error counters are reset and deactivated in this state. The Listen Only mode is activated by setting the mode request bits in the CANCON register.

### 19.3.5 LOOPBACK MODE

This mode will allow internal transmission of messages from the transmit buffers to the receive buffers without actually transmitting messages on the CAN bus. This mode can be used in system development and testing. In this mode, the ACK bit is ignored and the device will allow incoming messages from itself, just as if they were coming from another node. The Loopback mode is a silent mode, meaning no messages will be transmitted while in this state, including error flags or Acknowledge signals. The TXCAN pin will revert to port I/O while the device is in this mode. The filters and masks can be used to allow only particular messages to be loaded into the receive registers. The masks can be set to all zeros to provide a mode that accepts all messages. The Loopback mode is activated by setting the mode request bits in the CANCON register.

### 19.3.6 ERROR RECOGNITION MODE

The module can be set to ignore all errors and receive all message. The Error Recognition mode is activated by setting the RXM<1:0> bits in the RXBnCON registers to '11'. In this mode, all messages, valid or invalid, are received and copied to the receive buffer.

### 19.4 CAN Message Transmission

### 19.4.1 TRANSMIT BUFFERS

The PIC18FXX8 implements three transmit buffers (Figure 19-2). Each of these buffers occupies 14 bytes of SRAM and are mapped into the device memory map.


For the MCU to have write access to the message buffer, the TXREQ bit must be clear, indicating that the message buffer is clear of any pending message to be transmitted. At a minimum, the TXBnSIDH, TXBnSIDL and TXBnDLC registers must be loaded. If data bytes are present in the message, the TXBnDm registers must also be loaded. If the message is to use extended identifiers, the TXBnEIDm registers must also be loaded and the EXIDE bit set.

Prior to sending the message, the MCU must initialize the TXInE bit to enable or disable the generation of an interrupt when the message is sent. The MCU must also initialize the TXP priority bits (see **Section 19.4.2** "**Transmit Priority**").

### 19.4.2 TRANSMIT PRIORITY

Transmit priority is a prioritization within the PIC18FXX8 of the pending transmittable messages. This is independent from and not related to any prioritization implicit in the message arbitration scheme built into the CAN protocol. Prior to sending the SOF, the priority of all buffers that are queued for transmission is compared. The transmit buffer with the highest priority will be sent first. If two buffers have the same priority setting, the buffer with the highest buffer number will be sent first. There are four levels of transmit priority. If TXP bits for a particular message buffer are set to '11', that buffer has the highest possible priority. If TXP bits for a particular message buffer are '00', that buffer has the lowest possible priority.

FIGURE 19-2: TRANSMIT BUFFER BLOCK DIAGRAM



### 19.4.3 INITIATING TRANSMISSION

To initiate message transmission, the TXREQ bit must be set for each buffer to be transmitted. When TXREQ is set, the TXABT, TXLARB and TXERR bits will be cleared.

Setting the TXREQ bit does not initiate a message transmission; it merely flags a message buffer as ready for transmission. Transmission will start when the device detects that the bus is available. The device will then begin transmission of the highest priority message that is ready.

When the transmission has completed successfully, the TXREQ bit will be cleared, the TXBnIF bit will be set and an interrupt will be generated if the TXBnIE bit is set.

If the message transmission fails, the TXREQ will remain set, indicating that the message is still pending for transmission and one of the following condition flags will be set. If the message started to transmit but encountered an error condition, the TXERR and the IRXIF bits will be set and an interrupt will be generated. If the message lost arbitration, the TXLARB bit will be set.

### 19.4.4 ABORTING TRANSMISSION

The MCU can request to abort a message by clearing the TXREQ bit associated with the corresponding message buffer (TXBnCON<3>). Setting the ABAT bit (CANCON<4>) will request an abort of all pending messages. If the message has not yet started transmission, or if the message started but is interrupted by loss of arbitration or an error, the abort will be processed. The abort is indicated when the module sets the ABT bits for the corresponding buffer (TXBnCON<6>). If the message has started to transmit, it will attempt to transmit the current message fully. If the current message is transmitted fully and is not lost to arbitration or an error, the ABT bit will not be set because the message was transmitted successfully. Likewise, if a message is being transmitted during an abort request and the message is lost to arbitration or an error, the message will not be retransmitted and the ABT bit will be set, indicating that the message was successfully aborted.

Start The message transmission sequence begins when the device determines that the TXREQ for any of the transmit registers has been set. Are any TXREQ No bits = 1? Clearing the TXREQ bit while it is set, or setting the ABAT bit before the message has started transmission, will abort the message. Clear: TXABT, TXLARB and TXERR No  $\begin{array}{c} \text{Is} \\ \text{TXREQ} = 0 \end{array}$ Yes Is CAN bus No Available to Start ABAT = 1?Transmission? Yes Examine TXPRI <1:0> to Determine Highest Priority Message Begin Transmission (SOF) Was
Message Transmitted
Successfully? No Set TXERR = 1 Yes Set TXREQ = 0 ls TXLARB = 1? Arbitration Lost During Transmission Yes Is TXIE = 1? Generate Interrupt A message can also be aborted if a message No error or lost arbitration No condition occurred during transmission. Yes TXREQ = 0or TXABT = 1? Set TXBUFE = 1 No The TXIE bit determines if an interrupt should be generated when a message is successfully transmitted. Abort Transmission: Set TXABT = 1 **END** 

FIGURE 19-3: INTERNAL TRANSMIT MESSAGE FLOWCHART

### 19.5 Message Reception

### 19.5.1 RECEIVE MESSAGE BUFFERING

The PIC18FXX8 includes two full receive buffers with multiple acceptance filters for each. There is also a separate Message Assembly Buffer (MAB) which acts as a third receive buffer (see Figure 19-4).

### 19.5.2 RECEIVE BUFFERS

Of the three receive buffers, the MAB is always committed to receiving the next message from the bus. The remaining two receive buffers are called RXB0 and RXB1 and can receive a complete message from the protocol engine. The MCU can access one buffer while the other buffer is available for message reception or holding a previously received message.

The MAB assembles all messages received. These messages will be transferred to the RXBn buffers only if the acceptance filter criteria are met.

Note

The entire contents of the MAB are moved into the receive buffer once a message is accepted. This means that regardless of the type of identifier (standard or extended) and the number of data bytes received, the entire receive buffer is overwritten with the MAB contents. Therefore, the contents of all registers in the buffer must be assumed to have been modified when any message is received.

When a message is moved into either of the receive buffers, the appropriate RXBnIF bit is set. This bit must be cleared by the MCU when it has completed processing the message in the buffer in order to allow a new message to be received into the buffer. This bit provides a positive lockout to ensure that the MCU has finished with the message before the PIC18FXX8 attempts to load a new message into the receive buffer. If the RXBnIE bit is set, an interrupt will be generated to indicate that a valid message has been received.

### 19.5.3 RECEIVE PRIORITY

RXB0 is the higher priority buffer and has two message acceptance filters associated with it. RXB1 is the lower priority buffer and has four acceptance filters associated with it. The lower number of acceptance filters makes the match on RXB0 more restrictive and implies a higher priority for that buffer. Additionally, the RXB0CON register can be configured such if RXB0 contains a valid message and another valid message is received, an overflow error will not occur and the new message will be moved into RXB1 regardless of the acceptance criteria of RXB1. There are also two programmable acceptance filter masks available, one for each receive buffer (see Section 19.6 "Message Acceptance Filters and Masks").

When a message is received, bits <3:0> of the RXBnCON register will indicate the acceptance filter number that enabled reception and whether the received message is a remote transfer request.


The RXM bits set special Receive modes. Normally, these bits are set to '00' to enable reception of all valid messages as determined by the appropriate acceptance filters. In this case, the determination of whether or not to receive standard or extended messages is determined by the EXIDE bit in the Acceptance Filter register. If the RXM bits are set to '01' or '10', the receiver will accept only messages with standard or extended identifiers, respectively. If an acceptance filter has the EXIDE bit set, such that it does not correspond with the RXM mode, that acceptance filter is rendered useless. These two modes of RXM bits can be used in systems where it is known that only standard or extended messages will be on the bus. If the RXM bits are set to '11', the buffer will receive all messages regardless of the values of the acceptance filters. Also, if a message has an error before the end of frame, that portion of the message assembled in the MAB before the error frame will be loaded into the buffer. This mode has some value in debugging a CAN system and would not be used in an actual system environment.


### 19.5.4 TIME-STAMPING

The CAN module can be programmed to generate a time-stamp for every message that is received. When enabled, the module generates a capture signal for CCP1 which in turns captures the value of either Timer1 or Timer3. This value can be used as the message time-stamp.

To use the time-stamp capability, the CANCAP bit (CIOCAN<4>) must be set. This replaces the capture input for CCP1 with the signal generated from the CAN module. In addition, CCP1CON<3:0> must be set to '0011' to enable the CCP special event trigger for CAN events.

FIGURE 19-4: RECEIVE BUFFER BLOCK DIAGRAM





## 19.6 Message Acceptance Filters and Masks

The message acceptance filters and masks are used to determine if a message in the message assembly buffer should be loaded into either of the receive buffers. Once a valid message has been received into the MAB, the identifier fields of the message are compared to the filter values. If there is a match, that message will be loaded into the appropriate receive buffer. The filter masks are used to determine which bits in the identifier are examined with the filters. A truth table is shown below in Table 19-2 that indicates how each bit in the identifier is compared to the masks and filters to determine if a message should be loaded into a receive buffer. The mask essentially determines which bits to apply the acceptance filters to. If any mask bit is set to a zero, then that bit will automatically be accepted regardless of the filter bit.

TABLE 19-2: FILTER/MASK TRUTH TABLE

Mask bit n	Filter bit n	Message Filter bit n Identifier bit n001	
0	х	х	Accept
1	0	0	Accept
1	0	1	Reject
1	1	0	Reject
1	1	1	Accept

**Legend:** x = don't care

As shown in the receive buffer block diagram (Figure 19-4), acceptance filters RXF0 and RXF1 and filter mask RXM0 are associated with RXB0. Filters RXF2, RXF3, RXF4 and RXF5 and mask RXM1 are associated with RXB1. When a filter matches and a message is loaded into the receive buffer, the filter number that enabled the message reception is loaded into the FILHIT bit(s).

For RXB1, the RXB1CON register contains the FILHIT<2:0> bits. They are coded as follows:

- 101 = Acceptance Filter 5 (RXF5)
- 100 = Acceptance Filter 4 (RXF4)
- 011 = Acceptance Filter 3 (RXF3)
- 010 = Acceptance Filter 2 (RXF2)
- 001 = Acceptance Filter 1 (RXF1)
- 000 = Acceptance Filter 0 (RXF0)

Note: '000' and '001' can only occur if the RXB0DBEN bit is set in the RXB0CON register allowing RXB0 messages to rollover into RXB1.

The coding of the RXB0DBEN bit enables these three bits to be used similarly to the FILHIT bits and to distinguish a hit on filter RXF0 and RXF1, in either RXB0. or after a rollover into RXB1.


- 111 = Acceptance Filter 1 (RXF1)
- 110 = Acceptance Filter 0 (RXF0)
- 001 = Acceptance Filter 1 (RXF1)
- 000 = Acceptance Filter 0

If the RXB0DBEN bit is clear, there are six codes corresponding to the six filters. If the RXB0DBEN bit is set, there are six codes corresponding to the six filters plus two additional codes corresponding to RXF0 and RXF1 filters that rollover into RXB1.

If more than one acceptance filter matches, the FILHIT bits will encode the binary value of the lowest numbered filter that matched. In other words, if filter RXF2 and filter RXF4 match, FILHIT will be loaded with the value for RXF2. This essentially prioritizes the acceptance filters with a lower number filter having higher priority. Messages are compared to filters in ascending order of filter number.

The mask and filter registers can only be modified when the PIC18FXX8 is in Configuration mode. The mask and filter registers cannot be read outside of Configuration mode. When outside of Configuration mode, all mask and filter registers will be read as '0'.

FIGURE 19-6: MESSAGE ACCEPTANCE MASK AND FILTER OPERATION



### 19.7 Baud Rate Setting

All nodes on a given CAN bus must have the same nominal bit rate. The CAN protocol uses Non-Return-to-Zero (NRZ) coding which does not encode a clock within the data stream. Therefore, the receive clock must be recovered by the receiving nodes and synchronized to the transmitters clock.

As oscillators and transmission time may vary from node to node, the receiver must have some type of Phase Lock Loop (PLL) synchronized to data transmission edges to synchronize and maintain the receiver clock. Since the data is NRZ coded, it is necessary to include bit stuffing to ensure that an edge occurs at least every six bit times to maintain the Digital Phase Lock Loop (DPLL) synchronization.

The bit timing of the PIC18FXX8 is implemented using a DPLL that is configured to synchronize to the incoming data and provides the nominal timing for the transmitted data. The DPLL breaks each bit time into multiple segments made up of minimal periods of time called the *Time Quanta* (TQ).

Bus timing functions executed within the bit time frame, such as synchronization to the local oscillator, network transmission delay compensation and sample point positioning, are defined by the programmable bit timing logic of the DPLL.

All devices on the CAN bus must use the same bit rate. However, all devices are not required to have the same master oscillator clock frequency. For the different clock frequencies of the individual devices, the bit rate has to be adjusted by appropriately setting the baud rate prescaler and number of time quanta in each segment.

The *Nominal Bit Rate* is the number of bits transmitted per second, assuming an ideal transmitter with an ideal oscillator, in the absence of resynchronization. The nominal bit rate is defined to be a maximum of 1 Mb/s.

The Nominal Bit Time is defined as:

TBIT = 1/Nominal Bit Rate

The nominal bit time can be thought of as being divided into separate, non-overlapping time segments. These segments (Figure 19-7) include:

- Synchronization Segment (Sync\_Seg)
- Propagation Time Segment (Prop\_Seg)
- Phase Buffer Segment 1 (Phase\_Seg1)
- Phase Buffer Segment 2 (Phase\_Seg2)


The time segments (and thus, the nominal bit time) are, in turn, made up of integer units of time called time quanta or TQ (see Figure 19-7). By definition, the nominal bit time is programmable from a minimum of 8 TQ to a maximum of 25 TQ. Also, by definition, the minimum nominal bit time is 1  $\mu$ s corresponding to a maximum 1 Mb/s rate. The actual duration is given by the relationship:

The time quantum is a fixed unit derived from the oscillator period. It is also defined by the programmable baud rate prescaler, with integer values from 1 to 64, in addition to a fixed divide-by-two for clock generation. Mathematically, this is

$$T_{Q}(\mu s) = (2 * (BRP + 1))/Fosc (MHz)$$
  
or  
 $T_{Q}(\mu s) = (2 * (BRP + 1)) * Tosc (\mu s)$ 

where Fosc is the clock frequency, Tosc is the corresponding oscillator period and BRP is an integer (0 through 63) represented by the binary values of BRGCON1<5:0>.

### FIGURE 19-7: BIT TIME PARTITIONING



### 19.7.1 TIME QUANTA

As already mentioned, the time quanta is a fixed unit derived from the oscillator period and baud rate prescaler. Its relationship to TBIT and the nominal bit rate is shown in Example 19-2.

# EXAMPLE 19-2: CALCULATING TQ, NOMINAL BIT RATE AND NOMINAL BIT TIME

 $TQ~(\mu s) = (2~*(BRP+1))/FOSC~(MHz)$   $TBIT~(\mu s) = TQ~(\mu s)~*number~of~TQ~per~bit~interval$  Nominal~Bit~Rate~(bits/s) = 1/TBIT

### CASE 1:

For Fosc = 16 MHz, BRP<5:0> = 00h and Nominal Bit Time = 8 TQ:

 $T_Q = (2 * 1)/16 = 0.125 \,\mu s \,(125 \,ns)$  $T_{BIT} = 8 * 0.125 = 1 \,\mu s \,(10^{-6}s)$ 

Nominal Bit Rate =  $1/10^{-6} = 10^{6}$  bits/s (1 Mb/s)

### CASE 2:

For FOSC = 20 MHz, BRP<5:0> = 01h and Nominal Bit Time = 8 TQ:

 $TQ = (2 * 2)/20 = 0.2 \ \mu s \ (200 \ ns)$  $TBIT = 8 * 0.2 = 1.6 \ \mu s \ (1.6 * 10^{-6} s)$ 

Nominal Bit Rate =  $1/1.6 * 10^{-6}$ s = 625,000 bits/s (625 Kb/s)

### CASE 3:

For Fosc = 25 MHz, BRP<5:0> = 3Fh and Nominal Bit Time = 25 TQ:

 $T_Q = (2 * 64)/25 = 5.12 \ \mu s$ 

TBIT =  $25 * 5.12 = 128 \,\mu s \,(1.28 * 10^{-4} s)$ 

Nominal Bit Rate =  $1/1.28 * 10^{-4} = 7813 \text{ bits/s}$ (7.8 Kb/s)

The frequencies of the oscillators in the different nodes must be coordinated in order to provide a system wide specified nominal bit time. This means that all oscillators must have a Tosc that is an integral divisor of TQ. It should also be noted that although the number of TQ is programmable from 4 to 25, the usable minimum is 8 TQ. A bit time of less than 8 TQ in length is not ensured to operate correctly.

### 19.7.2 SYNCHRONIZATION SEGMENT

This part of the bit time is used to synchronize the various CAN nodes on the bus. The edge of the input signal is expected to occur during the sync segment. The duration is 1 TQ.

### 19.7.3 PROPAGATION SEGMENT

This part of the bit time is used to compensate for physical delay times within the network. These delay times consist of the signal propagation time on the bus line and the internal delay time of the nodes. The length of the Propagation Segment can be programmed from 1 TQ to 8 TQ by setting the PRSEG2:PRSEG0 bits.

### 19.7.4 PHASE BUFFER SEGMENTS

The phase buffer segments are used to optimally locate the sampling point of the received bit within the nominal bit time. The sampling point occurs between Phase Segment 1 and Phase Segment 2. These segments can be lengthened or shortened by the resynchronization process. The end of Phase Segment 1 determines the sampling point within a bit time. Phase Segment 1 is programmable from 1 To to 8 To in duration. Phase Segment 2 provides delay before the next transmitted data transition and is also programmable from 1 To to 8 To in duration. However, due to IPT requirements, the actual minimum length of Phase Segment 2 is 2 To or it may be defined to be equal to the greater of Phase Segment 1 or the Information Processing Time (IPT).

### 19.7.5 SAMPLE POINT

The sample point is the point of time at which the bus level is read and the value of the received bit is determined. The sampling point occurs at the end of Phase Segment 1. If the bit timing is slow and contains many To, it is possible to specify multiple sampling of the bus line at the sample point. The value of the received bit is determined to be the value of the majority decision of three values. The three samples are taken at the sample point and twice before, with a time of To/2 between each sample.

### 19.7.6 INFORMATION PROCESSING TIME

The Information Processing Time (IPT) is the time segment, starting at the sample point, that is reserved for calculation of the subsequent bit level. The CAN specification defines this time to be less than or equal to 2 Tq. The PIC18FXX8 defines this time to be 2 Tq. Thus, Phase Segment 2 must be at least 2 Tq long.

### 19.8 Synchronization

To compensate for phase shifts between the oscillator frequencies of each of the nodes on the bus, each CAN controller must be able to synchronize to the relevant signal edge of the incoming signal. When an edge in the transmitted data is detected, the logic will compare the location of the edge to the expected time (Sync\_Seg). The circuit will then adjust the values of Phase Segment 1 and Phase Segment 2, as necessary. There are two mechanisms used for synchronization.

### 19.8.1 HARD SYNCHRONIZATION

Hard synchronization is only done when there is a recessive to dominant edge during a bus Idle condition, indicating the start of a message. After hard synchronization, the bit time counters are restarted with Sync\_Seg. Hard synchronization forces the edge which has occurred to lie within the synchronization segment of the restarted bit time. Due to the rules of synchronization, if a hard synchronization occurs, there will not be a resynchronization within that bit time.

### 19.8.2 RESYNCHRONIZATION

As a result of resynchronization, Phase Segment 1 may be lengthened or Phase Segment 2 may be shortened. The amount of lengthening or shortening of the phase buffer segments has an upper bound given by the Synchronization Jump Width (SJW). The value of the SJW will be added to Phase Segment 1 (see Figure 19-8) or subtracted from Phase Segment 2 (see Figure 19-9). The SJW is programmable between 1 TQ and 4 TQ.

Clocking information will only be derived from recessive to dominant transitions. The property, that only a fixed maximum number of successive bits have the same value, ensures resynchronization to the bit stream during a frame.

The phase error of an edge is given by the position of the edge relative to Sync\_Seg, measured in TQ. The phase error is defined in magnitude of TQ as follows:

- e = 0 if the edge lies within Sync\_Seg.
- e > 0 if the edge lies before the sample point.
- e < 0 if the edge lies after the sample point of the previous bit.

If the magnitude of the phase error is less than or equal to the programmed value of the synchronization jump width, the effect of a resynchronization is the same as that of a hard synchronization.

If the magnitude of the phase error is larger than the synchronization jump width and if the phase error is positive, then Phase Segment 1 is lengthened by an amount equal to the synchronization jump width.

If the magnitude of the phase error is larger than the resynchronization jump width and if the phase error is negative, then Phase Segment 2 is shortened by an amount equal to the synchronization jump width.

### 19.8.3 SYNCHRONIZATION RULES

- Only one synchronization within one bit time is allowed.
- An edge will be used for synchronization only if the value detected at the previous sample point (previously read bus value) differs from the bus value immediately after the edge.
- All other recessive to dominant edges, fulfilling rules 1 and 2, will be used for resynchronization with the exception that a node transmitting a dominant bit will not perform a resynchronization as a result of a recessive to dominant edge with a positive phase error.







FIGURE 19-9: SHORTENING A BIT PERIOD (SUBTRACTING SJW FROM PHASE SEGMENT 2)



### 19.9 Programming Time Segments

Some requirements for programming of the time segments:

- Prop Seg + Phase Seg 1 ≥ Phase Seg 2
- Phase Seg 2 ≥ Sync Jump Width

For example, assume that a 125 kHz CAN baud rate is desired using 20 MHz for Fosc. With a Tosc of 50 ns, a baud rate prescaler value of 04h gives a TQ of 500 ns. To obtain a nominal bit rate of 125 kHz, the nominal bit time must be 8  $\mu s$  or 16 TQ.

Using 1 TQ for the Sync Segment, 2 TQ for the Propagation Segment and 7 TQ for Phase Segment 1 would place the sample point at 10 TQ after the transition. This leaves 6 TQ for Phase Segment 2.

By the rules above, the Sync Jump Width could be the maximum of 4 Tq. However, normally a large SJW is only necessary when the clock generation of the different nodes is inaccurate or unstable, such as using ceramic resonators. Typically, an SJW of 1 is enough.

### 19.10 Oscillator Tolerance

As a rule of thumb, the bit timing requirements allow ceramic resonators to be used in applications with transmission rates of up to 125 Kbit/sec. For the full bus speed range of the CAN protocol, a quartz oscillator is required. A maximum node-to-node oscillator variation of 1.7% is allowed.

# 19.11 Bit Timing Configuration Registers

The Configuration registers (BRGCON1, BRGCON2, BRGCON3) control the bit timing for the CAN bus interface. These registers can only be modified when the PIC18FXX8 is in Configuration mode.

### 19.11.1 BRGCON1

The BRP bits control the baud rate prescaler. The SJW<1:0> bits select the synchronization jump width in terms of multiples of To.

### 19.11.2 BRGCON2

The PRSEG bits set the length of the Propagation Segment in terms of Tq. The SEG1PH bits set the length of Phase Segment 1 in TQ. The SAM bit controls how many times the RXCAN pin is sampled. Setting this bit to a '1' causes the bus to be sampled three times; twice at TQ/2 before the sample point and once at the normal sample point (which is at the end of Phase Segment 1). The value of the bus is determined to be the value read during at least two of the samples. If the SAM bit is set to a '0', then the RXCAN pin is sampled only once at the sample point. The SEG2PHTS bit controls how the length of Phase Segment 2 is determined. If this bit is set to a '1', then the length of Phase Segment 2 is determined by the SEG2PH bits of BRGCON3. If the SEG2PHTS bit is set to a '0', then the length of Phase Segment 2 is the greater of Phase Segment 1 and the information processing time (which is fixed at 2 TQ for the PIC18FXX8).

### 19.11.3 BRGCON3

The PHSEG2<2:0> bits set the length (in TQ) of Phase Segment 2 if the SEG2PHTS bit is set to a '1'. If the SEG2PHTS bit is set to a '0', then the PHSEG2<2:0> bits have no effect.

### 19.12 Error Detection

The CAN protocol provides sophisticated error detection mechanisms. The following errors can be detected.

### 19.12.1 CRC ERROR

With the Cyclic Redundancy Check (CRC), the transmitter calculates special check bits for the bit sequence, from the start of a frame until the end of the data field. This CRC sequence is transmitted in the CRC field. The receiving node also calculates the CRC sequence using the same formula and performs a comparison to the received sequence. If a mismatch is detected, a CRC error has occurred and an error frame is generated. The message is repeated.

### 19.12.2 ACKNOWLEDGE ERROR

In the Acknowledge field of a message, the transmitter checks if the Acknowledge slot (which was sent out as a recessive bit) contains a dominant bit. If not, no other node has received the frame correctly. An Acknowledge Error has occurred; an error frame is generated and the message will have to be repeated.

### 19.12.3 FORM ERROR

If a node detects a dominant bit in one of the four segments, including end of frame, interframe space, Acknowledge delimiter or CRC delimiter, then a Form Error has occurred and an error frame is generated. The message is repeated.

### 19.12.4 BIT ERROR

A Bit Error occurs if a transmitter sends a dominant bit and detects a recessive bit, or if it sends a recessive bit and detects a dominant bit, when monitoring the actual bus level and comparing it to the just transmitted bit. In the case where the transmitter sends a recessive bit and a dominant bit is detected during the arbitration field and the Acknowledge slot, no Bit Error is generated because normal arbitration is occurring.

### 19.12.5 STUFF BIT ERROR

If, between the start of frame and the CRC delimiter, six consecutive bits with the same polarity are detected, the bit stuffing rule has been violated. A Stuff Bit Error occurs and an error frame is generated. The message is repeated.

### 19.12.6 ERROR STATES


Detected errors are made public to all other nodes via error frames. The transmission of the erroneous message is aborted and the frame is repeated as soon as possible. Furthermore, each CAN node is in one of the three error states "error-active", "error-passive" or "bus-off" according to the value of the internal error counters. The error-active state is the usual state, where the bus node can transmit messages and activate error frames (made of dominant bits) without any restrictions. In the error-passive state, messages and passive error frames (made of recessive bits) may be transmitted. The bus-off state makes it temporarily impossible for the station to participate in the bus communication. During this state, messages can neither be received nor transmitted.


### 19.12.7 ERROR MODES AND ERROR COUNTERS

The PIC18FXX8 contains two error counters: the Receive Error Counter (RXERRCNT) and the Transmit Error Counter (TXERRCNT). The values of both counters can be read by the MCU. These counters are incremented or decremented in accordance with the CAN bus specification.

The PIC18FXX8 is error-active if both error counters are below the error-passive limit of 128. It is error-passive if at least one of the error counters equals or exceeds 128. It goes to bus-off if the transmit error counter equals or exceeds the bus-off limit of 256. The device remains in this state until the bus-off recovery sequence is received. The bus-off recovery sequence consists of 128 occurrences of 11 consecutive recessive bits (see Figure 19-10). Note that the CAN module, after going bus-off, will recover back to erroractive without any intervention by the MCU if the bus remains Idle for 128 x 11 bit times. If this is not desired, the error Interrupt Service Routine should address this. The current error mode of the CAN module can be read by the MCU via the COMSTAT register.

Additionally, there is an Error State Warning flag bit, EWARN, which is set if at least one of the error counters equals or exceeds the error warning limit of 96. EWARN is reset if both error counters are less than the error warning limit.





### 19.13 CAN Interrupts

The module has several sources of interrupts. Each of these interrupts can be individually enabled or disabled. The CANINTF register contains interrupt flags. The CANINTE register contains the enables for the 8 main interrupts. A special set of read-only bits in the CANSTAT register, the ICODE bits, can be used in combination with a jump table for efficient handling of interrupts.

All interrupts have one source, with the exception of the error interrupt. Any of the error interrupt sources can set the error interrupt flag. The source of the error interrupt can be determined by reading the Communication Status register, COMSTAT.

The interrupts can be broken up into two categories: receive and transmit interrupts.

The receive related interrupts are:

- Receive Interrupts
- · Wake-up Interrupt
- Receiver Overrun Interrupt
- · Receiver Warning Interrupt
- · Receiver Error-Passive Interrupt

The transmit related interrupts are:

- Transmit Interrupts
- Transmitter Warning Interrupt
- Transmitter Error-Passive Interrupt
- Bus-Off Interrupt

#### 19.13.1 INTERRUPT CODE BITS

The source of a pending interrupt is indicated in the ICODE (Interrupt Code) bits of the CANSTAT register (ICODE<2:0>). Interrupts are internally prioritized such that the higher priority interrupts are assigned lower ICODE values. Once the highest priority interrupt condition has been cleared, the code for the next highest priority interrupt that is pending (if any) will be reflected by the ICODE bits (see Table 19-3, following page). Note that only those interrupt sources that have their associated CANINTE enable bit set will be reflected in the ICODE bits.

#### 19.13.2 TRANSMIT INTERRUPT

When the transmit interrupt is enabled, an interrupt will be generated when the associated transmit buffer becomes empty and is ready to be loaded with a new message. The TXBnIF bit will be set to indicate the source of the interrupt. The interrupt is cleared by the MCU resetting the TXBnIF bit to a '0'.

### 19.13.3 RECEIVE INTERRUPT

When the receive interrupt is enabled, an interrupt will be generated when a message has been successfully received and loaded into the associated receive buffer. This interrupt is activated immediately after receiving the EOF field. The RXBnIF bit will be set to indicate the source of the interrupt. The interrupt is cleared by the MCU resetting the RXBnIF bit to a '0'.

TABLE 19-3: VALUES FOR ICODE<2:0>

ICOD <2:0>	Interrupt	Boolean Expression
000	None	ERR•WAK•TX0•TX1•TX2•RX0•
001	Error	ERR
010	TXB2	ERR•TX0•TX1•TX2
011	TXB1	ERR•TX0•TX1
100	TXB0	ERR•TX0
101	RXB1	ERR•TX0•TX1•TX2•RX0•RX1
110	RXB0	ERR•TX0•TX1•TX2•RX0
111	Wake on Interrupt	ERR•TX0•TX1•TX2•RX0•RX1• WAK
Key:	ERRIF * ERI	RIE RX0 = RXB0IF * RXB0IE
	XB0IF * TXE	
	XB1IF * TXE XB2IF * TXE	

### 19.13.4 MESSAGE ERROR INTERRUPT

When an error occurs during transmission or reception of a message, the message error flag IRXIF will be set and if the IRXIE bit is set, an interrupt will be generated. This is intended to be used to facilitate baud rate determination when used in conjunction with Listen Only mode.

### 19.13.5 BUS ACTIVITY WAKE-UP INTERRUPT

When the PIC18FXX8 is in Sleep mode and the bus activity wake-up interrupt is enabled, an interrupt will be generated and the WAKIF bit will be set when activity is detected on the CAN bus. This interrupt causes the PIC18FXX8 to exit Sleep mode. The interrupt is reset by the MCU, clearing the WAKIF bit.

### 19.13.6 ERROR INTERRUPT

When the error interrupt is enabled, an interrupt is generated if an overflow condition occurs or if the error state of transmitter or receiver has changed. The error flags in COMSTAT will indicate one of the following conditions.

### 19.13.6.1 Receiver Overflow

An overflow condition occurs when the MAB has assembled a valid received message (the message meets the criteria of the acceptance filters) and the receive buffer associated with the filter is not available for loading of a new message. The associated COMSTAT.RXnOVFL bit will be set to indicate the overflow condition. This bit must be cleared by the MCU.

### 19.13.6.2 Receiver Warning

The receive error counter has reached the MCU warning limit of 96.

### 19.13.6.3 Transmitter Warning

The transmit error counter has reached the MCU warning limit of 96.

### 19.13.6.4 Receiver Bus Passive

The receive error counter has exceeded the errorpassive limit of 127 and the device has gone to error-passive state.

### 19.13.6.5 Transmitter Bus Passive

The transmit error counter has exceeded the errorpassive limit of 127 and the device has gone to error-passive state.

### 19.13.6.6 Bus-Off

The transmit error counter has exceeded 255 and the device has gone to bus-off state.

### 19.13.7 INTERRUPT ACKNOWLEDGE

Interrupts are directly associated with one or more status flags in the PIR register. Interrupts are pending as long as one of the flags is set. Once an interrupt flag is set by the device, the flag cannot be reset by the microcontroller until the interrupt condition is removed.

# www.DataPIC18FXX8

NOTES:

### 20.0 COMPATIBLE 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The Analog-to-Digital (A/D) Converter module has five inputs for the PIC18F2X8 devices and eight for the PIC18F4X8 devices. This module has the ADCON0 and ADCON1 register definitions that are compatible with the PICmicro® mid-range A/D module.

The A/D allows conversion of an analog input signal to a corresponding 10-bit digital number.

The A/D module has four registers. These registers are:

- A/D Result High Register (ADRESH)
- A/D Result Low Register (ADRESL)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)

The ADCON0 register, shown in Register 20-1, controls the operation of the A/D module. The ADCON1 register, shown in Register 20-2, configures the functions of the port pins.

### REGISTER 20-1: ADCON0: A/D CONTROL REGISTER 0

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0
ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON
hit 7							bit 0

### bit 7-6 ADCS1:ADCS0: A/D Conversion Clock Select bits (ADCON0 bits in bold)

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion				
0	00	Fosc/2				
0	01	Fosc/8				
0	10	Fosc/32				
0	11	FRC (clock derived from the internal A/D RC oscillator)				
1	0.0	Fosc/4				
1	01	Fosc/16				
1	10	Fosc/64				
1	11	FRC (clock derived from the internal A/D RC oscillator)				

### bit 5-3 CHS2:CHS0: Analog Channel Select bits

- 000 = Channel 0 (AN0)
- 001 = Channel 1 (AN1)
- 010 = Channel 2 (AN2)
- 011 = Channel 3 (AN3)
- 100 = Channel 4 (AN4)
- 101 = Channel 5 (AN5)(1)
- 110 = Channel 6 (AN6)(1)
- 111 = Channel 7 (AN7)<sup>(1)</sup>

**Note 1:** These channels are unimplemented on PIC18F2X8 (28-pin) devices. Do not select any unimplemented channel.

### bit 2 GO/DONE: A/D Conversion Status bit

### When ADON = 1:

- 1 = A/D conversion in progress (setting this bit starts the A/D conversion which is automatically cleared by hardware when the A/D conversion is complete)
- 0 = A/D conversion not in progress

### bit 1 Unimplemented: Read as '0'

- bit 0 ADON: A/D On bit
  - 1 = A/D converter module is powered up
  - 0 = A/D converter module is shut-off and consumes no operating current

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### PIC18FXX8

#### **ADCON1: A/D CONTROL REGISTER 1** REGISTER 20-2:

R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0
bit 7							bit 0

bit 0

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified. Six (6) Most Significant bits of ADRESH are read as '0'.

0 = Left justified. Six (6) Least Significant bits of ADRESL are read as '0'.

ADCS2: A/D Conversion Clock Select bit (ADCON1 bits in bold) bit 6

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion
0	0.0	Fosc/2
0	01	Fosc/8
0	10	Fosc/32
0	11	FRC (clock derived from the internal A/D RC oscillator)
1	0 0	Fosc/4
1	01	Fosc/16
1	10	Fosc/64
1	11	FRC (clock derived from the internal A/D RC oscillator)

bit 5-4 Unimplemented: Read as '0'

bit 3-0 PCFG3:PCFG0: A/D Port Configuration Control bits

PCFG	AN7	AN6	AN5	AN4	AN3	AN2	AN1	AN0	VREF+	VREF-	C/R
0000	Α	Α	Α	Α	Α	Α	Α	Α	VDD	Vss	8/0
0001	Α	Α	Α	Α	VREF+	Α	Α	Α	AN3	Vss	7/1
0010	D	D	D	Α	Α	Α	Α	Α	VDD	Vss	5/0
0011	D	D	D	Α	VREF+	Α	Α	Α	AN3	Vss	4/1
0100	D	D	D	D	Α	D	Α	Α	VDD	Vss	3/0
0101	D	D	D	D	VREF+	D	Α	Α	AN3	Vss	2/1
011x	D	D	D	D	D	D	D	D	_	_	0/0
1000	Α	Α	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	6/2
1001	D	D	Α	Α	Α	Α	Α	Α	VDD	Vss	6/0
1010	D	D	Α	Α	VREF+	Α	Α	Α	AN3	Vss	5/1
1011	D	D	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	4/2
1100	D	D	D	Α	VREF+	VREF-	Α	Α	AN3	AN2	3/2
1101	D	D	D	D	VREF+	VREF-	Α	Α	AN3	AN2	2/2
1110	D	D	D	D	D	D	D	Α	VDD	Vss	1/0
1111	D	D	D	D	VREF+	VREF-	D	Α	AN3	AN2	1/2

A = Analog input D = Digital I/O

C/R = # of analog input channels/# of A/D voltage references

Shaded cells indicate channels available only on PIC18F4X8 devices.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note: On any device Reset, the port pins that are multiplexed with analog functions (ANx) are forced to be analog inputs.

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (VDD and Vss) or the voltage level on the RA3/AN3/ VREF+ pin and RA2/AN2/VREF- pin.

The A/D converter has a unique feature of being able to operate while the device is in Sleep mode. To operate in Sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.


The output of the sample and hold is the input into the converter which generates the result via successive approximation.

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off and any conversion is aborted.

Each port pin associated with the A/D converter can be configured as an analog input (RA3 can also be a voltage reference) or as a digital I/O.

The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH/ADRESL registers, the GO/DONE bit (ADCON0<2>) is cleared and A/D Interrupt Flag bit, ADIF, is set. The block diagram of the A/D module is shown in Figure 20-1.

**FIGURE 20-1:** A/D BLOCK DIAGRAM



### www.DataPIC18FXX8

The value that is in the ADRESH/ADRESL registers is not modified for a Power-on Reset. The ADRESH/ADRESL registers will contain unknown data after a Power-on Reset.

After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see **Section 20.1** "A/D Acquisition Requirements". After this acquisition time has elapsed, the A/D conversion can be started. The following steps should be followed for doing an A/D conversion:

- 1. Configure the A/D module:
  - Configure analog pins, voltage reference and digital I/O (ADCON1)
  - Select A/D input channel (ADCON0)
  - Select A/D conversion clock (ADCON0)
  - Turn on A/D module (ADCON0)
- 2. Configure A/D interrupt (if desired):
  - · Clear ADIF bit
  - · Set ADIE bit
  - · Set GIE bit
- 3. Wait the required acquisition time.
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0)
- 5. Wait for A/D conversion to complete, by either:
  - Polling for the GO/DONE bit to be cleared OR
  - Waiting for the A/D interrupt


- Read A/D Result registers (ADRESH/ADRESL); clear bit ADIF if required.
- For next conversion, go to step 1 or step 2 as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before next acquisition starts.

### 20.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 20-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 2.5 k $\Omega$ . After the analog input channel is selected (changed), this acquisition must be done before the conversion can be started.

**Note:** When the conversion is started, the holding capacitor is disconnected from the input pin.

### FIGURE 20-2: ANALOG INPUT MODEL



To calculate the minimum acquisition time, Equation 20-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

Example 20-1 shows the calculation of the minimum required acquisition time TACQ. This calculation is based on the following application system assumptions:

• CHOLD = 120 pF • Rs = 2.5 k $\Omega$ • Conversion Error  $\leq$  1/2 LSb

• VDD =  $5V \rightarrow Rss = 7 \text{ k}\Omega$ • Temperature =  $50^{\circ}\text{C}$  (system max.) • VHOLD =  $0V \otimes time = 0$ 

### **EQUATION 20-1: ACQUISITION TIME**

```
TACQ = Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient
= TAMP + TC + TCOFF
```

### **EQUATION 20-2: A/D MINIMUM CHARGING TIME**

```
VHOLD = (VREF - (VREF/2048)) \cdot (1 - e^{(-Tc/CHOLD(RIC + RSS + RS))})

or

Tc = -(120 \text{ pF})(1 \text{ k}\Omega + \text{Rss} + \text{Rs}) \ln(1/2047)
```

### **EXAMPLE 20-1: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME**

```
TacQ = Tamp + Tc + Tcoff

Temperature coefficient is only required for temperatures > 25°C.

TacQ = 2 \mu s + Tc + [(Temp - 25°C)(0.05 \mu s/°C)]

Tc = -Chold (Ric + Rss + Rs) ln(1/2047)
-120 pF (1 kΩ + 7 kΩ + 2.5 kΩ) ln(0.0004885)
-120 pF (10.5 kΩ) ln(0.0004885)
-1.26 μs (-7.6241)
9.61 μs

TacQ = 2 \mu s + 9.61 \mu s + [(50°C - 25°C)(0.05 \mu s/°C)]
11.61 μs + 1.25 μs
12.86 μs
```

Note: When using external voltage references with the A/D converter, the source impedance of the external voltage references must be less than  $20\Omega$  to obtain the specified A/D resolution. Higher reference source impedances will increase both offset and gain errors. Resistive voltage dividers will not provide a sufficiently low source impedance.

To maintain the best possible performance in A/D conversions, external VREF inputs should be buffered with an operational amplifier or other low output impedance circuit.

### 20.2 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 12 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable. The seven possible options for TAD are:

- 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- · Internal RC oscillator.

For correct A/D conversions, the A/D conversion clock (TAD) must be selected to ensure a minimum TAD time of 1.6  $\mu$ s.

Table 20-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

### 20.3 Configuring Analog Port Pins

The ADCON1, TRISA and TRISE registers control the operation of the A/D port pins. The port pins that are desired as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS2:CHS0 bits and the TRIS bits.

- Note 1: When reading the port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs will convert an analog input. Analog levels on a digitally configured input will not affect the conversion accuracy.
  - 2: Analog levels on any pin that is defined as a digital input (including the AN4:AN0 pins) may cause the input buffer to consume current that is out of the device's specification.

TABLE 20-1: TAD vs. DEVICE OPERATING FREQUENCIES

AD Clock Source (TAD)		Device Frequency					
Operation ADCS2:ADCS0		20 MHz	5 MHz	1.25 MHz	333.33 kHz		
2 Tosc	000	100 ns <sup>(2)</sup>	400 ns <sup>(2)</sup>	1.6 µs	6 μs		
4 Tosc	100	200 ns <sup>(2)</sup>	800 ns <sup>(2)</sup>	3.2 μs	12 μs		
8 Tosc	001	400 ns <sup>(2)</sup>	1.6 µs	6.4 μs	24 μs <sup>(3)</sup>		
16 Tosc	101	800 ns <sup>(2)</sup>	3.2 μs	12.8 μs	48 μs <sup>(3)</sup>		
32 Tosc	010	1.6 µs	6.4 μs	25.6 μs <sup>(3)</sup>	96 μs <sup>(3)</sup>		
64 Tosc	110	3.2 μs	12.8 µs	51.2 μs <sup>(3)</sup>	192 μs <sup>(3)</sup>		
RC	011	2-6 μs <sup>(1)</sup>	2-6 μs <sup>(1)</sup>	2-6 μs <sup>(1)</sup>	2-6 μs <sup>(1)</sup>		

**Legend:** Shaded cells are outside of recommended range.

Note 1: The RC source has a typical TAD time of  $4 \mu s$ .

2: These values violate the minimum required TAD time.

3: For faster conversion times, the selection of another clock source is recommended.

TABLE 20-2: TAD vs. DEVICE OPERATING FREQUENCIES (FOR EXTENDED, LF DEVICES)

AD Clock Source (TAD)		Device Frequency					
Operation ADCS2:ADCS0		4 MHz 2 MHz		1.25 MHz	333.33 kHz		
2 Tosc	000	500 ns <sup>(2)</sup>	1.0 μs <sup>(2)</sup>	1.6 μs <sup>(2)</sup>	6 μs		
4 Tosc	100	1.0 μs <sup>(2)</sup>	2.0 μs <sup>(2)</sup>	3.2 μs <sup>(2)</sup>	12 μs		
8 Tosc	001	2.0 μs <sup>(2)</sup>	4.0 μs	6.4 μs	24 μs <sup>(3)</sup>		
16 Tosc	101	4.0 μs <sup>(2)</sup>	8.0 µs	12.8 μs	48 μs <sup>(3)</sup>		
32 Tosc	010	8.0 µs	16.0 μs	25.6 μs <sup>(3)</sup>	96 μs <sup>(3)</sup>		
64 Tosc	110	16.0 μs	32.0 μs	51.2 μs <sup>(3)</sup>	192 μs <sup>(3)</sup>		
RC	011	3-9 μs <sup>(1)</sup>	3-9 μs <sup>(1)</sup>	3-9 μs <sup>(1)</sup>	3-9 μs <sup>(1)</sup>		

Legend: Shaded cells are outside of recommended range.

Note 1: The RC source has a typical TAD time of 6  $\mu$ s.

2: These values violate the minimum required TAD time.

3: For faster conversion times, the selection of another clock source is recommended.

### 20.4 A/D Conversions


Figure 20-4 shows the operation of the A/D converter after the GO bit has been set. Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D Result register pair will not be updated with the partially completed A/D conversion sample. That is, the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion (or the last value written to the ADRESH:ADRESL registers). After the A/D conversion is aborted, a 2 TAD wait is required before the next acquisition is started. After this 2 TAD wait, acquisition on the selected channel is automatically started.

**Note:** The GO/DONE bit should **NOT** be set in the same instruction that turns on the A/D.

### 20.4.1 A/D RESULT REGISTERS

The ADRESH:ADRESL register pair is the location where the 10-bit A/D result is loaded at the completion of the A/D conversion. This register pair is 16 bits wide. The A/D module gives the flexibility to left or right justify the 10-bit result in the 16-bit result register. The A/D Format Select bit (ADFM) controls this justification. Figure 20-3 shows the operation of the A/D result justification. The extra bits are loaded with '0's. When an A/D result will not overwrite these locations (A/D disable), these registers may be used as two general purpose 8-bit registers.





### 20.5 Use of the ECCP Trigger

An A/D conversion can be started by the "special event trigger" of the ECCP module. This requires that the ECCP1M3:ECCP1M0 bits (ECCP1CON<3:0>) be programmed as '1011' and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/DONE bit will be set, starting the A/D conversion and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the A/D

acquisition period with minimal software overhead (moving ADRESH/ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition done before the "special event trigger" sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), the "special event trigger" will be ignored by the A/D module but will still reset the Timer1 (or Timer3) counter.

### FIGURE 20-4: A/D CONVERSION TAD CYCLES




TABLE 20-3: SUMMARY OF A/D REGISTERS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
PIR2	_	CMIF <sup>(1)</sup>	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>	-0-0 0000	-0-0 0000
PIE2	_	CMIE <sup>(1)</sup>	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>	-0-0 0000	-0-0 0000
IPR2	_	CMIP <sup>(1)</sup>	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP <sup>(1)</sup>	-1-1 1111	-1-1 1111
ADRESH	A/D Result Register								xxxx xxxx	uuuu uuuu
ADRESL	A/D Result Register								xxxx xxxx	uuuu uuuu
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	0000 00-0
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000
PORTA	_	RA6	RA5	RA4	RA3	RA2	RA1	RA0	-x0x 0000	-u0u 0000
TRISA	PORTA Data Direction Register							-111 1111	-111 1111	
PORTE	_	_	_	_	_	RE2	RE1	RE0	xxx	000
LATE	_	_	_	_		LATE2	LATE1	LATE0	xxx	uuu
TRISE	IBF	OBF	IBOV	PSPMODE		TRISE2	TRISE1	TRISE0	0000 -111	0000 -111

 $\textbf{Legend:} \hspace{0.5cm} x = \text{unknown}, \ u = \text{unchanged}, \ - = \text{unimplemented}, \ \text{read as `0'}. \ Shaded \ \text{cells are not used for A/D conversion}.$ 

Note 1: These bits are reserved on PIC18F2X8 devices; always maintain these bits clear.

### 21.0 COMPARATOR MODULE

Note: The analog comparators are only available on the PIC18F448 and PIC18F458.

The comparator module contains two analog comparators. The inputs to the comparators are multiplexed with the RD0 through RD3 pins. The on-chip voltage reference (Section 22.0 "Comparator Voltage Reference Module") can also be an input to the comparators.

The CMCON register, shown in Register 21-1, controls the comparator input and output multiplexers. A block diagram of the comparator is shown in Figure 21-1.

### REGISTER 21-1: CMCON: COMPARATOR CONTROL REGISTER

R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
C2OUT	C10UT	C2INV	C1INV	CIS	CM2	CM1	CM0
bit 7							bit 0

bit 7 C2OUT: Comparator 2 Output bit

When C2INV = 0:

1 = C2 VIN+ > C2 VIN-

0 = C2 VIN+ < C2 VIN-

When C2INV = 1:

1 = C2 VIN+ < C2 VIN-

0 = C2 Vin+ > C2 Vin-

bit 6 **C1OUT**: Comparator 1 Output bit

When C1INV = 0:

1 = C1 Vin+ > C1 Vin-

0 = C1 VIN+ < C1 VIN-

When C1INV = 1:

1 = C1 VIN+ < C1 VIN-

0 = C1 Vin+ > C1 Vin-

bit 5 C2INV: Comparator 2 Output Inversion bit

1 = C2 output inverted

0 = C2 output not inverted

bit 4 C1INV: Comparator 1 Output Inversion bit

1 = C1 output inverted

0 = C1 output not inverted

bit 3 CIS: Comparator Input Switch bit

When CM2:CM0 = 110:

1 = C1 Vin-connects to RD0/PSP0

C2 VIN- connects to RD2/PSP2

0 = C1 VIN- connects to RD1/PSP1

C2 VIN- connects to RD3/PSP3

bit 2-0 CM2:CM0: Comparator Mode bits

Figure 21-1 shows the Comparator modes and CM2:CM0 bit settings.


Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### 21.1 Comparator Configuration

There are eight modes of operation for the comparators. The CMCON register is used to select these modes. Figure 21-1 shows the eight possible modes. The TRISD register controls the data direction of the comparator pins for each mode. If the Comparator mode is changed, the comparator output level may not be valid for the specified mode change delay shown in **Section 27.0** "Electrical Characteristics".

**Note:** Comparator interrupts should be disabled during a Comparator mode change; otherwise, a false interrupt may occur.

### FIGURE 21-1: COMPARATOR I/O OPERATING MODES




## 21.2 Comparator Operation

A single comparator is shown in Figure 21-2 along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 21-2 represent the uncertainty due to input offsets and response time.

## 21.3 Comparator Reference

An external or internal reference signal may be used depending on the comparator operating mode. The analog signal present at VIN- is compared to the signal at VIN+ and the digital output of the comparator is adjusted accordingly (Figure 21-2).

FIGURE 21-2: SINGLE COMPARATOR



## 21.3.1 EXTERNAL REFERENCE SIGNAL

When external voltage references are used, the comparator module can be configured to have the comparators operate from the same or different reference sources. However, threshold detector applications may require the same reference. The reference signal must be between VSS and VDD and can be applied to either pin of the comparator(s).

### 21.3.2 INTERNAL REFERENCE SIGNAL

The comparator module also allows the selection of an internally generated voltage reference for the comparators. **Section 22.0 "Comparator Voltage Reference Module"** contains a detailed description of the module that provides this signal. The internal reference signal is used when comparators are in mode CM<2:0>=110 (Figure 21-1). In this mode, the internal voltage reference is applied to the VIN+ pin of both comparators.

## 21.4 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output has a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (Section 27.0 "Electrical Characteristics").

## 21.5 Comparator Outputs

The comparator outputs are read through the CMCON register. These bits are read-only. The comparator outputs may also be directly output to the RE1 and RE2 I/O pins. When enabled, multiplexors in the output path of the RE1 and RE2 pins will switch and the output of each pin will be the unsynchronized output of the comparator. The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications. Figure 21-3 shows the comparator output block diagram.

The TRISE bits will still function as an output enable/ disable for the RE1 and RE2 pins while in this mode.

The polarity of the comparator outputs can be changed using the C2INV and C1INV bits (CMCON<4:5>).

- Note 1: When reading the Port register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input according to the Schmitt Trigger input specification.
  - 2: Analog levels on any pin defined as a digital input may cause the input buffer to consume more current than is specified.




FIGURE 21-3: COMPARATOR OUTPUT BLOCK DIAGRAM

## 21.6 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<7:6>, to determine the actual change that occurred. The CMIF bit (PIR2 register) is the Comparator Interrupt Flag. The CMIF bit must be reset by clearing '0'. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

The CMIE bit (PIE2 register) and the PEIE bit (INTCON register) must be set to enable the interrupt. In addition, the GIE bit must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

Note: If a change in the CMCON register (C1OUT or C2OUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR2 register) interrupt flag may not get set.

The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of CMCON will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition and allow flag bit CMIF to be cleared.

# 21.7 Comparator Operation During Sleep

When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode when enabled. While the comparator is powered up, higher Sleep currents than shown in the power-down current specification will occur. Each operational comparator will consume additional current, as shown in the comparator specifications. To minimize power consumption while in Sleep mode, turn off the comparators, CM<2:0>=111, before entering Sleep. If the device wakes up from Sleep, the contents of the CMCON register are not affected.

#### 21.8 Effects of a Reset

A device Reset forces the CMCON register to its Reset state, causing the comparator module to be in the Comparator Reset mode, CM<2:0>=000. This ensures that all potential inputs are analog inputs. Device current is minimized when analog inputs are present at Reset time. The comparators will be powered down during the Reset interval.

# 21.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 21-4. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up condition may occur. A maximum source impedance of  $10\ k\Omega$  is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.

FIGURE 21-4: ANALOG INPUT MODEL




TABLE 21-1: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

Name	Bit 7	Bit 6	Bit 5			Bit 2	Bit 1	Bit 0		e on DR	Value on all other Resets	
CMCON	C2OUT	C10UT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000	0000	0000	0000
CVRCON	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000	0000	0000	0000
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR2	_	CMIF <sup>(1)</sup>	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF <sup>(1)</sup>	-0-0	0000	-0-0	0000
PIE2	_	CMIE <sup>(1)</sup>	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE <sup>(1)</sup>	-0-0	0000	-0-0	0000
IPR2	_	CMIP <sup>(1)</sup>		EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP(1)	-1-1	1111	-1-1	1111
PORTD	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	xxxx	xxxx	uuuu	uuuu
LATD	LATD7	LATD6	LATD5	LATD4	LATD3	LATD2	LATD1	LATD0	xxxx	xxxx	uuuu	uuuu
TRISD	PORTD	Data Dire	ction Re	gister					1111	1111	1111	1111
PORTE			_			RE2	RE1	RE0		-xxx		-000
LATE		_			_	LATE2	LATE1	LATE0		-xxx		-uuu
TRISE	IBF <sup>(1)</sup>	OBF <sup>(1)</sup>	IBOV <sup>(1)</sup>	PSPMODE <sup>(1)</sup>		TRISE2	TRISE1	TRISE0	0000	-111	0000	-111

**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'

Note 1: These bits are reserved on PIC18F2X8 devices; always maintain these bits clear.

# 22.0 COMPARATOR VOLTAGE REFERENCE MODULE

Note: The comparator voltage reference is only available on the PIC18F448 and PIC18F458.

This module is a 16-tap resistor ladder network that provides a selectable voltage reference. The resistor ladder is segmented to provide two ranges of CVREF values and has a power-down function to conserve power when the reference is not being used. The CVRCON register controls the operation of the reference, as shown in Register 22-1. The block diagram is shown in Figure 22-1.

The comparator and reference supply voltage can come from either VDD and VSS, or the external VREF+ and VREF+, that are multiplexed with RA3 and RA2. The comparator reference supply voltage is controlled by the CVRSS bit.

# 22.1 Configuring the Comparator Voltage Reference

The comparator voltage reference can output 16 distinct voltage levels for each range. The equations used to calculate the output of the comparator voltage reference are as follows.

#### **EQUATION 22-1:**

```
If CVRR = 1:

CVREF = (CVR<3:0>/24) x CVRSRC

where:

CVRSS = 1, CVRSRC = (VREF+) - (VREF-)

CVRSS = 0, CVRSRC = AVDD - AVSS
```

#### **EQUATION 22-2:**

```
If CVRR = 0:
CVREF = (CVRSRC x 1/4) + (CVR<3:0>/32) x CVRSRC
where:
CVRSS = 1, CVRSRC = (VREF+) - (VREF-)
CVRSS = 0, CVRSRC = AVDD - AVSS
```

The settling time of the Comparator Voltage Reference must be considered when changing the RA0/AN0/ CVREF output (see Table 27-4 in **Section 27.2 "DC Characteristics"**).

## REGISTER 22-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| CVREN | CVROE | CVRR  | CVRSS | CVR3  | CVR2  | CVR1  | CVR0  |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7 CVREN: Comparator Voltage Reference Enable bit

1 = CVREF circuit powered on

0 = CVREF circuit powered down

bit 6 CVROE: Comparator VREF Output Enable bit

1 = CVREF voltage level is also output on the RAO/ANO/CVREF pin

0 = CVREF voltage is disconnected from the RA0/AN0/CVREF pin

bit 5 CVRR: Comparator VREF Range Selection bit

1 = 0.00 CVRSRC to 0.625 CVRSRC with CVRSRC/24 step size

0 = 0.25 CVRSRC to 0.719 CVRSRC with CVRSRC/32 step size

bit 4 CVRSS: Comparator VREF Source Selection bit

1 = Comparator reference source, CVRSRC = (VREF+) - (VREF-)

0 = Comparator reference source, CVRSRC = VDD - VSS

bit 3-0 CVR<3:0>: Comparator VREF Value Selection 0 ≤ CVR3:CVR0 ≤ 15 bits


When CVRR = 1:

CVREF = (CVR3:CVR0/24) • (CVRSRC)

When CVRR = 0:

CVREF = 1/4 • (CVRSRC) + (CVR3:CVR0/32) • (CVRSRC)

#### FIGURE 22-1: VOLTAGE REFERENCE BLOCK DIAGRAM



## 22.2 Voltage Reference Accuracy/Error

The full range of voltage reference cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 22-1) keep VREF from approaching the reference source rails. The voltage reference is derived from the reference source; therefore, the VREF output changes with fluctuations in that source. The absolute accuracy of the voltage reference can be found in **Section 27.0** "Electrical Characteristics".

### 22.3 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the CVRCON register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

## 22.4 Effects of a Reset


A device Reset disables the voltage reference by clearing bit CVREN (CVRCON register). This Reset also disconnects the reference from the RA2 pin by clearing bit CVROE (CVRCON register) and selects the high-voltage range by clearing bit CVRR (CVRCON register). The CVRSS value select bits, CVRCON<3:0>, are also cleared.

## 22.5 Connection Considerations

The voltage reference module operates independently of the comparator module. The output of the reference generator may be connected to the RA0/AN0 pin if the TRISA<0> bit is set and the CVROE bit (CVRCON<6>) is set. Enabling the voltage reference output onto the RA0/AN0 pin, with an input signal present, will increase current consumption. Connecting RA0/AN0 as a digital output, with CVRSS enabled, will also increase current consumption.

The RAO/ANO pin can be used as a simple D/A output with limited drive capability. Due to the limited current drive capability, a buffer must be used on the voltage reference output for external connections to VREF. Figure 22-2 shows an example buffering technique.

## FIGURE 22-2: VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE



## TABLE 22-1: REGISTERS ASSOCIATED WITH COMPARATOR VOLTAGE REFERENCE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
CVRCON	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000 0000	0000 0000
CMCON	C2OUT	C10UT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	0000 0000
TRISA	_	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	-111 1111	-111 1111

NOTES:

#### LOW-VOLTAGE DETECT 23.0

In many applications, the ability to determine if the device voltage (VDD) is below a specified voltage level is a desirable feature. A window of operation for the application can be created, where the application software can do "housekeeping tasks" before the device voltage exits the valid operating range. This can be done using the Low-Voltage Detect module.


This module is a software programmable circuitry, where a device voltage trip point can be specified. When the voltage of the device becomes lower than the specified point, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to that interrupt source.

The Low-Voltage Detect circuitry is completely under software control. This allows the circuitry to be "turned off" by the software which minimizes the current consumption for the device.

Figure 23-1 shows a possible application voltage curve (typically for batteries). Over time, the device voltage decreases. When the device voltage equals voltage VA, the LVD logic generates an interrupt. This occurs at time Ta. The application software then has the time, until the device voltage is no longer in valid operating range, to shutdown the system. Voltage point VB is the minimum valid operating voltage specification. This occurs at time TB. The difference TB - TA is the total time for shutdown.


The block diagram for the LVD module is shown in Figure 23-2. A comparator uses an internally generated reference voltage as the set point. When the selected tap output of the device voltage crosses the set point (is lower than), the LVDIF bit is set.

Each node in the resistor divider represents a "trip point" voltage. The "trip point" voltage is the minimum supply voltage level at which the device can operate before the LVD module asserts an interrupt. When the supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal, setting the LVDIF bit. This voltage is software programmable to any one of 16 values (see Figure 23-2). The trip point is selected by programming the LVDL3:LVDL0 bits (LVDCON<3:0>).



**FIGURE 23-1:** TYPICAL LOW-VOLTAGE DETECT APPLICATION


FIGURE 23-2: LOW-VOLTAGE DETECT (LVD) BLOCK DIAGRAM



The LVD module has an additional feature that allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits LVDL3:LVDL0 are set to '1111'. In this state, the comparator input is multiplexed from the external input pin LVDIN to one input of the comparator (Figure 23-3).

The other input is connected to the internally generated voltage reference (parameter #D423 in **Section 27.2** "**DC Characteristics**"). This gives users flexibility, because it allows them to configure the Low-Voltage Detect interrupt to occur at any voltage in the valid operating range.

FIGURE 23-3: LOW-VOLTAGE DETECT (LVD) WITH EXTERNAL INPUT BLOCK DIAGRAM



#### 23.1 **Control Register**

The Low-Voltage Detect Control register controls the operation of the Low Voltage Detect circuitry.

### REGISTER 23-1: LVDCON: LOW-VOLTAGE DETECT CONTROL REGISTER

U-0	U-0	R-0	R/W-0	R/W-0	R/W-1	R/W-0	R/W-1
_	_	IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0
bit 7							bit 0

bit 0

- bit 7-6 Unimplemented: Read as '0'
- bit 5 IRVST: Internal Reference Voltage Stable Flag bit
  - 1 = Indicates that the Low-Voltage Detect logic will generate the interrupt flag at the specified voltage range
  - 0 = Indicates that the Low-Voltage Detect logic will not generate the interrupt flag at the specified voltage range and the LVD interrupt should not be enabled
- bit 4 LVDEN: Low-Voltage Detect Power Enable bit
  - 1 = Enables LVD, powers up LVD circuit
  - 0 = Disables LVD, powers down LVD circuit
- LVDL3:LVDL0: Low-Voltage Detection Limit bits bit 3-0
  - 1111 = External analog input is used (input comes from the LVDIN pin)
  - 1110 = 4.45V min.-4.83V max.
  - 1101 = 4.16V min.-4.5V max.
  - 1100 = 3.96V min.-4.2V max.
  - 1011 = 3.76V min.-4.08V max.
  - 1010 = 3.57V min.- 3.87V max.
  - 1001 = 3.47V min.- 3.75V max.
  - 1000 = 3.27V min.- 3.55V max.
  - 0111 = 2.98V min.- 3.22V max.
  - 0110 = 2.77V min.- 3.01V max.
  - 0101 = 2.67V min.-2.89V max. 0100 = 2.48V min.- 2.68V max.
  - 0011 = 2.37V min.- 2.57V max.
  - 0010 = 2.18V min.-2.36V max.
  - 0001 = 1.98V min.-2.14V max.
  - 0000 = Reserved

Note: LVDL3:LVDL0 modes, which result in a trip point below the valid operating voltage of the device, are not tested.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## 23.2 Operation

Depending on the power source for the device voltage, the voltage normally decreases relatively slowly. This means that the LVD module does not need to be constantly operating. To decrease the current requirements, the LVD circuitry only needs to be enabled for short periods where the voltage is checked. After doing the check, the LVD module may be disabled.


Each time that the LVD module is enabled, the circuitry requires some time to stabilize. After the circuitry has stabilized, all status flags may be cleared. The module will then indicate the proper state of the system.

The following steps are needed to set up the LVD module:

- Write the value to the LVDL3:LVDL0 bits (LVDCON register) which selects the desired LVD trip point.
- Ensure that LVD interrupts are disabled (the LVDIE bit is cleared or the GIE bit is cleared).
- Enable the LVD module (set the LVDEN bit in the LVDCON register).
- 4. Wait for the LVD module to stabilize (the IRVST bit to become set).
- Clear the LVD interrupt flag, which may have falsely become set, until the LVD module has stabilized (clear the LVDIF bit).
- Enable the LVD interrupt (set the LVDIE and the GIE bits).

Figure 23-4 shows typical waveforms that the LVD module may be used to detect.

FIGURE 23-4: LOW-VOLTAGE DETECT WAVEFORMS



### 23.2.1 REFERENCE VOLTAGE SET POINT

The internal reference voltage of the LVD module may be used by other internal circuitry (the Programmable Brown-out Reset). If these circuits are disabled (lower current consumption), the reference voltage circuit requires a time to become stable before a low-voltage condition can be reliably detected. This time is invariant of system clock speed. This start-up time is specified in electrical specification parameter #36. The low-voltage interrupt flag will not be enabled until a stable reference voltage is reached. Refer to the waveform in Figure 23-4.

### 23.2.2 CURRENT CONSUMPTION

When the module is enabled, the LVD comparator and voltage divider are enabled and will consume static current. The voltage divider can be tapped from multiple places in the resistor array. Total current consumption, when enabled, is specified in electrical specification parameter #D022B.

## 23.3 Operation During Sleep

When enabled, the LVD circuitry continues to operate during Sleep. If the device voltage crosses the trip point, the LVDIF bit will be set and the device will wake-up from Sleep. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

#### 23.4 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the LVD module to be turned off.

NOTES:

# 24.0 SPECIAL FEATURES OF THE CPU

There are several features intended to maximize system reliability, minimize cost through elimination of external components, provide power-saving operating modes and offer code protection. These are:

- · Oscillator Selection
- Reset
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Reset (BOR)
- Interrupts
- Watchdog Timer (WDT)
- Sleep
- Code Protection
- ID Locations
- In-Circuit Serial Programming

All PIC18FXX8 devices have a Watchdog Timer which is permanently enabled via the configuration bits or software controlled. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT) which provides a fixed delay on power-up only, designed to keep the part in Reset while the power supply stabilizes. With these two timers on-chip, most applications need no external Reset circuitry.

Sleep mode is designed to offer a very Low-Current Power-Down mode. The user can wake-up from Sleep through external Reset, Watchdog Timer wake-up or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost while the LP crystal option saves power. A set of configuration bits is used to select various options.

## 24.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1'), to select various device configurations. These bits are mapped starting at program memory location 300000h.

The user will note that address 300000h is beyond the user program memory space. In fact, it belongs to the configuration memory space (300000h-3FFFFFh) which can only be accessed using table reads and table writes.

Programming the Configuration registers is done in a manner similar to programming the Flash memory. The EECON1 register  $\overline{WR}$  bit starts a self-timed write to the Configuration register. In normal operation mode, a TBLWT instruction, with the TBLPTR pointed to the Configuration register, sets up the address and the data for the Configuration register write. Setting the  $\overline{WR}$  bit starts a long write to the Configuration register. The Configuration registers are written a byte at a time. To write or erase a configuration cell, a TBLWT instruction can write a '1' or a '0' into the cell.

TABLE 24-1: CONFIGURATION BITS AND DEVICE IDS

File	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Default/ Unprogrammed Value
300001h	CONFIG1H	_	_	OSCSEN	_	_	FOSC2	FOSC1	FOSC0	1111
300002h	CONFIG2L	_	_	_	_	BORV1	BORV0	BOREN	PWRTEN	1111
300003h	CONFIG2H	_	_	_	_	WDTPS2	WDTPS1	WDTPS0	WDTEN	1111
300006h	CONFIG4L	DEBUG	_	_	_	_	LVP	_	STVREN	11-1
300008h	CONFIG5L	_	_	_	_	CP3	CP2	CP1	CP0	1111
300009h	CONFIG5H	CPD	СРВ	_	_	_	_	_	_	11
30000Ah	CONFIG6L	_	_	_	_	WRT3	WRT2	WRT1	WRT0	1111
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	_	_	_	_	_	111
30000Ch	CONFIG7L	_	_	_	_	EBTR3	EBTR2	EBTR1	EBTR0	1111
30000Dh	CONFIG7H	-	EBTRB	_	_			_	_	-1
3FFFFEh	DEVID1	DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0	(1)
3FFFFFh	DEVID2	DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3	0000 1000

 $\textbf{Legend:} \qquad \textbf{x} = \textbf{unknown}, \textbf{u} = \textbf{unknown}, \textbf{u} = \textbf{unimplemented}, \textbf{q} = \textbf{value} \ \textbf{depends} \ \textbf{on condition}. \ \textbf{Shaded cells are unimplemented}, \textbf{read as '0'}.$ 

Note 1: See Register 24-11 for DEVID1 values.

#### REGISTER 24-1: CONFIG1H: CONFIGURATION REGISTER 1 HIGH (BYTE ADDRESS 300001h)

U-0	U-0	R/P-1	U-0	U-0	R/P-1	R/P-1	R/P-1
_	_	OSCSEN	_	-	FOSC2	FOSC1	FOSC0
bit 7							bit 0

bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 **OSCSEN**: Oscillator System Clock Switch Enable bit

1 = Oscillator system clock switch option is disabled (main oscillator is source)

0 = Oscillator system clock switch option is enabled (oscillator switching is enabled)

bit 4-3 Unimplemented: Read as '0'

bit 2-0 FOSC2:FOSC0: Oscillator Selection bits

111 = RC oscillator w/OSC2 configured as RA6

110 = HS oscillator with PLL enabled/clock frequency = (4 x Fosc)

101 = EC oscillator w/OSC2 configured as RA6

100 = EC oscillator w/OSC2 configured as divide-by-4 clock output

011 = RC oscillator

010 = HS oscillator

001 = XT oscillator

000 = LP oscillator

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

#### REGISTER 24-2: CONFIG2L: CONFIGURATION REGISTER 2 LOW (BYTE ADDRESS 300002h)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
_	_	_	_	BORV1	BORV0	BOREN	PWRTEN
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

BORV1:BORV0: Brown-out Reset Voltage bits bit 3-2

11 = VBOR set to 2.0V

10 = VBOR set to 2.7V

01 = VBOR set to 4.2V

00 = VBOR set to 4.5V

bit 1 **BOREN:** Brown-out Reset Enable bit

1 = Brown-out Reset enabled

0 = Brown-out Reset disabled

PWRTEN: Power-up Timer Enable bit bit 0

1 = PWRT disabled

0 = PWRT enabled

## Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0' u = Unchanged from programmed state -n = Value when device is unprogrammed

## REGISTER 24-3: CONFIG2H: CONFIGURATION REGISTER 2 HIGH (BYTE ADDRESS 300003h)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
_	_	_	_	WDTPS2	WDTPS1	WDTPS0	WDTEN
bit 7							hit 0

## bit 7-4 Unimplemented: Read as '0'

#### bit 3-1 WDTPS2:WDTPS0: Watchdog Timer Postscale Select bits

111 = 1:128

110 = 1:64

101 = 1:32

100 = 1.32100 = 1:16

011 = 1:8

010 = 1:4

001 = 1:2

000 = 1:1

Note:

The Watchdog Timer postscale select bits configuration used in the PIC18FXXX devices has changed from the configuration used in the PIC18CXXX devices.

#### bit 0 WDTEN: Watchdog Timer Enable bit

1 = WDT enabled

0 = WDT disabled (control is placed on the SWDTEN bit)

## Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$   $-n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

## REGISTER 24-4: CONFIG4L: CONFIGURATION REGISTER 4 LOW (BYTE ADDRESS 300006h)

R/P-1	U-0	U-0	U-0	U-0	R/P-1	U-0	R/P-1
DEBUG	_	_	_	_	LVP	_	STVREN

bit 7 bit 0

#### bit 7 **DEBUG:** Background Debugger Enable bit

- 1 = Background Debugger disabled. RB6 and RB7 configured as general purpose I/O pins.
- 0 = Background Debugger enabled. RB6 and RB7 are dedicated to In-Circuit Debug.

## bit 6-3 Unimplemented: Read as '0'

bit 2 LVP: Low-Voltage ICSP Enable bit

1 = Low-Voltage ICSP enabled

0 = Low-Voltage ICSP disabled

## bit 1 **Unimplemented:** Read as '0'

## bit 0 STVREN: Stack Full/Underflow Reset Enable bit

1 = Stack Full/Underflow will cause Reset

0 = Stack Full/Underflow will not cause Reset

## Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$   $u = Unchanged \ from \ programmed \ state$ 

#### **REGISTER 24-5:** CONFIG5L: CONFIGURATION REGISTER 5 LOW (BYTE ADDRESS 300008h)

U-0	U-0	U-0	U-0	R/C-1	R/C-1	R/C-1	R/C-1
_	_	_	_	CP3 <sup>(1)</sup>	CP2 <sup>(1)</sup>	CP1	CP0
bit 7							bit 0

bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 CP3: Code Protection bit(1)

> 1 = Block 3 (006000-007FFFh) not code-protected 0 = Block 3 (006000-007FFFh) code-protected

CP2: Code Protection bit(1) bit 2

> 1 = Block 2 (004000-005FFFh) not code-protected 0 = Block 2 (004000-005FFFh) code-protected

bit 1 CP1: Code Protection bit

> 1 = Block 1 (002000-003FFFh) not code-protected 0 = Block 1 (002000-003FFFh) code-protected

bit 0 CP0: Code Protection bit

> 1 = Block 0 (000200-001FFFh) not code-protected 0 = Block 0 (000200-001FFFh) code-protected

Note 1: Unimplemented in PIC18FX48 devices; maintain this bit set.

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

#### REGISTER 24-6: CONFIG5H: CONFIGURATION REGISTER 5 HIGH (BYTE ADDRESS 300009h)

R/C-1	R/C-1	U-0	U-0	U-0	U-0	U-0	U-0
CPD	СРВ	_	_	_	_	_	_
bit 7							bit 0

bit 7 CPD: Data EEPROM Code Protection bit

1 = Data EEPROM not code-protected

0 = Data EEPROM code-protected

bit 6 CPB: Boot Block Code Protection bit

1 = Boot Block (000000-0001FFh) not code-protected

0 = Boot Block (000000-0001FFh) code-protected

bit 5-0 Unimplemented: Read as '0'

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-7: CONFIG6L: CONFIGURATION REGISTER 6 LOW (BYTE ADDRESS 30000Ah)

=		•		•	•		
_	_	_	_	WRT3 <sup>(1)</sup>	WRT2 <sup>(1)</sup>	WRT1	WRT0
U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1

bit 7 bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 WRT3: Write Protection bit<sup>(1)</sup>

1 = Block 3 (006000-007FFFh) not write-protected 0 = Block 3 (006000-007FFFh) write-protected

bit 2 WRT2: Write Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not write-protected 0 = Block 2 (004000-005FFFh) write-protected

bit 1 WRT1: Write Protection bit

1 = Block 1 (002000-003FFFh) not write-protected 0 = Block 1 (002000-003FFFh) write-protected

bit 0 WRT0: Write Protection bit

1 = Block 0 (000200-001FFFh) not write-protected

0 = Block 0 (000200-001FFFh) write-protected

Note 1: Unimplemented in PIC18FX48 devices; maintain this bit set.

#### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$  $-n = Value \ when \ device is unprogrammed <math>u = Unchanged \ from \ programmed \ state$ 

## REGISTER 24-8: CONFIG6H: CONFIGURATION REGISTER 6 HIGH (BYTE ADDRESS 30000Bh)

R/P-1	R/P-1	R-1	U-0	U-0	U-0	U-0	U-0
WRTD	WRTB	WRTC	_	_	_	_	
bit 7							bit 0

bit 7 WRTD: Data EEPROM Write Protection bit

1 = Data EEPROM not write-protected

0 = Data EEPROM write-protected

bit 6 WRTB: Boot Block Write Protection bit

1 = Boot Block (000000-0001FFh) not write-protected

0 = Boot Block (000000-0001FFh) write-protected

bit 5 WRTC: Configuration Register Write Protection bit

1 = Configuration registers (300000-3000FFh) not write-protected

0 = Configuration registers (300000-3000FFh) write-protected

**Note:** This bit is read-only and cannot be changed in user mode.

bit 4-0 Unimplemented: Read as '0'

## Legend:

 $R = Readable \ bit \qquad P = Programmable \ bit \qquad U = Unimplemented \ bit, \ read \ as \ `0' \\ -n = Value \ when \ device \ is \ unprogrammed \qquad \qquad u = Unchanged \ from \ programmed \ state$ 

## REGISTER 24-9: CONFIG7L: CONFIGURATION REGISTER 7 LOW (BYTE ADDRESS 30000Ch)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
_	_	_	_	EBTR3 <sup>(1)</sup>	EBTR2 <sup>(1)</sup>	EBTR1	EBTR0
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 **EBTR3:** Table Read Protection bit<sup>(1)</sup>

1 =Block 3 (006000-007FFFh) not protected from table reads executed in other blocks 0 =Block 3 (006000-007FFFh) protected from table reads executed in other blocks

bit 2 **EBTR2:** Table Read Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not protected from table reads executed in other blocks 0 = Block 2 (004000-005FFFh) protected from table reads executed in other blocks

bit 1 EBTR1: Table Read Protection bit

1 =Block 1 (002000-003FFFh) not protected from table reads executed in other blocks 0 =Block 1 (002000-003FFFh) protected from table reads executed in other blocks

bit 0 **EBTR0:** Table Read Protection bit

1 = Block 0 (000200-001FFFh) not protected from table reads executed in other blocks

0 = Block 0 (000200-001FFFh) protected from table reads executed in other blocks

Note 1: Unimplemented in PIC18FX48 devices; maintain this bit set.

### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-10: CONFIG7H: CONFIGURATION REGISTER 7 HIGH (BYTE ADDRESS 30000Dh)

U-0	R/P-1	U-0	U-0	U-0	U-0	U-0	U-0
_	EBTRB	_	_	_	_	_	_
bit 7							hit 0

bit 7 **Unimplemented:** Read as '0'

bit 6 EBTRB: Boot Block Table Read Protection bit

1 = Boot Block (000000-0001FFh) not protected from table reads executed in other blocks

0 = Boot Block (000000-0001FFh) protected from table reads executed in other blocks

bit 5-0 Unimplemented: Read as '0'

#### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-11: DEVID1: DEVICE ID REGISTER 1 FOR PIC18FXX8 DEVICES (BYTE ADDRESS 3FFFFEh)

R	R	R	R	R	R	R	R
DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0
bit 7							bit 0

#### bit 7-5 **DEV2:DEV0:** Device ID bits

These bits are used with the DEV<10:3> bits in the Device ID Register 2 to identify the part number.

000 = PIC18F248

001 = PIC18F448

010 = PIC18F258

011 = PIC18F458

#### bit 4-0 REV4:REV0: Revision ID bits

These bits are used to indicate the device revision.

#### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 24-12: DEVID2: DEVICE ID REGISTER 2 FOR PIC18FXX8 DEVICES (BYTE ADDRESS 3FFFFFh)

R	R	R	R	R	R	R	R
DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3
bit 7							bit 0

#### bit 7-0 DEV10:DEV3: Device ID bits

These bits are used with the DEV<2:0> bits in the Device ID Register 1 to identify the part number.

00001000 = PIC18FXX8

## Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0' -n = Value when device is unprogrammed u = Unchanged from programmed state

## 24.2 Watchdog Timer (WDT)

The Watchdog Timer is a free running, on-chip RC oscillator which does not require any external components. This RC oscillator is separate from the RC oscillator of the OSC1/CLKI pin. That means that the WDT will run, even if the clock on the OSC1/CLKI and OSC2/CLKO/RA6 pins of the device has been stopped, for example, by execution of a SLEEP instruction.

During normal operation, a WDT time-out generates a device Reset (Watchdog Timer Reset). If the device is in Sleep mode, a WDT time-out causes the device to wake-up and continue with normal operation (Watchdog Timer wake-up). The TO bit in the RCON register will be cleared upon a WDT time-out.

The Watchdog Timer is enabled/disabled by a device configuration bit. If the WDT is enabled, software execution may not disable this function. When the WDTEN configuration bit is cleared, the SWDTEN bit enables/disables the operation of the WDT.

The WDT time-out period values may be found in **Section 27.0** "**Electrical Characteristics**" under parameter #31. Values for the WDT postscaler may be assigned using the configuration bits.

Note: The CLRWDT and SLEEP instructions clear the WDT and the postscaler if assigned to the WDT and prevent it from timing out and generating a device Reset condition.

Note: When a CLRWDT instruction is executed and the postscaler is assigned to the WDT, the postscaler count will be cleared but the postscaler assignment is not changed.

#### 24.2.1 CONTROL REGISTER

Register 24-13 shows the WDTCON register. This is a readable and writable register which contains a control bit that allows software to override the WDT enable configuration bit only when the configuration bit has disabled the WDT.

#### REGISTER 24-13: WDTCON: WATCHDOG TIMER CONTROL REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
_	_	_	_	_	_	_	SWDTEN
bit 7							bit 0

### bit 7-1 Unimplemented: Read as '0'

bit 0 **SWDTEN:** Software Controlled Watchdog Timer Enable bit

- 1 = Watchdog Timer is on
- 0 = Watchdog Timer is turned off if the WDTEN configuration bit in the Configuration register = 0

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR

### 24.2.2 WDT POSTSCALER

Note:

The WDT has a postscaler that can extend the WDT Reset period. The postscaler is selected at the time of device programming by the value written to the CONFIG2H Configuration register.

Postscaler

WDT Timer

Postscaler

8
8-to-1 MUX

WDTEN

Configuration bit

WDT

Time-out

FIGURE 24-1: WATCHDOG TIMER BLOCK DIAGRAM

TABLE 24-2: SUMMARY OF WATCHDOG TIMER REGISTERS

WDTPS2:WDTPS0 are bits in register CONFIG2H.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
CONFIG2H	_	_	_	_	WDTPS2	WDTPS1	WDTPS0	WDTEN
RCON	IPEN	_	_	RI	TO	PD	POR	BOR
WDTCON	_			_	_	_		SWDTEN

Legend: Shaded cells are not used by the Watchdog Timer.

## 24.3 Power-Down Mode (Sleep)

Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared but keeps running, the  $\overline{PD}$  bit (RCON<2>) is cleared, the  $\overline{TO}$  bit (RCON<3>) is set and the oscillator driver is turned off. The I/O ports maintain the status they had before the SLEEP instruction was executed (driving high, low or high-impedance).

For lowest current consumption in this mode, place all I/O pins at either VDD or Vss, ensure no external circuitry is drawing current from the I/O pin, power-down the A/D and disable external clocks. Pull all I/O pins that are high-impedance inputs, high or low externally, to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on-chip pull-ups on PORTB should be considered.

The MCLR pin must be at a logic high level (VIHMC).

### 24.3.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- External Reset input on MCLR pin.
- Watchdog Timer wake-up (if WDT was enabled).
- Interrupt from INT pin, RB port change or a peripheral interrupt.

The following peripheral interrupts can wake the device from Sleep:

- 1. PSP read or write.
- TMR1 interrupt. Timer1 must be operating as an asynchronous counter.
- TMR3 interrupt. Timer3 must be operating as an asynchronous counter.
- 4. CCP Capture mode interrupt.
- Special event trigger (Timer1 in Asynchronous mode using an external clock).
- 6. MSSP (Start/Stop) bit detect interrupt.
- MSSP transmit or receive in Slave mode (SPI/I<sup>2</sup>C).
- 8. USART RX or TX (Synchronous Slave mode).
- 9. A/D conversion (when A/D clock source is RC).
- 10. EEPROM write operation complete.
- 11. LVD interrupt.

Other peripherals cannot generate interrupts, since during Sleep, no on-chip clocks are present.

External MCLR Reset will cause a device Reset. All other events are considered a continuation of program execution and will cause a "wake-up". The TO and PD bits in the RCON register can be used to determine the cause of the device Reset. The PD bit, which is set on power-up, is cleared when Sleep is invoked. The TO bit is cleared if a WDT time-out occurred (and caused wake-up).

When the SLEEP instruction is being executed, the next instruction (PC + 2) is prefetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address. In cases where the execution of the instruction following SLEEP is not desirable, the user should have a NOP after the SLEEP instruction.

#### 24.3.2 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If an interrupt condition (interrupt flag bit and interrupt enable bits are set) occurs **before** the execution of a SLEEP instruction, the SLEEP instruction will complete as a NOP. Therefore, the WDT and WDT postscaler will not be cleared, the TO bit will not be set and the PD bit will not be cleared.
- If the interrupt condition occurs during or after
  the execution of a SLEEP instruction, the device
  will immediately wake-up from Sleep. The SLEEP
  instruction will be completely executed before the
  wake-up. Therefore, the WDT and WDT
  postscaler will be cleared, the TO bit will be set
  and the PD bit will be cleared.

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.

To ensure that the WDT is cleared, a <code>CLRWDT</code> instruction should be executed before a <code>SLEEP</code> instruction.





Note XT, HS or LP Oscillator mode assumed. 1:

- GIE = 1 assumed. In this case, after wake-up, the processor jumps to the interrupt routine. If GIE = 0, execution will continue in-line. Tost = 1024 Tosc (drawing not to scale). This delay will not occur for RC and EC Oscillator modes. CLKO is not available in these oscillator modes but shown here for timing reference. 2:
- 3:

# 24.4 Program Verification and Code Protection

The overall structure of the code protection on the PIC18 Flash devices differs significantly from other PICmicro devices.

The user program memory is divided into five blocks. One of these is a boot block of 512 bytes. The remainder of the memory is divided into four blocks on binary boundaries.

Each of the five blocks has three code protection bits associated with them. They are:

- Code-Protect bit (CPn)
- Write-Protect bit (WRTn)
- External Block Table Read bit (EBTRn)

Figure 24-3 shows the program memory organization for 16 and 32-Kbyte devices and the specific code protection bit associated with each block. The actual locations of the bits are summarized in Table 24-3.

FIGURE 24-3: CODE-PROTECTED PROGRAM MEMORY FOR PIC18FXX8

MEMORY S	IZE/DEVICE		
16 Kbytes (PIC18FX48)	32 Kbytes (PIC18FX58)	Address Range	Block Code Protection Controlled By:
Boot Block	Boot Block	000000h 0001FFh	CPB, WRTB, EBTRB
Block 0	Block 0	000200h 001FFFh	CP0, WRT0, EBTR0
Block 1	Block 1	002000h 003FFFh	CP1, WRT1, EBTR1
Unimplemented Read '0's	Block 2	004000h 005FFFh	CP2, WRT2, EBTR2
Unimplemented Read '0's	Block 3	006000h 007FFFh	CP3, WRT3, EBTR3
Unimplemented Read '0's	Unimplemented Read 'o's	008000h	(Unimplemented Memory Space)
		1FFFFFh	

TABLE 24-3: SUMMARY OF CODE PROTECTION REGISTERS

.,											
File	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		
300008h	CONFIG5L	_	_	_	_	CP3	CP2	CP1	CP0		
300009h	CONFIG5H	CPD	CPB	_	_	_	_	_	_		
30000Ah	CONFIG6L	_	_	_	_	WRT3	WRT2	WRT1	WRT0		
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	_	_	_	_	_		
30000Ch	CONFIG7L	_	_	_	_	EBTR3	EBTR2	EBTR1	EBTR0		
30000Dh	CONFIG7H	_	EBTRB	_	_	_	_	_	_		

Legend: Shaded cells are unimplemented.


## 24.4.1 PROGRAM MEMORY CODE PROTECTION

The user memory may be read to or written from any location using the table read and table write instructions. The device ID may be read with table reads. The Configuration registers may be read and written with the table read and table write instructions.

In user mode, the CPn bits have no direct effect. CPn bits inhibit external reads and writes. A block of user memory may be protected from table writes if the WRTn configuration bit is '0'. The EBTRn bits control table reads. For a block of user memory with the EBTRn bit set to '0', a table read instruction that executes from within that block is allowed to read. A table read instruction that executes from a location outside of that block is not allowed to read and will result in reading '0's. Figures 24-4 through 24-6 illustrate table write and table read protection.

Code protection bits may only be written to a '0' from a '1' state. It is not possible to write a '1' to a bit in the '0' state. Code protection bits are only set to '1' by a full chip erase or block erase function. The full chip erase and block erase functions can only be initiated via ICSP or an external programmer.

FIGURE 24-4: TABLE WRITE (WRTn) DISALLOWED



Note:

FIGURE 24-5: EXTERNAL BLOCK TABLE READ (EBTRn) DISALLOWED





FIGURE 24-6: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED



## 24.4.2 DATA EEPROM CODE PROTECTION

The entire data EEPROM is protected from external reads and writes by two bits: CPD and WRTD. CPD inhibits external reads and writes of data EEPROM. WRTD inhibits external writes to data EEPROM. The CPU can continue to read and write data EEPROM regardless of the protection bit settings.

## 24.4.3 CONFIGURATION REGISTER PROTECTION

The Configuration registers can be write-protected. The WRTC bit controls protection of the Configuration registers. In user mode, the WRTC bit is readable only. WRTC can only be written via ICSP or an external programmer.

### 24.5 ID Locations

Eight memory locations (200000h-200007h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are accessible during normal execution through the TBLRD and TBLWT instructions or during program/verify. The ID locations can be read when the device is code-protected.

## 24.6 In-Circuit Serial Programming

PIC18FXXX microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

## 24.7 In-Circuit Debugger

When the DEBUG bit in Configuration register, CONFIG4L, is programmed to a '0', the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB® IDE. When the microcontroller has this feature enabled, some of the resources are not available for general use. Resources used include 2 I/O pins, stack locations, program memory and data memory. For more information on the resources required, see the User's Guide for the In-Circuit Debugger you are using.

To use the In-Circuit Debugger function of the microcontroller, the design must implement In-Circuit Serial Programming connections to MCLR/VPP, VDD, GND, RB7 and RB6. This will interface to the In-Circuit Debugger module available from Microchip or one of the third party development tool companies. The Microchip In-Circuit Debugger (ICD) used with the PIC18FXXX microcontrollers is the MPLAB® ICD 2.

## 24.8 Low-Voltage ICSP Programming

The LVP bit in Configuration register, CONFIG4L, enables Low-Voltage ICSP Programming. This mode allows the microcontroller to be programmed via ICSP using a VDD source in the operating voltage range. This only means that VPP does not have to be brought to VIHH but can instead be left at the normal operating voltage. In this mode, the RB5/PGM pin is dedicated to the programming function and ceases to be a general purpose I/O pin. During programming, VDD is applied to the MCLR/VPP pin. To enter Programming mode, VDD must be applied to the RB5/PGM pin, provided the LVP bit is set. The LVP bit defaults to a ('1') from the factory.

- Note 1: The High-Voltage Programming mode is always available, regardless of the state of the LVP bit, by applying VIHH to the MCLR pin.
  - 2: While in Low-Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin.
  - 3: When using Low-Voltage ICSP Programming (LVP) and the pull-ups on PORTB are enabled, bit 5 in the TRISB register must be cleared to disable the pull-up on RB5 and ensure the proper operation of the device.

If Low-Voltage Programming mode is not used, the LVP bit can be programmed to a 'o' and RB5/PGM becomes a digital I/O pin. However, the LVP bit may only be programmed when programming is entered with VIHH on MCLR/VPP. The LVP bit can only be charged when using high voltage on MCLR.

It should be noted that once the LVP bit is programmed to '0', only the High-Voltage Programming mode is available and only High-Voltage Programming mode can be used to program the device.

When using Low-Voltage ICSP Programming, the part must be supplied 4.5V to 5.5V if a bulk erase will be executed. This includes reprogramming of the codeprotect bits from an ON state to an OFF state. For all other cases of Low-Voltage ICSP Programming, the part may be programmed at the normal operating voltage. This means unique user IDs or user code can be reprogrammed or added.

NOTES:

## 25.0 INSTRUCTION SET SUMMARY

The PIC18 instruction set adds many enhancements to the previous PICmicro instruction sets, while maintaining an easy migration from these PICmicro instruction sets.

Most instructions are a single program memory word (16 bits) but there are three instructions that require two program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- · Byte-oriented operations
- · Bit-oriented operations
- Literal operations
- · Control operations

The PIC18 instruction set summary in Table 25-2 lists **byte-oriented**, **bit-oriented**, **literal** and **control** operations. Table 25-1 shows the opcode field descriptions.

Most byte-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction.

The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All bit-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The **literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the CALL or RETURN instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for three double-word instructions. These three instructions were made double-word instructions so that all the required information is available in these 32 bits. In the second word, the 4 MSbs are '1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles, with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true, or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 25-1 shows the general formats that the instructions can have.

All examples use the format 'nnh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

The Instruction Set Summary, shown in Table 25-2, lists the instructions recognized by the Microchip MPASM $^{TM}$  Assembler.

**Section 25.2 "Instruction Set"** provides a description of each instruction.

## 25.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (R-M-W) operation. The register is read, the data is modified and the result is stored according to either the instruction or the destination designator 'd'. A read operation is performed on a register even if the instruction writes to that register.

For example, a "CLRF PORTB" instruction will read PORTB, clear all the data bits, then write the result back to PORTB. This example would have the unintended result that the condition that sets the RBIF flag would be cleared.

## TABLE 25-1: OPCODE FIELD DESCRIPTIONS

Field	Description
a	RAM access bit:
1	a = 0: RAM location in Access RAM (BSR register is ignored)
<u></u>	a = 1: RAM bank is specified by BSR register
bbb	Bit address within an 8-bit file register (0 to 7).
BSR	Bank Select Register. Used to select the current RAM bank.
d	Destination select bit:
	d = 0: store result in WREG d = 1: store result in file register f
dest	Destination either the WREG register or the specified register file location.
f	8-bit register file address (0x00 to 0xFF).
fs	12-bit register file address (0x000 to 0xFFF). This is the source address.
fd	12-bit register file address (0x000 to 0xFFF). This is the destination address.
k	Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value).
label	Label name.
mm	The mode of the TBLPTR register for the table read and table write instructions.
111111	Only used with table read and table write instructions:
*	No change to register (such as TBLPTR with table reads and writes)
*+	Post-Increment register (such as TBLPTR with table reads and writes)
*-	Post-Decrement register (such as TBLPTR with table reads and writes)
+*	Pre-Increment register (such as TBLPTR with table reads and writes)
n	The relative address (2's complement number) for relative branch instructions or the direct address for
 	Call/Branch and Return instructions.
PRODH	Product of Multiply High Byte.
PRODL	Product of Multiply Low Byte.
s	Fast Call/Return mode select bit:
	s = 0: do not update into/from shadow registers
<u> </u>	s = 1: certain registers loaded into/from shadow registers (Fast mode)
u	Unused or unchanged.
WREG	Working register (accumulator).
х	Don't care (0 or 1).
1	The assembler will generate code with $x = 0$ . It is the recommended form of use for compatibility with all Microchip software tools.
TBLPTR	21-bit Table Pointer (points to a program memory location).
TABLAT	8-bit Table Latch.
TOS	Top-of-Stack.
PC	Program Counter
PCL	Program Counter Low Byte.
PCH	Program Counter High Byte.
PCLATH	Program Counter High Byte Latch.
PCLATU	Program Counter Upper Byte Latch.
GIE	Global Interrupt Enable bit.
WDT	Watchdog Timer.
TO	Time-out bit.
PD	Power-Down bit.
C, DC, Z, OV, 1	N ALU status bits: Carry, Digit Carry, Zero, Overflow, Negative.
[ ]	Optional.
( )	Contents.
$\rightarrow$	Assigned to.
< >	Register bit field.
€	In the set of.
I E	

#### **FIGURE 25-1: GENERAL FORMAT FOR INSTRUCTIONS**

#### Byte-oriented file register operations **Example Instruction** 10 8 7 15 OPCODE f (FILE #) ADDWF MYREG, W, B d а d = 0 for result destination to be WREG register d = 1 for result destination to be file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Byte to Byte move operations (2-word) 12 11 OPCODE f (Source FILE #) MOVFF MYREG1, MYREG2 15 12 11 0 f (Destination FILE #) 1111 f = 12-bit file register address Bit-oriented file register operations 12 11 OPCODE b (BIT #) f (FILE #) а BSF MYREG, bit, B b = 3-bit position of bit in file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Literal operations 15 0 **OPCODE** k (literal) MOVLW 0x7F k = 8-bit immediate value **Control** operations CALL, GOTO and Branch operations 15 0 OPCODE n<7:0> (literal) GOTO Label 15 12 11 0 1111 n<19:8> (literal)

n = 20-bit	immediate	value
$\Pi = 20$ -bit	immediale	value

15	8 7							
	OPCODE	S	n<7:0> (literal)					
15	12 11			0				
	n<19:8> (literal)							
S = Fast bit								

11 10 OPCODE n<10:0> (literal) 15 8 7

n<7:0> (literal)

CALL MYFUNC

BRA MYFUNC

BC MYFUNC

OPCODE

TABLE 25-2: PIC18FXXX INSTRUCTION SET

Mnemonic,		Description		16-E	Bit Instr	uction V	Vord	Status	Natas
Opera	-	Description	Cycles	MSb			LSb	Affected	Notes
BYTE-ORIENTED FILE REGISTER OPERATIONS									
ADDWF	f, d, a	Add WREG and f	1	0010	01da	ffff	ffff	C, DC, Z, OV, N	1, 2
ADDWFC	f, d, a	Add WREG and Carry bit to f	1	0010	00da	ffff	ffff	C, DC, Z, OV, N	1, 2
ANDWF	f, d, a	AND WREG with f	1	0001	01da	ffff	ffff	Z, N	1,2
CLRF	f, a	Clear f	1	0110	101a	ffff	ffff	Z	2
COMF	f, d, a	Complement f	1	0001	11da	ffff	ffff	Z, N	1, 2
CPFSEQ	f, a	Compare f with WREG, skip =	1 (2 or 3)	0110	001a	ffff	ffff	None	4
CPFSGT	f, a	Compare f with WREG, skip >	1 (2 or 3)	0110	010a	ffff	ffff	None	4
CPFSLT	f, a	Compare f with WREG, skip <	1 (2 or 3)	0110	000a	ffff	ffff	None	1, 2
DECF	f, d, a	Decrement f	1	0000	01da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
DECFSZ	f, d, a	Decrement f, Skip if 0	1 (2 or 3)	0010	11da	ffff	ffff	None	1, 2, 3, 4
DCFSNZ	f, d, a	Decrement f, Skip if Not 0	1 (2 or 3)	0100	11da	ffff	ffff	None	1, 2
INCF	f, d, a	Increment f	1	0010	10da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
INCFSZ	f, d, a	Increment f, Skip if 0	1 (2 or 3)	0011	11da	ffff	ffff	None	4
INFSNZ	f, d, a	Increment f, Skip if Not 0	1 (2 or 3)	0100	10da	ffff	ffff	None	1, 2
IORWF	f, d, a	Inclusive OR WREG with f	1 `	0001	00da	ffff	ffff	Z, N	1, 2
MOVF	f, d, a	Move f	1	0101	00da	ffff	ffff	Z, N	1
MOVFF	$f_s$ , $f_d$	Move f <sub>s</sub> (source) to 1st word	2	1100	ffff	ffff	ffff	None	
	o	f <sub>d</sub> (destination) 2nd word		1111	ffff	ffff	ffff		
MOVWF	f, a	Move WREG to f	1	0110	111a	ffff	ffff	None	
MULWF	f, a	Multiply WREG with f	1	0000	001a	ffff	ffff	None	
NEGF	f, a	Negate f	1	0110	110a	ffff	ffff	C, DC, Z, OV, N	1, 2
RLCF	f, d, a	Rotate Left f through Carry	1	0011	01da	ffff	ffff	C, Z, N	
RLNCF		Rotate Left f (No Carry)	1	0100	01da	ffff	ffff	Z, N	1, 2
RRCF	f, d, a	Rotate Right f through Carry	1	0011	00da	ffff	ffff	C, Z, N	,
RRNCF	f, d, a	Rotate Right f (No Carry)	1	0100	00da	ffff	ffff	Z, N	
SETF	f, a	Set f	1	0110	100a	ffff	ffff	None	
SUBFWB	f, d, a	Subtract f from WREG with	1	0101	01da	ffff	ffff	C, DC, Z, OV, N	1, 2
	, ,	borrow							,
SUBWF	f, d, a	Subtract WREG from f	1	0101	11da	ffff	ffff	C, DC, Z, OV, N	
SUBWFB	f, d, a	Subtract WREG from f with	1	0101	10da	ffff	ffff	C, DC, Z, OV, N	1, 2
	, ,	borrow						, , , ,	,
SWAPF	f, d, a	Swap nibbles in f	1	0011	10da	ffff	ffff	None	4
TSTFSZ	f, a	Test f, skip if 0	1 (2 or 3)	0110	011a	ffff	ffff	None	1, 2
XORWF	f, d, a	Exclusive OR WREG with f	1	0001	10da	ffff	ffff	Z, N	,
	BIT-ORIENTED FILE REGISTER OPERATIONS								
BCF		Bit Clear f	1	1001	bbba	ffff	ffff	None	1, 2
BSF		Bit Set f	i		bbba	ffff	ffff	None	1, 2
BTFSC		Bit Test f, Skip if Clear	1 (2 or 3)	1011		ffff	ffff	None	3, 4
BTFSS		Bit Test f, Skip if Set	1 (2 or 3)			ffff	ffff	None	3, 4
BTG		Bit Toggle f	1		bbba	ffff	ffff	None	1, 2
סום	ı, u, a	Pit 1099ie i	<b>'</b>	0111	DDDa	TTTT	TTTT	1110116	٠, ح

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.
  - **3:** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 25-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Mnemonic,		Description	Cycles	16-Bit Instruction Word				Status	Natas
Opera	nds	Description	Cycles	MSb			LSb	Affected	Notes
CONTROL	. OPER	ATIONS							
ВС	n	Branch if Carry	1 (2)	1110	0010	nnnn	nnnn	None	
BN	n	Branch if Negative	1 (2)	1110	0110	nnnn	nnnn	None	
BNC	n	Branch if Not Carry	1 (2)	1110	0011	nnnn	nnnn	None	
BNN	n	Branch if Not Negative	1 (2)	1110	0111	nnnn	nnnn	None	
BNOV	n	Branch if Not Overflow	1 (2)	1110	0101	nnnn	nnnn	None	
BNZ	n	Branch if Not Zero	2	1110	0001	nnnn	nnnn	None	
BOV	n	Branch if Overflow	1 (2)	1110	0100	nnnn	nnnn	None	
BRA	n	Branch Unconditionally	1 (2)	1101	0nnn	nnnn	nnnn	None	
BZ	n	Branch if Zero	1 (2)	1110	0000	nnnn	nnnn	None	
CALL	n, s	Call subroutine1st word	2	1110	110s	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
CLRWDT	_	Clear Watchdog Timer	1	0000	0000	0000	0100	TO, PD	
DAW	_	Decimal Adjust WREG	1	0000	0000	0000	0111	С	
GOTO	n	Go to address 1st word	2	1110	1111	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
NOP	_	No Operation	1	0000	0000	0000	0000	None	
NOP	_	No Operation	1	1111	XXXX	XXXX	XXXX	None	4
POP	_	Pop top of return stack (TOS)	1	0000	0000	0000		None	
PUSH	_	Push top of return stack (TOS)	1	0000	0000	0000	0101	None	
RCALL	n	Relative Call	2	1101	1nnn	nnnn	nnnn	None	
RESET		Software device Reset	1	0000	0000	1111	1111		
RETFIE	S	Return from interrupt enable	2	0000	0000	0001	000s	GIE/GIEH,	
DETLIM	l.	Deturn with literal in MDEC		0000	1100	1-1-1-1	1-1-1-1	PEIE/GIEL	
RETLUDA	k	Return with literal in WREG	2	0000	1100	kkkk		None	
RETURN	S	Return from Subroutine	2	0000	0000	0001		None	
SLEEP		Go into Standby mode	I	0000	0000	0000	0011	TO, PD	

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.
  - **3:** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - 4: Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - **5:** If the table write starts the write cycle to internal memory, the write will continue until terminated.

TABLE 25-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Mnemonic, Operands		Description	Cycles	16-Bit Instruction Word				Status	Notes
				MSb			LSb	Affected	Notes
LITERAL	OPERAT	TIONS							
ADDLW	k	Add literal and WREG	1	0000	1111	kkkk	kkkk	C, DC, Z, OV, N	
ANDLW	k	AND literal with WREG	1	0000	1011	kkkk	kkkk	Z, N	
IORLW	k	Inclusive OR literal with WREG	1	0000	1001	kkkk	kkkk	Z, N	
LFSR	f, k	Move literal (12-bit) 2nd word	2	1110	1110	OOff	kkkk	None	
		to FSRx 1st word		1111	0000	kkkk	kkkk		
MOVLB	k	Move literal to BSR<3:0>	1	0000	0001	0000	kkkk	None	
MOVLW	k	Move literal to WREG	1	0000	1110	kkkk	kkkk	None	
MULLW	k	Multiply literal with WREG	1	0000	1101	kkkk	kkkk	None	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
SUBLW	k	Subtract WREG from literal	1	0000	1000	kkkk	kkkk	C, DC, Z, OV, N	
XORLW	k	Exclusive OR literal with WREG	1	0000	1010	kkkk	kkkk	Z, N	
DATA MEI	MORY ←	PROGRAM MEMORY OPERA	TIONS						
TBLRD*		Table Read	2	0000	0000	0000	1000	None	
TBLRD*+		Table Read with post-increment		0000	0000	0000	1001	None	
TBLRD*-		Table Read with post-decrement		0000	0000	0000	1010	None	
TBLRD+*		Table Read with pre-increment		0000	0000	0000	1011	None	
TBLWT*		Table Write	2 (5)	0000	0000	0000	1100	None	
TBLWT*+		Table Write with post-increment		0000	0000	0000	1101	None	
TBLWT*-		Table Write with post-decrement		0000	0000	0000	1110	None	
TBLWT+*		Table Write with pre-increment		0000	0000	0000	1111	None	

- Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.
  - 2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.
  - **3:** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
  - **4:** Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
  - 5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

#### 25.2 Instruction Set

ADDLW	ADD Literal to W	
Syntax:	[label] ADDLW	k
Operands:	$0 \le k \le 255$	
Operation:	$(W) + k \rightarrow W$	
Status Affected:	N, OV, C, DC, Z	

Encoding: 0000 1111 kkkk kkkk

Description: The contents of W are added to the 8-bit

literal 'k' and the result is placed in W.

Words: 1
Cycles: 1
Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to W
	literal 'k'	Data	

Example: ADDLW 0x15

Before Instruction W = 0x10After Instruction W = 0x25

ADD	WF	ADD W to f			
Synta	ax:	[ label ] ADDWF f [,d [,a]]			
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			
Oper	ation:	$(W)+(f)\rightarrow$	dest		
Statu	s Affected:	N, OV, C, DC, Z			
Enco	ding:	0010	01da	ffff	ffff
Desc	Description:  Add W to register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR is used.			ı', the er 'f' ss Bank	
Word	ls:	1			
Cycle	es:	1			
QC	ycle Activity:				
	Q1	Q2	Q	3	Q4
	Decode	Read register 'f'	Proce Dat		Write to estination

Example: ADDWF REG, W

Before Instruction

W = 0x17 REG = 0xC2

After Instruction

W = 0xD9 REG = 0xC2

ADDWFC	ADD W and Carry bit to f			
Syntax:	[ label ] ADI	DWFC	f [,d [,a]]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			
Operation:	$(W) + (f) + (C) \to dest$			
Status Affected:	N, OV, C, D	C, Z		
Encoding:	0010	00da	ffff	ffff
Description:	Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'. If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR will not be overridden.			
Words:	1			

words.		
Cycles:	1	
0.00		

#### Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example:	ADDWFC	REG,	W
----------	--------	------	---

Before Instruction

 $\begin{array}{lll} \text{Carry bit} &=& 1 \\ \text{REG} &=& 0x02 \\ \text{W} &=& 0x4D \end{array}$ 

After Instruction

 $\begin{array}{lll} \text{Carry bit} & = & 0 \\ \text{REG} & = & 0x02 \\ \text{W} & = & 0x50 \end{array}$ 

ANDLW AND Literal with W

Syntax: [label] ANDLW k

Operands:  $0 \le k \le 255$ 

Operation: (W) .AND.  $k \rightarrow W$ 

Status Affected: N, Z

Encoding: 0000 1011 kkkk kkkk

Description: The contents of W are ANDed with the 8-bit literal 'k'. The result is placed in W.

Words: 1

Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to W
	'k'	Data	

Example: ANDLW 0x5F

Before Instruction

W = 0xA3

After Instruction

W = 0x03

ANDWF	AND W with f			
Syntax:	[ label ] ANDWF f [,d [,a]]			
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			
Operation:	(W) .AND. (f) $\rightarrow$ dest			
Status Affected:	N, Z			
Encoding:	0001 01da ffff ffff			
Description:	The contents of W are ANDed with register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR will not be overridden (default).			
Words:	1			
Cycles:	1			

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example: ANDWF REG, W

Before Instruction

Q Cycle Activity:

W REG 0x17 0xC2

After Instruction

0x02 0xC2 W REG

ВС	Branch if Carry		
Syntax:	[ label ] BC n		
Operands:	-128 ≤ n ≤ 127		
Operation:	if Carry bit is '1' $(PC) + 2 + 2n \rightarrow PC$		
Status Affected:	None		
Encoding:	1110 0010 nnnn nnnn		
Description:	If the Carry bit is '1', then the program will branch.		

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: Cycles: 1(2)

Q Cycle Activity: If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	ʻn'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE ВC JUMP

Before Instruction

PC address (HERE)

After Instruction

If Carry PC

address (JUMP)

If Carry PC =

address (HERE + 2)

BCF		Bit Clear f				
Synta	ax:	[ label ] BCF f,b[,a]				
Oper	ands:	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$				
Oper	ation:	$0 \to f {<} b {>}$				
Statu	s Affected:	None				
Enco	ding:	1001	bbba	fff	f ffff	
Desc	ription:	the Access	Bank wi BSR value e selecte	ll be se e. If 'a'	ed. If 'a' is '0', elected, over- = 1, then the er the BSR	
Word	ls:	1	1			
Cycle	es:	1				
Q Cycle Activity:						
	Q1	Q2	Q	3	Q4	
	Decode	Read	Proce		Write	
		register 'f'	Dat	a	register 'f'	

FLAG\_REG, 7 Example: BCF

> Before Instruction  $FLAG_REG = 0xC7$ After Instruction  $FLAG_REG = 0x47$

BN	Branch if	Negative	)	
Syntax:	[label] B	N n		
Operands:	-128 ≤ n ≤	127		
Operation:	if Negative bit is '1' $(PC) + 2 + 2n \rightarrow PC$			
Status Affected:	None			
Encoding:	1110	0110	nnnn	nnnn
Description:	If the Negative bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.			
Words:	1			
Cycles:	1(2)			
Q Cycle Activity:				

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNJump

Before Instruction

PC address (HERE)

After Instruction

If Negative PC

1; address (Jump)

If Negative PC 0;

address (HERE + 2)

BNC	Branch if Not Carry				
Syntax:	[ label ] BNC n				
Operands:	$-128 \le n \le 127$				
Operation:	if Carry bit is '0' $(PC) + 2 + 2n \rightarrow PC$				
Status Affected:	None				
Encoding:	1110 0011 nnnn nnnn				
Description:	If the Carry bit is '0', then the program will branch.				

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	ʻn'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	ʻn'	Data	operation

address (HERE + 2)

Example:	HERE	BNC	Jump		
Before Instruction PC After Instruction	=	address	(HERE)		
If Carry PC If Carry PC	= = = =	0; address 1; address		+	

BNN	Branch if Not Negative
Syntax:	[label] BNN n
Operands:	$-128 \le n \le 127$
Operation:	if Negative bit is '0' (PC) + 2 + 2n $\rightarrow$ PC
Status Affected:	None

Encoding: 1110 0111

nnnn nnnn Description:

If the Negative bit is '0', then the program will branch.

> The 2's complement number '2n' is added to the PC. Since the PC will have

incremented to fetch the next instruction, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example:	HERE	BNN	Jump

Before Instruction

PC address (HERE)

After Instruction

If Negative 0;

PC = address (Jump)

If Negative = 1;

PC address (HERE + 2)

BNOV B	ranch if No	ot Overflow

Syntax: [label] BNOV n Operands:  $-128 \le n \le 127$ Operation: if Overflow bit is 'o'

(PC) + 2 + 2n  $\rightarrow$  PC

Status Affected: None

Encoding: 1110 0101 nnnn nnnn

Description: If the Overflow bit is '0', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruc-

tion, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	'n'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BNOV Jump

Before Instruction

PC = address (HERE)

After Instruction

If Overflow = 0:

PC = address (Jump)

If Overflow = 1;

PC = address (HERE + 2)

BNZ Branch if Not Zero

Syntax: [label] BNZ n Operands:  $-128 \le n \le 127$ 

Operation: if Zero bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

 Encoding:
 1110
 0001
 nnnn
 nnnn

If the Zero bit is '0', then the program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruc-

tion, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1

Cycles: 1(2)

Q Cycle Activity: If Jump:

Description:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	ʻn'	Data	
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	ʻn'	Data	operation

Example: HERE BNZ Jump

Before Instruction

PC = address (HERE)

After Instruction

If Zero = 0;

PC = address (Jump)

If Zero = 1;

PC = address (HERE + 2)

BRA	Unconditional Branch			
Syntax:	[ label ] BRA n			
Operands:	$-1024 \le n \le 1023$			
Operation:	$(PC) + 2 + 2n \rightarrow PC$			
Status Affected:	None			
Encoding:	1101	0nnn	nnnn	nnnn
Description:	Add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be			

two-cycle instruction. Words: 1

Q Cycle Activity:

Cycles:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to PC
	ʻn'	Data	
No	No	No	No
operation	operation	operation	operation

PC + 2 + 2n. This instruction is a

Example: HERE BRA Jump

2

Before Instruction

PC = address (HERE)

After Instruction

PC = address (Jump)

BSF	Bit Set f		
Syntax:	[ label ] BSF f,b[,a]		
Operands:	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$		
Operation:	$1 \rightarrow f < b >$		
Status Affected:	None		
Encoding:	1000 bbba ffff ffff		
Description:	Bit 'b' in register 'f' is set. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value.		

Words: 1
Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: BSF FLAG\_REG, 7

Before Instruction

 $FLAG_REG = 0x0A$ 

After Instruction

FLAG\_REG = 0x8A

**BTFSC** Bit Test File, Skip if Clear

Syntax: [ label ] BTFSC f,b[,a]

Operands:  $0 \le f \le 255$  $0 \le b \le 7$  $a \in [0,1]$ 

Operation: skip if (f < b >) = 0

Status Affected: None

Encoding: ffff ffff 1011 bbba

Description: If bit 'b' in register 'f' is '0', then the next

instruction is skipped.

If bit 'b' is '0', then the next instruction fetched during the current instruction execution is discarded and a NOP is executed instead, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).

1 Words:

Cycles: 1(2)

> Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4	
No	No	No	No	
operation	operation	operation	operation	
No	No	No	No	_
operation	operation	operation	operation	

Example: HERE BTFSC FLAG, 1

FALSE : TRUE

Before Instruction

PC address (HERE)

After Instruction

address (TRUE)

address (FALSE)

**BTFSS** Bit Test File, Skip if Set

Syntax: [ label ] BTFSS f,b[,a]

Operands:  $0 \le f \le 255$  $0 \le b \le 7$ 

 $a \in [0,1]$ 

None

Operation: skip if (f < b >) = 1Status Affected:

Encoding: ffff 1010 bbba

Description: If bit 'b' in register 'f' is '1', then the next

instruction is skipped.

If bit 'b' is '1', then the next instruction fetched during the current instruction execution is discarded and a NOP is executed instead, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).

ffff

1 Words:

Cycles: 1(2)

> Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation
No	No	No	No
operation	operation	operation	operation

Example: HERE FLAG, 1 BTFSS

> FALSE TRUE

Before Instruction

PC address (HERE)

After Instruction

If FLAG<1>

address (FALSE)

address (TRUE)

BTG	Bit Toggle	e f		
Syntax:	[ label ] BTG f,b[,a]			
Operands:	$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$			
Operation:	$(\overline{f}) \to f$			
Status Affected:	None			
Encoding:	0111	bbba	ffff	ffff
Description:	Bit 'b' in data memory location 'f' is inverted. If 'a' is '0', the Access Bank will			

be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).

Words: Cycles: 1 Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: BTG PORTC, 4

Before Instruction:

PORTC = 0111 0101 **[0x75]** 

After Instruction:

PORTC = 0110 0101 **[0x65]** 

BOV	Branch if Overflow			
Syntax:	[label] BC	OV n		
Operands:	-128 ≤ n ≤ 127			
Operation:	if Overflow bit is '1' $(PC) + 2 + 2n \rightarrow PC$			
Status Affected:	None			
Encoding:	1110	0100	nnnn	nnnn
Description:	If the Overflow bit is '1', then the program will branch.			

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: Cycles: 1(2)

Q Cycle Activity: If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to
	ʻn'	Data	PC
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	ʻn'	Data	operation

Example: HERE BOV JUMP

Before Instruction

PC address (HERE)

After Instruction

If Overflow

address (JUMP)

If Overflow PC

address (HERE + 2)

BZ Branch if Zero

Syntax: [label] BZ n Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0000 nnnn nnnn

Description: If the Zero bit is '1', then the program

will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruc-

tion, the new address will be

PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1
Cycles: 1(2)

Q Cycle Activity:

If Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	Write to
	'n'	Data	PC
No	No	No	No
operation	operation	operation	operation

If No Jump:

Q1	Q2	Q3	Q4
Decode	Read literal	Process	No
	'n'	Data	operation

Example: HERE BZ Jump

Before Instruction

PC = address (HERE)

After Instruction

If Zero = 1;

PC = address (Jump)

If Zero = 0;

PC = address (HERE + 2)

CALL Subroutine Call

Syntax: [ label ] CALL k [,s]

Operands:  $0 \le k \le 1048575$ 

 $s \in [0,1]$ 

Operation:  $(PC) + 4 \rightarrow TOS$ ,

 $k \rightarrow PC < 20:1>,$  if s = 1

 $\begin{array}{l} \text{(W)} \rightarrow \text{WS,} \\ \text{(Status)} \rightarrow \text{STATUSS,} \end{array}$ 

 $(BSR) \rightarrow BSRS$ 

Status Affected: None

Encoding: 1st word (k<7:0>) 2nd word(k<19:8>) 1110 110s k<sub>7</sub>kkk kkkk<sub>0</sub>
1111 k<sub>19</sub>kkk kkkk kkkk kkkk<sub>8</sub>

Description: Subroutine call of entire 2-Mbyte

memory range. First, return address (PC + 4) is pushed onto the return stack. If 's' = 1, the W, Status and BSR registers are also pushed into their respective shadow registers, WS, STATUSS and BSRS. If 's' = 0, no update occurs (default). Then, the 20-bit value 'k' is loaded into PC<20:1>. CALL is a two-cycle instruction.

Words: 2 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal	Push PC to	Read literal
	'k'<7:0>,	stack	'k'<19:8>,
			Write to PC
No	No	No	No
operation	operation	operation	operation

Example: HERE CALL THERE, FAST

Before Instruction

PC = address (HERE)

After Instruction

PC = address (THERE) TOS = address (HERE + 4)

WS = W BSRS = BSR STATUSS= Status

CLR	F	Clear f						
Synta	ax:	[ label ] CL	RF f[,a]	]				
Oper	ands:	$0 \le f \le 255$ $a \in [0,1]$						
Oper	ation:	$\begin{array}{c} 000h \rightarrow f \\ 1 \rightarrow Z \end{array}$						
Statu	s Affected:	Z						
Enco	ding:	0110	101a	fff	f ffff			
Desc	ription:	register. If 'be selected If 'a' = 1, the	Clears the contents of the specified register. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).					
Word	ls:	1						
Cycle	es:	1						
QC	ycle Activity:							
	Q1	Q2	Q3		Q4			
	Decode	Read	Proce		Write			

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: CLRF FLAG\_REG

Before Instruction

FLAG\_REG 0x5A

After Instruction

 $\mathsf{FLAG}\_\mathsf{REG}$ 0x00 =

CLR	WDT	Clear Wate	hdog Ti	mer			
Synta	ax:	[label] Cl	RWDT				
Oper	ands:	None	None				
Oper	ation:						
Statu	s Affected:	$\overline{TO}, \overline{PD}$					
Enco	Encoding: 0000 0000 0000 0100						
Desc	eription:	CLRWDT instruction resets the Watchdog Timer. It also resets the postscaler of the WDT. Status bits TO and PD are set.					
Word	ls:	1					
Cycle	es:	1					
QC	ycle Activity:						
	Q1	Q2	Q	3	Q4		
	Decode	No	Proce	ess	No		
		operation	Dat	a c	peration		

Example: CLRWDT Before Instruction WDT Counter ? After Instruction WDT Counter 0x00 WDT Postscaler TO PD = 0 1 1

COM	COMF Complement f							
Synta	ax:	[label] C	OMF f	[,d [,a]]				
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$						
Oper	ation:	$(\overline{f}) \rightarrow des$	st					
Statu	s Affected:	N, Z						
Enco	ding:	0001	11da	ffff	ffff			
Description:  The contents of register 'f' are complemented. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). Is '0', the Access Bank will be select overriding the BSR value. If 'a' = 1, the bank will be selected as per the BSR value (default).					e result is sult is ault). If 'a' selected, ' = 1, then			
Word	ls:	1						
Cycle	es:	1						
QC	ycle Activity:							
	Q1	Q2	Q3		Q4			
	Decode	Read	Proces		Vrite to			

Decode	Read	Process	Write to
	register 'f'	Data	destination

REG, W

Example: Before Instruction

REG 0x13

COMF

After Instruction

REG 0x13 W 0xEC

CPFSEQ	Compare	f with W,	Skip if f =	· W
Syntax:	[label] C	PFSEQ	f [,a]	
Operands:	$0 \le f \le 255$ $a \in [0,1]$	5		
Operation:	(f) - (W), skip if $(f) =$ (unsigned	` '	on)	
Status Affected:	None			
Encoding:	0110	001a	ffff	ffff
Description:	Compares location 'f' performing If 'f' = W, ti discarded	to the cor g an unsig hen the fe	ntents of V ined subtra etched inst	V by action. ruction is

Words:

Cycles: 1(2)

Note: 3 cycles if skip and followed

instead, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).

by a 2-word instruction.

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4	
No	No No		No	
operation	operation	operation	operation	
No	No	No	No	
operation	operation	operation	operation	

Example: HERE CPFSEQ REG NEQUAL

EQUAL

Before Instruction

PC Address W HERE ? ? REG

After Instruction

If REG PC If REG PC Address (EQUAL) W;

Address (NEQUAL)

CPFSGT	Compare f	with W, Skip	if f > W	CPF	SLT	Compare f	with W, Skip	if f < W
Syntax:	[label] CF	PFSGT f[,a]		Synta	ax:	[ label ] Cl	PFSLT f[,a]	
Operands:	$0 \le f \le 255$ $a \in [0,1]$			Oper	ands:	$0 \le f \le 255$ $a \in [0,1]$		
Operation:	(f) - (W), skip if $(f) > ($ (unsigned of	` '		Oper	ation:	(f) - (W), skip if $(f) < (unsigned of)$	(W) comparison)	
Status Affected:	None			Statu	s Affected:	None		
Encoding:	0110	010a ff:	ff ffff	Enco	ding:	0110	000a ffi	ff ffff
Description:	location 'f' to performing If the content contents of instruction in executed in two-cycle in Access Bar overriding the	o the contents an unsigned s an unsigned s ants of 'f' are gr WREG, then is discarded as stead, making astruction. If 'a sk will be selected	subtraction. The ater than the the fetched and a NOP is this a 'is '0', the cited,  If 'a' = 1, then	Desc	ription:	location 'f' t performing If the conte contents of instruction i executed in two-cycle ir Access Bar	the contents of the contents an unsigned s ints of 'f' are le. W, then the fe is discarded ar instead, making instruction. If 'a ink will be selec Il not be overri	of W by ubtraction. ss than the stched nd a NOP is this a ' is '0', the ted. If 'a' is '1'
Words:	1	,		Cycle	es:	1(2)		
Cycles:		ycles if skip a a 2-word instr		QC	ycle Activity:	by	cycles if skip a a 2-word instr	uction.
Q Cycle Activity:	·				Q1	Q2	Q3	Q4
Q1	Q2	Q3	Q4		Decode	Read register 'f'	Process Data	No operation
Decode	Read	Process	No	If sk	ip:	1		
If all a	register 'f'	Data	operation		Q1	Q2	Q3	Q4
If skip: Q1	Q2	Q3	Q4		No 	No	No	No 
No	No No	No No	No No	16 - 1-	operation	operation	operation	operation
operation	operation	operation	operation	II SK	ip and followe Q1	d by 2-word ir Q2	Q3	Q4
If skip and followe	d by 2-word in	struction:			No No	No	No No	No
Q1	Q2	Q3	Q4		operation	operation	operation	operation
No	No	No	No		No	No	No	No
operation	operation	operation	operation		operation	operation	operation	operation
No operation	No operation	No operation	No operation	<u>Exan</u>	nple:		CPFSLT REG	
Example:	HERE NGREATER GREATER	CPFSGT R:	EG		Before Instruc	LESS	:	
Before Instruc		٠			PC W	= Ac = ?	ddress (HERE	)

After Instruction

If REG PC If REG PC

W;

= ≥ =

Address (LESS) W;

Address (NLESS)

Before Instruction PC W

After Instruction

If REG PC If REG PC

> = ≤ =

W;

Address (HERE) ?

W; Address (GREATER)

Address (NGREATER)

# WWW PIC18FXX8

DAW		Decimal Adjust W Register					
Synta	ax:	[ /	abel] DA	W			
Oper	ands:	N	one				
Operation:			If [W<3:0> > 9] or [DC = 1] then $ (W<3:0>) + 6 \to W<3:0>; $ else $ (W<3:0>) \to W<3:0> $				
		(V el:	[W<7:4> > V<7:4>) + se V<7:4>)	6 → W<	7:4>;	then	
Statu	s Affected:	С	T				
Enco	ding:		0000	0000	000	00	0111
Desc	Description:		AW adjusts sulting fro ariables (e ad produce sult.	m the ea ach in pa	rlier a acked	dditi BCI	on of two O format)
Word	s:	1					
Cycle	es:	1					
Q C	ycle Activity:						
	Q1		Q2	Q3			Q4
	Decode		Read jister W	Proce Data		١	Write W
Exam	nple 1:	D.	AW				
	Before Instruc	ction					
	W C DC	= = =	0xA5 0 0				
<u>C</u>		on = = =	0x05 1 0				
Before Instructi							
W C DC			0xCE 0 0				
	After Instructi		004				
	W C DC	= = =	0x34 1 0				

DEC	F	Decrement	f				
Synta	ax:	[ label ] DE	ECF f[,	d [,a]]			
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	d ∈ [0,1]				
Oper	ation:	$(f) - 1 \rightarrow de$	est				
Statu	s Affected:	C, DC, N, C	V, Z				
Enco	ding:	0000	01da	fff	f	ffff	
Desc	ription:	Decrement register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default)					
Word	ls:	1					
Cycle	es:	1					
Q C	ycle Activity:						
	Q1	Q2	Q	3		Q4	
	Decode	Read register 'f'	Proce Dat			rite to stination	

	Q1	Q2	Q3	Q4
	Decode	Read	Process	Write to
		register 'f'	Data	destination
Exan	nple:	DECF	CNT,	

 $\begin{array}{cccc} \text{Before Instruction} & & & \\ \text{CNT} & = & 0 \text{xo1} \\ \text{Z} & = & 0 \\ \text{After Instruction} & & \\ \text{CNT} & = & 0 \text{xo0} \\ \text{Z} & = & 1 \\ \end{array}$ 

DECFSZ	Decrement	t f, Skip if 0		DCF	SNZ	Decremen	t f, Skip if no	t 0
Syntax:	[ label ] DI	ECFSZ f[,d	[,a]]	Synta	ax:	[label] D	CFSNZ f[,d	[,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$		
Operation:	(f) $-1 \rightarrow de$ skip if resul	•		Oper	ation:	(f) $-1 \rightarrow de$ skip if resu	-	
Status Affected:	None			Statu	s Affected:	None		
Encoding:	0010	11da ff	ff ffff	Enco	ding:	0100	11da ff	ff ffff
Description:	decremented placed in William placed back of the result which is alroad a NOP in it a two-cychaccess Barroverriding to then the ba		the result is he result is ' (default). It instruction is discarded istead, making If 'a' is '0', the octed, e. If 'a' = 1,	Desc	ription:	decrements placed in V placed bac If the result instruction discarded a instead, mainstruction. will be selevalue. If 'a' selected as	ats of register 'ed. If 'd' is '0', V. If 'd' is '1', tl k in register 'f' is not '0', the which is alrea and a NOP is e aking it a two- If 'a' is '0', the cted, overridir = 1, then the s per the BSR	the result is ne result is (default). next dy fetched is executed cycle a Access Banlong the BSR bank will be
Words:	1					(default).		
Cycles:  Q Cycle Activity:		ycles if skip a a 2-word instr		Word Cycle			cycles if skip a a 2-word instr	
Q1	Q2	Q3	Q4	QC	ycle Activity:			
Decode	Read register 'f'	Process Data	Write to destination		Q1 Decode	Q2 Read	Q3 Process	Q4 Write to
If skip:	3					register 'f'	Data	destination
Q1	Q2	Q3	Q4	If sk	ip:			
No	No	No	No		Q1	Q2	Q3	Q4
operation	operation	operation	operation		No	No	No	No
If skip and followe	ed by 2-word in	struction:			operation	operation	operation	operation
Q1	Q2	Q3	Q4	If sk	ip and followe	ed by 2-word in	struction:	
No	No	No	No		Q1	Q2	Q3	Q4
operation	operation	operation	operation		No	No	No	No
No	No	No	No		operation	operation	operation	operation
operation	operation	operation	operation		No operation	No operation	No operation	No operation
Example:	HERE CONTINUE	DECFSZ GOTO	CNT LOOP	<u>Exan</u>		HERE ZERO	DCFSNZ TEM:	
Before Instru		s (HERE)			Before Instru		:	

?

= ≠ = TEMP – 1,

0; Address (ZERO) 0;

Address (NZERO)

TEMP

After Instruction TEMP If TEMP

PC If TEMP

After Instruction

CNT If CNT

PC =
If CNT ≠
PC =

CNT - 1

Address (CONTINUE)
0;

Address (HERE + 2)

GOTO	Unconditional Branch			
Syntax:	[ label ] GOTO k			
Operands:	$0 \leq k \leq 1048575$			
Operation:	$k \rightarrow PC < 20:1 >$			
Status Affected:	None			
Encoding: 1st word (k<7:0>) 2nd word(k<19:8>)	1110 1111 k <sub>7</sub> kkk kkkk <sub>0</sub> 1111 k <sub>19</sub> kkk kkkk kkkk <sub>8</sub>			
Description:	GOTO allows an unconditional branch anywhere within entire 2-Mbyte memory range. The 20-bit value 'k' is loaded into			

PC<20:1>. GOTO is always a two-cycle instruction.

Words: 2

Cycles: 2

Q Cycle Activity:

_	Q1	Q2	Q3	Q4
	Decode	Read literal	No	Read literal
		'k'<7:0>	operation	'k'<19:8>,
				Write to PC
	No	No	No	No
	operation	operation	operation	operation

Example: GOTO THERE

After Instruction

PC = Address (THERE)

INCF	Incremen	t f		
Syntax:	[ label ]	NCF f[	,d [,a]]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5		
Operation:	$(f) + 1 \rightarrow dest$			
Status Affected:	C, DC, N, OV, Z			
Encoding:	0010	10da	ffff	ffff
Description:	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).			
Words:	1			
Cycles:	1			
Q Cycle Activity:				

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

 $\begin{array}{c|cccc} \underline{Example:} & & INCF & & CNT \,, \\ \hline Before Instruction & & & \\ CNT & = & 0xFF \\ Z & = & 0 \\ C & = & ? \\ DC & = & ? \\ DC & = & ? \\ \hline After Instruction & & \\ CNT & = & 0x00 \\ Z & = & 1 \\ C & = & 1 \\ DC & = & 1 \\ \end{array}$ 

INCFSZ	Increment	f, Skip if 0		INF	SNZ	Increment	f, Skip if not	0
Syntax:	[ label ] IN	NCFSZ f[,d	[,a]]	Syn	tax:	[ label ] IN	NFSNZ f[,d	[,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			Оре	erands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$		
Operation:	(f) + 1 $\rightarrow$ deskip if result	-		Оре	eration:	(f) + 1 $\rightarrow$ deskip if resul	•	
Status Affected:	None			Stat	us Affected:	None		
Encoding:	0011	11da ff	ff ffff	Enc	oding:	0100	10da ff	ff ffff
Description:  The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If the result is '0', the next instruction which is already fetched is discarded and a NOP is executed instead, making it a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).		Des	cription:	incremente placed in W placed back If the result instruction will discarded a instead, ma instruction. will be selec- value. If 'a'	cted, overridin = 1, then the I	he result is ne result is (default). next dy fetched is executed eycle Access Bank g the BSR		
Words:	1	(40.44.1).		Wor	rds.	1	por 11.0 2011	raide (deidail).
Cycles:	1(2) <b>Note:</b> 3 cy	/cles if skip an a 2-word instru		Сус		1(2) <b>Note:</b> 3 c	ycles if skip ar a 2-word instr	
Q Cycle Activity:	·			Q	Cycle Activity:	•		
Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination		Decode	Read register 'f'	Process Data	Write to destination
If skip:				If s	kip:			_
Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
If skip and follow	ed by 2-word ir	struction:		If s	If skip and followed by 2-word instruction:			
Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
No	No	No	No		No	No	No	No
operation No	operation No	operation No	operation No		operation No	operation No	operation No	operation No
operation	operation	operation	operation		operation	operation	operation	operation
Example:		:	NT	<u>Exa</u>	mple:	HERE ZERO NZERO	INFSNZ REG	
Before Instruction			Before Instruc	ction				
PC		s (HERE)			PC	= Addres	s (HERE)	
After Instruc					After Instruction			
CNT If CNT PC If CNT PC	<b>≠</b> 0;	s (ZERO) s (NZERO)			REG If REG PC If REG PC	= 0;	s (NZERO) s (ZERO)	

**IORLW** Inclusive OR Literal with W

Syntax: [label] IORLW k

Operands:  $0 \le k \le 255$ Operation: (W) .OR.  $k \rightarrow W$ 

N, Z Status Affected:

Encoding: 0000 1001 kkkk kkkk

Description: The contents of W are ORed with the

eight-bit literal 'k'. The result is placed in

Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to W
	literal 'k'	Data	

Example: IORLW 0x35

Before Instruction

W 0x9A

After Instruction

W 0xBF

IORWF	Inclusive	OR W wi	th f		
Syntax:	[ label ]	ORWF	f [,d [,a]]		
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	5			
Operation:	(W) .OR. (f) $\rightarrow$ dest				
Status Affected:	N, Z				
Encoding:	0001	00da	ffff	ffff	
Description:	Inclusive OR W with register 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).				
Words:	1				
Cycles:	1				
O Cycle Activity:					

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example: IORWF RESULT, W

Before Instruction

RESULT = W = 0x13 0x91

After Instruction

RESULT = W = 0x13 0x93

LFSR	Load FSR		
Syntax:	[label] LFSR f,k		
Operands:	$0 \le f \le 2$ $0 \le k \le 4095$		
Operation:	$k \to FSRf$		
Status Affected:	None		
Encoding:	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$		
Description:	The 12-bit literal 'k' is loaded into the file select register pointed to by 'f'.		

Words: 2 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k' MSB	Process Data	Write literal 'k' MSB to FSRfH
Decode	Read literal 'k' LSB	Process Data	Write literal 'k' to FSRfL

Example: LFSR 2, 0x3AB

After Instruction

FSR2H = 0x03 FSR2L = 0xAB

MOVF	Move f			
Syntax:	[ label ]	MOVF f	[,d [,a]]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	;		
Operation:	$f \to \text{dest}$			
Status Affected:	N, Z			
Encoding:	0101	00da	ffff	ffff
	The contents of register 'f' are moved to a destination dependent upon the status of 'd'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). Location 'f' can be anywhere in the 256-byte bank. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).			
Words:	1			
Cycles:	1			
O Cycle Activity:				

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write W
	register 'f'	Data	

Example: MOVF REG, W

Before Instruction

REG = 0x22 W = 0xFF

After Instruction

 $\begin{array}{ccc} \mathsf{REG} & = & \mathsf{0x22} \\ \mathsf{W} & = & \mathsf{0x22} \end{array}$ 

MOVFF	Move f to f
Syntax:	[ label ] MOVFF f <sub>s</sub> ,f <sub>d</sub>
Operands:	$0 \le f_s \le 4095$ $0 \le f_d \le 4095$
Operation:	$(f_s)  o f_d$
Status Affected:	None
Encoding: 1st word (source) 2nd word (destin.)	1100 ffff ffff ffffs 1111 ffff ffff ffffd
Description:	The contents of source register 'fs' are

The contents of source register 'f<sub>s</sub>' are moved to destination register 'f<sub>d</sub>'.

Location of source 'f<sub>s</sub>' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination 'f<sub>d</sub>' can also be anywhere from 000h to FFFh.

Either source or destination can be W (a useful special situation).

MOVFF is particularly useful for transferring a data memory location to

transferring a data memory location to a peripheral register (such as the transmit buffer or an I/O port).

The MOVFF instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination register.

The MOVFF instruction should not be used to modify interrupt settings while any interrupt is enabled (see page 77).

Words: 2 Cycles: 2 (3)

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read register 'f' (src)	Process Data	No operation
Decode	No operation No dummy read	No operation	Write register 'f' (dest)

Example: MOVFF REG1, REG2

Before Instruction

 $REG1 = 0x33 \\
 REG2 = 0x11$ 

After Instruction

REG1 = 0x33 REG2 = 0x33

MOV	'LB	Move Liter	ral to Lov	w Nibble i	n BSR
Synta	ax:	[label] N	MOVLB I	ĸ	
Oper	rands:	$0 \le k \le 255$	i		
Operation: $k \rightarrow BSR$					
Statu	ıs Affected:	None			
Enco	oding:	0000	0001	kkkk	kkkk
Description:		The 8-bit lit Bank Selec			to the
Word	ds:	1			
Cycle	es:	1			
Q Cycle Activity:					
	Q1	Q2	Q3	}	Q4
	Decode	Read literal	Proce Data		Write eral 'k' to

**BSR** 

Example: MOVLB 5

Before Instruction

BSR register = 0x02

After Instruction

BSR register = 0x05

MOV	LW	Move Lite	ral to W			
Synta	ax:	[ label ]	MOVLW	k		
Oper	ands:	$0 \le k \le 25$	$0 \leq k \leq 255$			
Oper	ation:	$k\toW$				
Status Affected:		None				
Encoding:		0000	1110	kkk	k	kkkk
Description:		The eight-bit literal 'k' is loaded into W.				
Words:		1				
Cycles:		1				
Q Cycle Activity:						
	Q1	Q2	Q	3		Q4
	Decode	Read	Proce		Wri	te to W
	I	literal 'k'	Dat	a		

Example: MOVLW 0x5A

After Instruction

W = 0x5A

$\leq$ f $\leq$ 258 $\in$ [0,1] W) $\rightarrow$ f Hone 0110 Move data ocation 456-byte b	111a a from W t	anywhere	e in the
$\in [0,1]$ W) $\rightarrow$ f  Hone  0110  Move data ocation 456-byte byte 15	111a a from W t	o registe anywhere	er 'f'. e in the
lone 0110 love data ocation '1	a from W t f' can be a	o registe anywhere	er 'f'. e in the
0110 Nove data ocation (1	a from W t f' can be a	o registe anywhere	er 'f'. e in the
Nove data ocation 'i 56-byte b	a from W t f' can be a	o registe anywhere	er 'f'. e in the
ocation 'i 56-byte t	f' can be a	anywhere	e in the
SR value e selecte	be selecte	ed, overri ., then th	ding the e bank will
Q2	Q	3	Q4
Read			Write register 'f'
	Q2 Read	Q2 Q3 Read Proce	Q2 Q3 Read Process

Example: MOVWF REG

Before Instruction

W = 0x4FREG = 0xFF

After Instruction

W = 0x4F REG = 0x4F

MULLW	Multiply Literal with W		
Syntax:	[label] MULLW k		
Operands:	$0 \le k \le 255$		
Operation:	(W) $x k \rightarrow PRODH:PRODL$		
Status Affected:	None		
Encoding:	0000 1101 kkkk kkkk		
Description:	An unsigned multiplication is carried out between the contents of W and the 8-bit literal 'k'. The 16-bit result is placed in		

the PRODH:PRODL register pair. PRODH contains the high byte. W is unchanged. None of the status flags are affected.

Note that neither Overflow nor Carry is possible in this operation. A Zero result

is possible but not detected.

Words: Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'k'	Process Data	Write registers PRODH: PRODL

Example: MULLW 0xC4

Before Instruction

0xE2 PRODH PRODL

After Instruction

W 0xE2 PRODH PRODL 0xAD = 0x08

MULWF	Multiply W with f				
Syntax:	[ label ]	MULWF	f [,a]		
Operands:	$0 \le f \le 255$ $a \in [0,1]$				
Operation:	(W) $x (f) \rightarrow PRODH:PRODL$				
Status Affected:	None				
Encoding:	0000	001a	ffff	ffff	
Description:	An unsigned multiplication is carried out				

between the contents of W and the register file location 'f'. The 16-bit result is stored in the PRODH:PRODL register pair. PRODH contains the high byte. Both W and 'f' are unchanged.

None of the status flags are affected. Note that neither Overflow nor Carry is possible in this operation. A Zero result is possible but not detected. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a'= 1, then the bank will be selected as per the

BSR value (default).

Words: 1 Cycles:

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	registers
			PRODH:
			PRODL

Example: MULWF REG Before Instruction W 0xC4 REG 0xB5 PRODH PRODL After Instruction W 0xC4 REG 0xB5 PRODH 0x8A PRODL 0x94

NEGF	Negate f		
Syntax:	[ label ] NEGF f [,a]		
Operands:	$0 \le f \le 255$ $a \in [0,1]$		
Operation:	$(\overline{f}) + 1 \rightarrow f$		
Status Affected:	N, OV, C, DC, Z		
Encoding:	0110 110a ffff ffff		
Description:	Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value.		
Words:	1		
Cycles:	1		
Q Cycle Activity:			

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: NEGF REG, 1

Before Instruction

REG =  $0011 \ 1010 \ [0x3A]$ 

After Instruction

REG = 1100 0110 [0xC6]

NOP		No Operat	tion			
Synta	ax:	[ label ]	NOP			
Oper	ands:	None				
Oper	ation:	No operati	on			
Statu	s Affected:	None				
Enco	ding:	0000	0000	000	0	0000
		1111	XXXX	XXX	X	XXXX
Desc	ription:	No operati	on.			
Word	ls:	1				
Cycle	es:	1				
Q Cycle Activity:						
	Q1	Q2	Q	3		Q4
	Decode	No	No			No
		operation	opera	tion	ор	eration

Example:

None.

Before Instruction

After Instruction

TOS PC

TOS Stack (1 level down)

POP	POP Pop Top of Return Stack				
Synta	ax:	[ label ] F	POP		
Oper	ands:	None			
Oper	ation:	$(TOS) \rightarrow b$	it bucket		
Statu	s Affected:	None			
Enco	ding:	0000	0000	0000	0110
Desc	ription:	then becor was pushe This instru	s discard nes the p d onto th ction is p properly	led. The revious e returr rovided manag	e TOS value s value that n stack. to enable te the return
Word	ls:	1			
Cycle	es:	1			
QC	ycle Activity:				
	Q1	Q2	Q	3	Q4
	Decode	No	POP 1	ros	No
		operation	valu	e	operation
Example:		POP GOTO	NEW		

0x0031A2 0x014332

0x014332 NEW

PUSH		Push Top o	f Retur	n Stack			
Synta	ax:	[label] Pl	[label] PUSH				
Operands:		None					
Oper	ation:	$(PC+2)\rightarrow$	TOS				
Statu	s Affected:	None					
Enco	ding:	0000	0000	0000	0101		
Description:  The PC + 2 is pushed onto the top of the return stack. The previous TOS value is pushed down on the stack. This instruction allows the user to implement a software stack by modifying TOS and then pushing it of the return stack.			s TOS stack. ser to by				
Word	ls:	1					
Cycle	es:	1					
QC	ycle Activity:						
	Q1	Q2	Q:	3	Q4		
	Decode	PUSH PC + 2	No	)	No		
		onto return stack	opera	tion	peration		
Exan	nple:	PUSH					

RCALL	Relative Call			
Syntax:	[ label ] RCALL n			
Operands:	$-1024 \le n \le 1023$			
Operation:	$ (PC) + 2 \rightarrow TOS, $ $ (PC) + 2 + 2n \rightarrow PC $			
Status Affected:	None			
Encoding:	1101 1nnn nnnn nnnn			
Description:	Subroutine call with a jump up to 1K from the current location. First, return address (PC + 2) is pushed onto the			

address (PC + 2) is pushed onto the stack. Then, add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a two-cycle instruction.

two-cycle instruction

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read literal 'n'	Process	Write to
	Push PC to	Data	PC
	stack		
No	No	No	No
operation	operation	operation	operation

Example: HERE RCALL Jump

Before Instruction

PC = Address (HERE)

After Instruction

PC = Address (Jump) TOS = Address (HERE + 2)

RES	ET	Reset				
Synta	ax:	[label] F	RESET			
Oper	ands:	: None				
Operation:			Reset all registers and flags that are affected by a MCLR Reset.			
Statu	s Affected:	All				
Encoding:		0000	0000	111	.1	1111
Desc	ription:	This instruction				•
Word	ls:	1				
Cycles:		1				
Q Cycle Activity:						
	Q1	Q2	Q3			Q4
	Decode	Start	No			No

Example: RESET

After Instruction

Registers = Reset Value Flags\* = Reset Value

Reset

operation

operation

REIFIE	Return fr	om	Interru	ıpı

Syntax: [ label ] RETFIE [s] Operands:  $s \in [0,1]$ 

Operation:  $S \in [0,1]$ Operation:  $(TOS) \rightarrow PC$ ,

1 → GIE/GIEH or PEIE/GIEL,

if s = 1 (WS)  $\rightarrow$  W,

 $(STATUSS) \rightarrow Status,$  $(BSRS) \rightarrow BSR,$ 

PCLATU, PCLATH are unchanged.

Status Affected: GIE/GIEH, PEIE/GIEL.

Encoding: 0000 0000 0001 000s

Description: Return from interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into the PC. Interrupts are enabled by

the PC. Interrupts are enabled by setting either the high or low priority global interrupt enable bit. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers W, Status and BSR. If 's' = 0, no update of these

registers occurs (default).

Words: 1 Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	No	Pop PC from
	operation	operation	stack
			Set GIEH or GIEL
No	No	No	No
operation	operation	operation	operation

Example: RETFIE 1

After Interrupt

RETLW R	eturn Literal to W
---------	--------------------

Syntax: [ label ] RETLW k

Operands:  $0 \le k \le 255$ 

Operation:  $k \to W, \\ (TOS) \to PC,$ 

PCLATU, PCLATH are unchanged

Status Affected: None

Encoding: 0000 1100 kkkk kkkk

Description: W is loaded with the eight-bit literal 'k'.

The program counter is loaded from the

top of the stack (the return address).
The high address latch (PCLATH)

remains unchanged.

Words: 1
Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Pop PC
	literal 'k'	Data	from stack,
			Write to W
No	No	No	No
operation	operation	operation	operation

#### Example:

```
CALL TABLE ; W contains table ; offset value ; W now has ; table value
```

TABLE

ADDWF PCL ; W = offset RETLW k0 ; Begin table

RETLW k1 ;

:

RETLW kn ; End of table

Before Instruction

W = 0x07

After Instruction

W = value of kn

RETURN	Return from Subroutine			
Syntax:	[ label ] RETURN [s]			
Operands:	s ∈ [0,1]			
Operation:	$\begin{split} &(TOS) \to PC,\\ &if \; s = 1\\ &(WS) \to W,\\ &(STATUSS) \to Status,\\ &(BSRS) \to BSR,\\ &PCLATU, \; PCLATH \; are \; unchanged \end{split}$			
Status Affected:	None			
Encoding:	0000 0000 0001 001s			
Description:	Return from subroutine. The stack is popped and the top of the stack (TOS) is loaded into the program counter. If 's'= 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers W, Status and BSR. If 's' = 0, no update of these registers occurs (default).			
Words:	1			
Cycles:	2			
Q Cycle Activity:				

Q1	Q2	Q3	Q4
Decode	No	Process	Pop PC
	operation	Data	from stack
No	No	No	No
operation	operation	operation	operation

Example: RETURN

After Interrupt PC = TOS

RLCF	Rotate Lef	t f throu	gh Carry		
Syntax:	[ label ]	RLCF	f [,d [,a]]		
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d \in  [0,1] \\ a \in  [0,1] \end{array}$				
Operation:	$(f) \rightarrow dest,  (f<7>) \rightarrow C,  (C) \rightarrow dest<0>$				
Status Affected:	C, N, Z				
Encoding:	0011	01da	ffff	ffff	
Description:	The contents of register 'f' are rotated one bit to the left through the Carry flag. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q	3	Q4	
Decode	Read register 'f'	Proce Data		Write to estination	
Example:  Before Instruc	RLCF tion	RI	EG, W		

1110 0110

After Instruction

REG = 1110 0110

W = 1100 1100

C = 1

REG C

RLN	CF	Rotate Left f (no carry)				
Synta	ax:	[ label ]	RLNCF	f [,d	[,a]]	
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Oper	ation:	$(f) \rightarrow dest,$ $(f<7>) \rightarrow dest<0>$				
Statu	s Affected:	N, Z				
Enco	ding:	0100	01da	fff	f	ffff
	ription:	The contents of register 'f' are rotated one bit to the left. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).				
			reg	ister f		
Word	ls:	1				
Cycle	es:	1				
QC	ycle Activity:					
	Q1	Q2	Q	3		Q4
	Decode	Read register 'f'	Proce Data			rite to tination

Example: RLNCF REG Before Instruction REG 1010 1011 = After Instruction REG 0101 0111 =

RRCF	Rotate Right f through Carry				
Syntax:	[label] R	RCF f	[,d [,a]]		
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Operation:	$(f) \rightarrow de$ $(f<0>) \rightarrow C$ , $(C) \rightarrow dest<$		>,		
Status Affected:	C, N, Z				
Encoding:	0011	00da	ffff	ffff	
	one bit to the right through the Carry flag. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3		Q4	
Decode	Read register 'f'	Proce Data		Vrite to stination	
Example:	RRCF F	REG, W			

RRNCF	Rotate Right f (no carry)				
Syntax:	[ label ]	RRNCF	f [,d [,a]]		
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Operation:	$(f) \rightarrow dest,$ $(f<0>) \rightarrow dest<7>$				
Status Affected:	N, Z				
Encoding:	0100	00da	ffff	ffff	
Description:	The contents of register 'f' are rotated one bit to the right. If 'd' is '0', the result				

is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).



Words: 1 Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	register 'f'	Data	destination

Example 1: RRNCF REG, 1, 0

Before Instruction

1101 0111 REG

After Instruction

REG 1110 1011

Example 2: RRNCF REG, W

Before Instruction

W REG

1101 0111

After Instruction

1110 1011 REG 1101 0111

SETF	Set f			
Syntax:	[ label ] SETF f [,a]			
Operands:	$0 \le f \le 255$ $a \in [0,1]$			
Operation:	$FFh \to f$			
Status Affected:	None			
Encoding:	0110 100a ffff ffff			
Description:	The contents of the specified register are set to FFh. If 'a' is '0', the Access Bank will be selected, overriding the			

BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).

Words: 1

Cycles: 1 Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write
	register 'f'	Data	register 'f'

Example: SETF REG

Before Instruction

REG 0x5A

After Instruction

REG 0xFF

# PIC18FXX8

SLEE	P	Enter Sle	Enter Sleep Mode				
Synta	ax:	[ label ]	SLEEP				
Oper	ands:	None	None				
Oper	ation:						
Statu	s Affected:	TO, PD					
Enco	ding:	0000	0000	0000	0011		
Desc	ription:	cleared. T is set. Wa postscale The proce	The Power-Down status bit (\$\overline{PD}\$) is cleared. The Time-out status bit (\$\overline{TO}\$) is set. Watchdog Timer and its postscaler are cleared.  The processor is put into Sleep mode with the oscillator stopped.				
Word	s:	1					
Cycle	es:	1					
Q C	ycle Activity:						
	Q1	Q2	Q3		Q4		
	Decode	No	Proces	ss	Go to		

Example:		SLEEP			
Before Instruction					
TO	=	?			
PD	=	?			
After Instruction					
TO	=	1 †			
PD	=	0			

† If WDT causes wake-up, this bit is cleared.

operation

Data

Sleep

SUBFWB	•	Subtract	f from W with	Borrow
Syntax:	[	label]	SUBFWB f	[,d [,a]]
Operands:		$0 \le f \le 25$	55	
		$d \in [0,1]$ $a \in [0,1]$		
Operation:			$-(\overline{C}) \rightarrow dest$	
Status Affected:		N, OV, C	` '	
Encoding:	ſ	0101	01da ff	ff ffff
Description:	( r r v c	borrow) method). n W. If 'c register 'f Access E overridin hen the	register 'f' and from W (2's co If 'd' is '0', the r d' is '1', the resuf (default). If 'a sank will be seleg the BSR value bank will be se value (default).	mplement result is stored ult is stored in 'is '0', the ected, e. If 'a' is '1', lected as per
Words:	1	l	, ,	
Cycles:	1	I		
Q Cycle Activity:				
Q1		Q2	Q3	Q4
Decode		Read	Process Data	Write to destination
		jister 'f'		uesilialion
Example 1:		SUBFWB	REG	
Before Instruct REG W C After Instructio	= = =	0x03 0x02 0x01		
REG W C Z N	= = = = =	0xFF 0x02 0x00 0x00 0x01	; result is neg	ative
Example 2:	5	SUBFWB	REG, 0, 0	
Before Instruct	tion			
REG W C After Instructio	= = = n	2 5 1		
REG W C Z	= = =	2 3 1 0		
N	=	Ö	; result is posi	tive
Example 3:	S	SUBFWB	REG, 1, 0	)
Before Instruct REG W C	= = =	1 2 0		
After Instructio REG	n =	0		
W	=	2 1		
Ž N	=	i	; result is zero	)

SUBLW	Subtract W from Literal	SUBWF	Subtract W from f
Syntax:	[ label ] SUBLW k	Syntax:	[ label ] SUBWF f [,d [,a]]
Operands:	$0 \le k \le 255$	Operands:	$0 \leq f \leq 255$
Operation:	$k - (W) \rightarrow W$		$d \in [0,1]$
Status Affected:	N, OV, C, DC, Z	Onematica	$a \in [0,1]$
Encoding:	0000 1000 kkkk kkkk	Operation:	$(f) - (W) \rightarrow dest$
Description:	W is subtracted from the eight-bit	Status Affected:	N, OV, C, DC, Z
	literal 'k'. The result is placed in W.	Encoding:	0101   11da   ffff   ffff
Words:	1	Description:	Subtract W from register 'f' (2's complement method). If 'd' is '0', the
Cycles:	1		result is stored in W. If 'd' is '1', the
Q Cycle Activity:			result is stored back in register 'f'
Q1	Q2 Q3 Q4		(default). If 'a' is '0', the Access Bank will be selected, overriding the BSR
Decode	Read Process Write to W literal 'k' Data		value. If 'a' is '1', then the bank will be
			selected as per the BSR value (default).
Example 1:	SUBLW 0x02	Words:	1
Before Instruc W	etion = 1	Cycles:	1
С	= ?	Q Cycle Activity:	•
After Instruction	on = 1	Q Cycle Activity.	Q2 Q3 Q4
С	= 1 ; result is positive	Decode	Read Process Write to
Z N	= 0 = 0		register 'f' Data destination
Example 2:	SUBLW 0x02	Example 1:	SUBWF REG
Before Instruc	etion	Before Instruc	etion
W C	= 2 = ?	REG W	= 3 = 2
After Instruction		С	= ?
W	= 0	After Instruction	on = 1
C Z	= 1 ; result is zero = 1	W	= 2
N	= 0	C Z	= 1 ; result is positive = 0
Example 3:	SUBLW 0x02	N	= 0
Before Instruc		Example 2:	SUBWF REG, W
W C	= 3 = ?	Before Instruc	
After Instruction		REG W	= 2 = 2
W C	<ul><li>FF ; (2's complement)</li><li>0 ; result is negative</li></ul>	C After Instruction	= ?
Ž N	= 0	REG	= 2
N	= 1	W C	= 0 = 1 ; result is zero
		Z	= 1
		N Farmula 0	= 0
		Example 3:	SUBWF REG
		Before Instruc REG	etion = 0x01
		W	= 0x02
		C After Instruction	= ? on
		REG	= 0xFFh ;(2's complement)
		W C	= 0x02 = 0x00 ; result is negative
		Z N	= 0x00 = 0x01
		IV	_ 0,01

SUBWFB	Subtract W	/ from f with E	Borrow
Syntax:	[ label ] S	UBWFB f[,d	[,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$		
Operations	a ∈ [0,1]	<u></u>	
Operation:	(f) - (W) - (W)	,	
Status Affected:	N, OV, C, D		
Encoding:	0101	10da fff	
Description:	from register method). If in W. If 'd' is in register 'f Access Bar overriding t	and the Carry er 'f' (2's compl 'd' is '0', the result f' (default). If 'ank will be select he BSR value. Ink will be select (default).	ement sult is stored is stored back ' is '0', the ted, If 'a' is '1',
Words:	1	,	
Cycles:	1		
Q Cycle Activity:			
Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
Example 1:	SUBWFB	REG, 1, 0	
Before Instruc	tion		
REG ₩ C	= 0x19 = 0x0D = 0x01	(0001 100 (0000 110	
After Instruction	on = 0x0C	(0000 103	11)
W	= 0x0D	(0000 10	
C Z	= 0x01 = 0x00		
N	= 0x00	; result is po	ositive
Example 2:	SUBWFB	REG, 0, 0	
Before Instruc REG	tion = 0x1B	(0001 103	11)
W C	= 0x1A = 0x00	(0001 103	
After Instruction			
REG W	= 0x1B = 0x00	(0001 103	11)
Ċ Z	= 0x01	: result is ze	aro.
N N	= 0x01  = 0x00	, result is 26	910
Example 3:	SUBWFB	REG, 1, 0	
Before Instruc			
REG W	= 0x03 = 0x0E	(0000 001	
C After Instruction	= 0x01		
REG	= 0xF5	(1111 010	
W	= 0x0E	; [2's comp]	
C Z	= 0x00 = 0x00		•
N	= 0x01	; result is ne	egative

SWA	PF	Swap f				
Synta	ax:	[ label ]	SWAPF	f [,d [,a	a]]	
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Oper	ation:	$(f<3:0>) \rightarrow dest<7:4>,$ $(f<7:4>) \rightarrow dest<3:0>$				
Statu	s Affected:	None				
Enco	ding:	0011	10da	fff	f	ffff
Desc	ription:	The upper a 'f' are excha is placed in placed in re the Access overriding to then the ba the BSR va	anged. If W. If 'd' gister 'f' ( Bank wil he BSR v nk will be	'd' is 'is 'is '1', i (defau I be se value. e selec	o', the rate of the rate of the rate of the contract of the co	ne result result is f 'a' is '0', red, ' is '1',
Word	ls:	1				
Cycle	es:	1				
Q Cycle Activity:						
	Q1	Q2	Q3			Q4
	Decode	Read register 'f'	Proces Data			rite to stination

Example:	SWAPF		REG	
Before Instruc	tion			
REG	=	0x53		
After Instruction				
REG	=	0x35		

**TBLRD Table Read** 

TBLRD ( \*; \*+; \*-; +\*) Syntax: [ label ]

Operands: None

Operation:

if TBLRD \*, (Prog Mem (TBLPTR)) → TABLAT; TBLPTR – No Change; if TBLRD \*+,

(Prog Mem (TBLPTR))  $\rightarrow$  TABLAT; (TBLPTR) + 1  $\rightarrow$  TBLPTR; if TBLRD \*-,

(Prog Mem (TBLPTR)) → TABLAT;

(TBLPTR) – 1 → TBLPTR; if TBLRD +\*,

(TBLPTR)  $+'1 \rightarrow TBLPTR$ ;

(Prog Mem (TBLPTR)) → TABLAT

Status Affected: None

Encoding:

0000	0000	0000	10nr	ı
			nn=0	*
			=1	*+
			=2	* -
			=3	+*

Description:

This instruction is used to read the contents of Program Memory (P.M.). To address the program memory, a pointer called Table Pointer (TBLPTR) is used.

The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a

2-Mbyte address range.

TBLPTR[0] = 0:Least Significant

Byte of Program Memory Word

TBLPTR[0] = 1: Most Significant Byte

of Program Memory

Word

The  ${\tt TBLRD}$  instruction can modify the value of TBLPTR as follows:

no change

post-increment post-decrement

pre-increment

Words: Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No	No	No
	operation	operation	operation
No operation	No operation (Read Program Memory)	No operation	No operation (Write TABLAT)

Example 1: TBLRD \*+ ;

Before Instruction

**TABLAT** 0x55 **TBLPTR** 0x00A356 MEMORY(0x00A356) 0x34

After Instruction

**TABLAT** 0x34 **TBLPTR** 0x00A357 =

Example 2: TBLRD +\*;

Before Instruction

**TABLAT** 0xAA TBLPTR MEMORY(0x01A357) MEMORY(0x01A358) 0x01A357 0x12 0x34

After Instruction

TABLAT TBLPTR 0x34 0x01A358 **TBLWT Table Write** 

Syntax: TBLWT ( \*; \*+; \*-; +\*) [ label ]

Operands: None

Operation:

if TBLWT\*, (TABLAT) → Holding Register; TBLPTR – No Change; if TBLWT\*+,

(TABLAT) → Holding Register; (TBLPTR) + 1  $\rightarrow$  TBLPTR; if TBLWT\*-,

(TABLAT) → Holding Register; (TBLPTR) – 1 → TBLPTR; if TBLWT+\*,

(TBLPTR)  $+1 \rightarrow$  TBLPTR;

(TABLAT) → Holding Register;

Status Affected: None

Encoding:

0000	0000	0000	11nn
			nn=0 *
			=1 *+
			=2 *-
			=3 +*

Description:

This instruction uses the 3 LSBs of TBLPTR to determine which of the 8 holding registers the TABLAT is written to. The holding registers are used to program the contents of Program Memory (P.M.). (Refer to Section 6.0 "Flash **Program Memory**" for additional details.) The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2-Mbyte address range. The LSb of the TBLPTR selects which byte of the program memory location to access.

> Least Significant Byte TBLPTR[0] = 0:

of Program Memory

Word

TBLPTR[0] = 1: Most Significant Byte

of Program Memory Word

The TBLWT instruction can modify the value of TBLPTR as follows:

- · no change
- post-increment
- post-decrement
- pre-increment

#### **TBLWT Table Write (Continued)**

Words: 1

Cycles: 2 Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation
No operation	No operation (Read TABLAT)		No operation (Write to Holding Register)

Example 1:

TBLWT

Before Instruction

**TABLAT** 0x55 **TBLPTR** 0x00A356

HOLDING REGISTER

(0x00A356) 0xFF

After Instructions (table write completion) **TABLAT** 0x55 **TBLPTR** 0x00A357

HOLDING REGISTER (0x00A356) 0x55

Example 2: TBLWT +\*;

Before Instruction

**TABLAT** 0x34 0x01389A

TBLPTR HOLDING REGISTER

0xFF (0x01389A)

HOLDING REGISTER

0xFF (0x01389B)

After Instruction (table write completion)

**TABLAT** 0x34 **TBLPTR** 0x01389B

HOLDING REGISTER

0xFF (0x01389A)

HOLDING REGISTER

(0x01389B) 0x34 **TSTFSZ** Test f, Skip if 0

Syntax: [ label ] TSTFSZ f [,a]

Operands:  $0 \le f \le 255$  $a \in [0,1]$ 

skip if f = 0Operation:

Status Affected: None Encoding: 0110

Description: If 'f' = 0, the next instruction fetched

during the current instruction execution is discarded and a NOP is executed, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per

ffff

ffff

011a

the BSR value (default). Words:

Cycles: 1(2)

Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	No
	register 'f'	Data	operation

If skip:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation

If skip and followed by 2-word instruction:

Q1	Q2	Q3	Q4
No	No	No	No
operation	operation	operation	operation
No	No	No	No
operation	operation	operation	operation

Example: HERE TSTFSZ CNT

NZERO ZERO

Before Instruction

Address (HERE) PC

After Instruction

If CNT 0x00,

PC If CNT Address (ZERO)

0x00.

Address (NZERO)

XORLW	Exclusive OR Literal with W

Syntax: [label] XORLW k

Operands:  $0 \le k \le 255$ 

Operation: (W) .XOR.  $k \rightarrow W$ 

N, Z Status Affected:

Encoding: 0000 1010 kkkk kkkk

Description: The contents of W are XORed with the 8-bit literal 'k'. The result is placed

in W.

Words:

Cycles:

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	literal 'k'	Data	W

Example: XORLW 0xAF

Before Instruction

W 0xB5

After Instruction

W 0x1A

### WWW PIC18FXX8

XORWF Exclusive OR W with f

Syntax: [ label ] XORWF f [,d [,a]]

Operands:  $0 \leq f \leq 255 \\ d \in [0,1] \\ a \in [0,1]$ 

Operation: (W) .XOR. (f)  $\rightarrow$  dest

Status Affected: N, Z

Encoding: 0001 10da ffff ffff

Description: Exclusive OR the contents of W with register 'f'. If 'd' is '0', the result is stored

in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected,

overriding the BSR value. If 'a' is '1', then the bank will be selected as per

the BSR value (default).

Words: 1
Cycles: 1

Q Cycle Activity:

Q1	Q2	Q3	Q4	
Decode	Read	Process	Write to	l
	register 'f'	Data	destination	ı

Example: XORWF REG

Before Instruction

 $\begin{array}{rcl} \mathsf{REG} & = & \mathsf{0xAF} \\ \mathsf{W} & = & \mathsf{0xB5} \end{array}$ 

After Instruction

 $\begin{array}{ccc} \mathsf{REG} & = & \mathsf{0x1A} \\ \mathsf{W} & = & \mathsf{0xB5} \end{array}$ 

### 26.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM™ Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB C30 C Compiler
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
  - MPLAB dsPIC30 Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB ICE 4000 In-Circuit Emulator
- In-Circuit Debugger
  - MPLAB ICD 2
- Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Development Programmer
  - MPLAB PM3 Device Programmer
- · Low-Cost Demonstration Boards
  - PICDEM™ 1 Demonstration Board
  - PICDEM.net™ Demonstration Board
  - PICDEM 2 Plus Demonstration Board
  - PICDEM 3 Demonstration Board
  - PICDEM 4 Demonstration Board
  - PICDEM 17 Demonstration Board
  - PICDEM 18R Demonstration Board
  - PICDEM LIN Demonstration Board
  - PICDEM USB Demonstration Board
- Evaluation Kits
  - KEELOQ® Evaluation and Programming Tools
  - PICDEM MSC
  - microID® Developer Kits
  - CAN
  - PowerSmart® Developer Kits
  - Analog

## 26.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit microcontroller market. The MPLAB IDE is a Windows® based application that contains:

- · An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor with color coded context
- A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- · Mouse over variable inspection
- · Extensive on-line help

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - source files (assembly or C)
  - mixed assembly and C
  - machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increasing flexibility and power.

### 26.2 MPASM Assembler

The MPASM assembler is a full-featured, universal macro assembler for all PICmicro MCUs.

The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM assembler features include:

- · Integration into MPLAB IDE projects
- · User defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

## 26.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI C compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

## 26.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB object librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

### 26.5 MPLAB C30 C Compiler

The MPLAB C30 C compiler is a full-featured, ANSI compliant, optimizing compiler that translates standard ANSI C programs into dsPIC30F assembly language source. The compiler also supports many command line options and language extensions to take full advantage of the dsPIC30F device hardware capabilities and afford fine control of the compiler code generator.

MPLAB C30 is distributed with a complete ANSI C standard library. All library functions have been validated and conform to the ANSI C library standard. The library includes functions for string manipulation, dynamic memory allocation, data conversion, time-keeping and math functions (trigonometric, exponential and hyperbolic). The compiler provides symbolic information for high-level source debugging with the MPLAB IDE.

## 26.6 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 compiler uses the assembler to produce it's object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire dsPIC30F instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- · Flexible macro language
- MPLAB IDE compatibility

### 26.7 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any pin. The execution can be performed in Single-Step, Execute Until Break or Trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and MPLAB C18 C Compilers, as well as the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent, economical software development tool.

#### 26.8 MPLAB SIM30 Software Simulator

The MPLAB SIM30 software simulator allows code development in a PC hosted environment by simulating the dsPIC30F series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any of the pins.

The MPLAB SIM30 simulator fully supports symbolic debugging using the MPLAB C30 C Compiler and MPLAB ASM30 assembler. The simulator runs in either a Command Line mode for automated tasks, or from MPLAB IDE. This high-speed simulator is designed to debug, analyze and optimize time intensive DSP routines.

# 26.9 MPLAB ICE 2000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 2000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers. Software control of the MPLAB ICE 2000 in-circuit emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE 2000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft® Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 26.10 MPLAB ICE 4000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 4000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for highend PICmicro microcontrollers. Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICD 4000 is a premium emulator system, providing the features of MPLAB ICE 2000, but with increased emulation memory and high-speed performance for dsPIC30F and PIC18XXXX devices. Its advanced emulator features include complex triggering and timing, up to 2 Mb of emulation memory and the ability to view variables in real-time.

The MPLAB ICE 4000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

## 26.11 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PICmicro MCUs and can be used to develop for these and other PICmicro microcontrollers. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming™ (ICSP™) protocol, offers cost effective in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single-stepping and watching variables, CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real-time. MPLAB ICD 2 also serves as a development programmer for selected PICmicro devices.

## 26.12 PRO MATE II Universal Device Programmer

The PRO MATE II is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features an LCD display for instructions and error messages and a modular detachable socket assembly to support various package types. In Stand-Alone mode, the PRO MATE II device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode.

### 26.13 MPLAB PM3 Device Programmer

The MPLAB PM3 is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode. MPLAB PM3 connects to the host PC via an RS-232 or USB cable. MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

## 26.14 PICSTART Plus Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus development programmer supports most PICmicro devices up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

## 26.15 PICDEM 1 PICmicro Demonstration Board

The PICDEM 1 demonstration board demonstrates the capabilities of the PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The sample microcontrollers provided with the PICDEM 1 demonstration board can be programmed with a PRO MATE II device programmer or a PICSTART Plus development programmer. The PICDEM 1 demonstration board can be connected to the MPLAB ICE in-circuit emulator for testing. A prototype area extends the circuitry for additional application components. Features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs.

## 26.16 PICDEM.net Internet/Ethernet Demonstration Board

The PICDEM.net demonstration board is an Internet/ Ethernet demonstration board using the PIC18F452 microcontroller and TCP/IP firmware. The board supports any 40-pin DIP device that conforms to the standard pinout used by the PIC16F877 or PIC18C452. This kit features a user friendly TCP/IP stack, web server with HTML, a 24L256 Serial EEPROM for Xmodem download to web pages into Serial EEPROM, ICSP/MPLAB ICD 2 interface connector, an Ethernet interface, RS-232 interface and a 16 x 2 LCD display. Also included is the book and CD-ROM "TCP/IP Lean, Web Servers for Embedded Systems," by Jeremy Bentham

## 26.17 PICDEM 2 Plus Demonstration Board

The PICDEM 2 Plus demonstration board supports many 18, 28 and 40-pin microcontrollers, including PIC16F87X and PIC18FXX2 devices. All the necessary hardware and software is included to run the demonstration programs. The sample microcontrollers provided with the PICDEM 2 demonstration board can be programmed with a PRO MATE II device programmer, PICSTART Plus development programmer, or MPLAB ICD 2 with a Universal Programmer Adapter. The MPLAB ICD 2 and MPLAB ICE in-circuit emulators may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area extends the circuitry for additional application components. Some of the features include an RS-232 interface, a 2 x 16 LCD display, a piezo speaker, an on-board temperature sensor, four LEDs and sample PIC18F452 and PIC16F877 Flash microcontrollers.

## 26.18 PICDEM 3 PIC16C92X Demonstration Board

The PICDEM 3 demonstration board supports the PIC16C923 and PIC16C924 in the PLCC package. All the necessary hardware and software is included to run the demonstration programs.

## 26.19 PICDEM 4 8/14/18-Pin Demonstration Board

The PICDEM 4 can be used to demonstrate the capabilities of the 8, 14 and 18-pin PIC16XXXX and PIC18XXXX MCUs, including the PIC16F818/819, PIC16F87/88, PIC16F62XA and the PIC18F1320 family of microcontrollers. PICDEM 4 is intended to showcase the many features of these low pin count parts, including LIN and Motor Control using ECCP. Special provisions are made for low-power operation with the supercapacitor circuit and jumpers allow onboard hardware to be disabled to eliminate current draw in this mode. Included on the demo board are provisions for Crystal, RC or Canned Oscillator modes, a five volt regulator for use with a nine volt wall adapter or battery, DB-9 RS-232 interface, ICD connector for programming via ICSP and development with MPLAB ICD 2, 2 x 16 liquid crystal display, PCB footprints for H-Bridge motor driver, LIN transceiver and EEPROM. Also included are: header for expansion, eight LEDs, four potentiometers, three push buttons and a prototyping area. Included with the kit is a PIC16F627A and a PIC18F1320. Tutorial firmware is included along with the User's Guide.

#### 26.20 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. A programmed sample is included. The PRO MATE II device programmer, or the PICSTART Plus development programmer, can be used to reprogram the device for user tailored application development. The PICDEM 17 demonstration board supports program download and execution from external on-board Flash memory. A generous prototype area is available for user hardware expansion.

## 26.21 PICDEM 18R PIC18C601/801 Demonstration Board

The PICDEM 18R demonstration board serves to assist development of the PIC18C601/801 family of Microchip microcontrollers. It provides hardware implementation of both 8-bit Multiplexed/Demultiplexed and 16-bit Memory modes. The board includes 2 Mb external Flash memory and 128 Kb SRAM memory, as well as serial EEPROM, allowing access to the wide range of memory types supported by the PIC18C601/801.

## 26.22 PICDEM LIN PIC16C43X Demonstration Board

The powerful LIN hardware and software kit includes a series of boards and three PICmicro microcontrollers. The small footprint PIC16C432 and PIC16C433 are used as slaves in the LIN communication and feature on-board LIN transceivers. A PIC16F874 Flash microcontroller serves as the master. All three microcontrollers are programmed with firmware to provide LIN bus communication.

## 26.23 PICkit™ 1 Flash Starter Kit

A complete "development system in a box", the PICkit™ Flash Starter Kit includes a convenient multi-section board for programming, evaluation and development of 8/14-pin Flash PIC® microcontrollers. Powered via USB, the board operates under a simple Windows GUI. The PICkit 1 Starter Kit includes the User's Guide (on CD ROM), PICkit 1 tutorial software and code for various applications. Also included are MPLAB® IDE (Integrated Development Environment) software, software and hardware "Tips 'n Tricks for 8-pin Flash PIC® Microcontrollers" Handbook and a USB interface cable. Supports all current 8/14-pin Flash PIC microcontrollers, as well as many future planned devices.

## 26.24 PICDEM USB PIC16C7X5 Demonstration Board

The PICDEM USB Demonstration Board shows off the capabilities of the PIC16C745 and PIC16C765 USB microcontrollers. This board provides the basis for future USB products.

## 26.25 Evaluation and Programming Tools

In addition to the PICDEM series of circuits, Microchip has a line of evaluation kits and demonstration software for these products.

- KEELOQ evaluation and programming tools for Microchip's HCS Secure Data Products
- CAN developers kit for automotive network applications
- Analog design boards and filter design software
- PowerSmart battery charging evaluation/ calibration kits
- IrDA® development kit
- microID development and rfLab<sup>TM</sup> development software
- SEEVAL® designer kit for memory evaluation and endurance calculations
- PICDEM MSC demo boards for Switching mode power supply, high-power IR driver, delta sigma ADC and flow rate sensor

Check the Microchip web page and the latest Product Selector Guide for the complete list of demonstration and evaluation kits.

NOTES:

### 27.0 ELECTRICAL CHARACTERISTICS


## Absolute Maximum Ratings(†)

Ambient temperature under bias	
Storage temperature	65°C to +150°C
Voltage on any pin with respect to Vss (except VDD, MCLR and RA4)	0.3V to (VDD + 0.3V)
Voltage on VDD with respect to Vss	0.3V to +7.5V
Voltage on MCLR with respect to Vss (Note 2)	0V to +13.25V
Voltage on RA4 with respect to Vss	0V to +8.5V
Total power dissipation (Note 1)	1.0W
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Input clamp current, IiK (VI < 0 or VI > VDD)	±20 mA
Output clamp current, lok (Vo < 0 or Vo > VDD)	±20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by all ports (combined)	200 mA
Maximum current sourced by all ports (combined)	200 mA

- **Note 1:** Power dissipation is calculated as follows: Pdis = VDD x {IDD  $\Sigma$  IOH} +  $\Sigma$  {(VDD VOH) x IOH} +  $\Sigma$ (VOL x IOL)
  - 2: Voltage spikes below Vss at the  $\overline{\text{MCLR}}/\text{VPP}$  pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100 $\Omega$  should be used when applying a "low" level to the  $\overline{\text{MCLR}}/\text{VPP}$  pin rather than pulling this pin directly to Vss.

**Note:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.











FIGURE 27-3: PIC18LFXX8 VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)



FMAX = (16.36 MHz/V) (VDDAPPMIN -2.0V) + 4 MHz, if VDDAPPMIN  $\le 4.2V = 40$  MHz, if VDDAPPMIN > 4.2V **Note:** VDDAPPMIN is the minimum voltage of the PICmicro<sup>®</sup> device in the application.

#### 27.1 DC Characteristics

PIC18LI (Indus				lard O <sub>l</sub>			ditions (unless otherwise stated) -40°C ≤ Ta ≤ +85°C for industrial
PIC18FXX8 (Industrial, Extended)				dard O ating te	-	ture -	ditions (unless otherwise stated) $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended
Param No.	Symbol	Characteristic/ Device	Min	Min Typ Max Units Conditions			
	VDD	Supply Voltage					
D001		PIC18LFXX8	2.0	_	5.5	V	HS, XT, RC and LP Oscillator modes
D001		PIC18FXX8	4.2		5.5	V	
D002	VDR	RAM Data Retention Voltage <sup>(1)</sup>	1.5	-	_	V	
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	_		0.7	V	See section on Power-on Reset for details
D004	SVDD	VDD Rise Rate to ensure internal Power-on Reset signal	0.05		_	V/ms	See section on Power-on Reset for details
	VBOR	Brown-out Reset Voltag	е				
		PIC18LFXX8					
D005		BORV1:BORV0 = 11	1.96	_	2.16	V	
		BORV1:BORV0 = 10	2.64	_	2.92	V	
		BORV1:BORV0 = 01	4.07	_	4.59	V	
		BORV1:BORV0 = 00	4.36	_	4.92	V	
		PIC18FXX8					
D005		BORV1:BORV0 = 1x	N.A.	_	N.A.	V	Not in operating voltage range of device
		BORV1:BORV0 = 01	4.07		4.59	V	
		BORV1:BORV0 = 00	4.36	_	4.92	V	

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD MCLR = VDD; WDT enabled/disabled as specified.

- 3: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- **4:** For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

### 27.1 DC Characteristics (Continued)

PIC18LFXX8 (Industrial)				lard O <sub>l</sub>			ditions (unless otherwise stated) -40°C ≤ Ta ≤ +85°C for industrial
PIC18FX (Indus	XX8 trial, Exter	nded)		dard O ating te		ture -	nditions (unless otherwise stated) $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended
Param No.	Symbol	Characteristic/ Device	Min	Тур	Max	Units	Conditions
	IDD	Supply Current <sup>(2,3,4)</sup>					
D010		PIC18LFXX8		.7 .7 1.7 1 1 2.5 .7 .7	2 2 4 2.5 2.5 5 2.5 5	mA mA mA mA mA mA	XT oscillator configuration  VDD = 2.0V, +25°C, FoSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FoSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FoSC = 4 MHz  RC oscillator configuration  VDD = 2.0V, +25°C, FoSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FoSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FoSC = 4 MHz  RCIO oscillator configuration  VDD = 2.0V, +25°C, FoSC = 4 MHz  RCIO oscillator configuration  VDD = 2.0V, +25°C, FoSC = 4 MHz  VDD = 2.0V, -40°C to +85°C, FoSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FoSC = 4 MHz
D010		PIC18FXX8		1.7 1.7 1.7 1.7 2.5 2.5 2.5 1.8 1.8	4 4 4 5 5 6 4 5 5	mA mA mA mA mA mA mA	XT oscillator configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz  RC oscillator configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz  RCIO oscillator configuration  VDD = 4.2V, +25°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +85°C, FOSC = 4 MHz  VDD = 4.2V, -40°C to +125°C, FOSC = 4 MHz
D010A		PIC18LFXX8	_	18	40	μΑ	LP oscillator, Fosc = 32 kHz, WDT disabled VDD = 2.0V, -40°C to +85°C
D010A		PIC18FXX8		60 60	150 180	μ <b>Α</b> μ <b>Α</b>	LP oscillator, Fosc = 32 kHz, WDT disabled VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C

**Legend:** Rows are shaded for improved readability.

- Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

- OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD MCLR = VDD; WDT enabled/disabled as specified.
- 3: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- **4:** For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The \( \Delta \text{BOR} \) and \( \Delta \text{LVD} \) currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

### 27.1 DC Characteristics (Continued)

PIC18LFXX8 (Industrial)				lard O		_	ditions (unless otherwise stated) -40°C ≤ Ta ≤ +85°C for industrial		
PIC18FXX8 (Industrial, Extended)				Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \leq \text{Ta} \leq +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \leq \text{Ta} \leq +125^{\circ}\text{C}$ for extended					
Param No.	Symbol	Characteristic/ Device	Min	Min Typ Max Units Conditions					
	IDD	Supply Current <sup>(2,3,4)</sup>							
D010C		PIC18LFXX8	_	21	28	mA	EC, ECIO oscillator configurations VDD = 4.2V, -40°C to +85°C		
D010C		PIC18FXX8		21	30	mA	EC, ECIO oscillator configurations VDD = 4.2V, -40°C to +125°C, FOSC = 25 MHz		
D013		PIC18LFXX8		1.3 18 28	3 28 40	mA mA	HS oscillator configurations FOSC = 6 MHz, VDD = 2.0V FOSC = 25 MHz, VDD = 5.5V HS + PLL osc configuration FOSC = 10 MHz, VDD = 5.5V		
D013		PIC18FXX8	_ _	18 28	28 40	mA mA	HS oscillator configurations FOSC = 25 MHz, VDD = 5.5V HS + PLL osc configuration FOSC = 10 MHz, VDD = 5.5V		
D014		PIC18LFXX8	_	32	65	μΑ	Timer1 oscillator configuration FOSC = 32 kHz, VDD = 2.0V		
D014		PIC18FXX8	_ _	62 62	250 310	μ <b>Α</b> μ <b>Α</b>	Timer1 oscillator configuration FOSC = 32 kHz, VDD = 4.2V, -40°C to +85°C FOSC = 32 kHz, VDD = 4.2V, -40°C to +125°C		
	IPD	Power-Down Current <sup>(3)</sup>							
D020		PIC18LFXX8	<u> </u>	0.3 2	4 10	μ <b>Α</b> μ <b>Α</b>	VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C		
D020 D021B		PIC18FXX8	_	2 6	10 40	μ <b>Α</b> μ <b>Α</b>	VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C		

Legend: Rows are shaded for improved readability.

- Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD MCLR = VDD; WDT enabled/disabled as specified.

- **3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- **4:** For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

## 27.1 DC Characteristics (Continued)

	PIC18LFXX8 (Industrial)				<b>peratir</b> mpera	-	ditions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial				
	PIC18FXX8 (Industrial, Extended)			dard O ating te		ture -	nditions (unless otherwise stated) $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended				
Param No.	Symbol	Characteristic/ Device	Min	Min Typ Max Units Conditions			Conditions				
	$\Delta IWDT$	Module Differential Cur	rrent								
D022		Watchdog Timer PIC18LFXX8		0.75 0.8 7	1.5 8 25	μΑ μΑ μΑ	VDD = 2.5V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C				
D022		Watchdog Timer PIC18FXX8		7 7 7	25 25 45	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C				
D022A	Δlbor	Brown-out Reset <sup>(5)</sup> PIC18LFXX8		38 42 49	50 55 65	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C				
D022A		Brown-out Reset <sup>(5)</sup> PIC18FXX8		46 49 50	65 65 75	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C				
D022B	Δllvd	Low-Voltage Detect <sup>(5)</sup> PIC18LFXX8		36 40 47	50 55 65	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C				
D022B		Low-Voltage Detect <sup>(5)</sup> PIC18FXX8		44 47 47	65 65 75	μ <b>Α</b> μ <b>Α</b> μ <b>Α</b>	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C				
D025	ΔlTMR1	Timer1 Oscillator PIC18LFXX8		6.2 6.2 7.5	40 45 55	μ <b>Α</b> μ <b>Α</b> μ <b>Α</b>	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C				
D025		Timer1 Oscillator PIC18FXX8	_ _ _	7.5 7.5 7.5	55 55 65	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C				

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

- 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
  - The test conditions for all IDD measurements in active operation mode are:
    - $\overline{OSC1}$  = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD  $\overline{MCLR}$  = VDD; WDT enabled/disabled as specified.
- **3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- **4:** For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The ΔIBOR and ΔILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

## 27.2 DC Characteristics: PIC18FXX8 (Industrial, Extended) PIC18LFXX8 (Industrial)

DC CHARACTERISTICS			Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended				
Param No.	Symbol	Characteristic/ Device	Min	Min Max L		Conditions	
	VIL	Input Low Voltage					
		I/O ports:					
D030		with TTL buffer	Vss	0.15 VDD	V	VDD < 4.5V	
D030A			_	0.8	V	$4.5V \le VDD \le 5.5V$	
D031		with Schmitt Trigger buffer RC3 and RC4	Vss Vss	0.2 VDD 0.3 VDD	V V		
D032		MCLR	Vss	0.2 VDD	V		
D032A		OSC1 (in XT, HS and LP modes) and T1OSI	Vss	0.3 VDD	V		
D033		OSC1 (in RC mode) <sup>(1)</sup>	Vss	0.2 VDD	V		
	VIH	Input High Voltage					
		I/O ports:					
D040		with TTL buffer	0.25 VDD + 0.8V	VDD	V	VDD < 4.5V	
D040A			2.0	VDD	V	$4.5V \le VDD \le 5.5V$	
D041		with Schmitt Trigger buffer RC3 and RC4	0.8 VDD 0.7 VDD	Vdd Vdd	V V		
D042		MCLR	0.8 VDD	VDD	V		
D042A		OSC1 (in XT, HS and LP modes) and T1OSI	0.7 VDD	VDD	V		
D043		OSC1 (RC mode) <sup>(1)</sup>	0.9 VDD	VDD	V		
	lıL	Input Leakage Current <sup>(2,3)</sup>					
D060		I/O ports	_	±1	μΑ	Vss ≤ VPIN ≤ VDD, Pin at high-impedance	
D061		MCLR	_	±5	μΑ	Vss ≤ Vpin ≤ Vdd	
D063		OSC1	_	±5	μ <b>Α</b>	$Vss \le VPIN \le VDD$	
	IPU	Weak Pull-up Current					
D070	IPURB	PORTB weak pull-up current	50	450	μΑ	VDD = 5V, VPIN = VSS	

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro® device be driven with an external clock while in RC mode.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

**<sup>3:</sup>** Negative current is defined as current sourced by the pin.

## 27.2 DC Characteristics: PIC18FXX8 (Industrial, Extended) PIC18LFXX8 (Industrial) (Continued)

DC CH	ARACTE	RISTICS	Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended					
Param No.	Symbol	Characteristic/ Device	Min	Max	Units	Conditions		
	Vol	Output Low Voltage						
D080		I/O ports	_	0.6	V	IOL = $8.5 \text{ mA}$ , VDD = $4.2 \text{V}$ , $-40^{\circ}\text{C}$ to $+85^{\circ}\text{C}$		
D080A			_	0.6	V	IOL = $7.0 \text{ mA}$ , VDD = $4.2 \text{V}$ , $-40^{\circ}\text{C}$ to $+125^{\circ}\text{C}$		
D083		OSC2/CLKO (RC mode)	_	0.6	V	IOL = 1.6 mA, VDD = 4.2V, -40°C to +85°C		
D083A			_	0.6	V	IOL = 1.2 mA, VDD = 4.2V, -40°C to +125°C		
	Vон	Output High Voltage <sup>(3)</sup>						
D090		I/O ports	VDD - 0.7	_	V	IOH = $-3.0$ mA, VDD = $4.2$ V, $-40$ °C to $+85$ °C		
D090A			VDD - 0.7	_	V	IOH = -2.5 mA, VDD = 4.2V, -40°C to +125°C		
D092		OSC2/CLKO (RC mode)	VDD - 0.7	_	V	IOH = -1.3 mA, VDD = 4.2V, -40°C to +85°C		
D092A			VDD - 0.7	_	V	IOH = -1.0 mA, VDD = 4.2V, -40°C to +125°C		
D150	Vod	Open-Drain High Voltage	_	7.5	V	RA4 pin		
		Capacitive Loading Specs on Output Pins						
D101	Cio	All I/O pins and OSC2 (in RC mode)	_	50	pF	To meet the AC Timing Specifications		
D102	Св	SCL, SDA	_	400	pF	In I <sup>2</sup> C™ mode		

- **Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro® device be driven with an external clock while in RC mode.
  - 2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
  - 3: Negative current is defined as current sourced by the pin.

FIGURE 27-4: LOW-VOLTAGE DETECT CHARACTERISTICS




TABLE 27-1: LOW-VOLTAGE DETECT CHARACTERISTICS

		Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended						
Param No.	Symbol	Characteristi	c	Min	Тур	Max	Units	Conditions
D420	VLVD	LVD Voltage	LVV = 0001	1.96	2.06	2.16	V	T ≥ 25°C
			LVV = 0010	2.16	2.27	2.38	V	T ≥ 25°C
			LVV = 0011	2.35	2.47	2.59	V	T ≥ 25°C
			LVV = 0100	2.43	2.58	2.69	V	
			LVV = 0101	2.64	2.78	2.92	V	
			LVV = 0110	2.75	2.89	3.03	V	
			LVV = 0111	2.95	3.1	3.26	V	
			LVV = 1000	3.24	3.41	3.58	V	
			LVV = 1001	3.43	3.61	3.79	V	
			LVV = 1010	3.53	3.72	3.91	V	
			LVV = 1011	3.72	3.92	4.12	V	
			LVV = 1100	3.92	4.13	4.34	V	
			LVV = 1101	4.07	4.33	4.59	V	
			LVV = 1110	4.36	4.64	4.92	V	

TABLE 27-2: DC CHARACTERISTICS: EEPROM AND ENHANCED FLASH

DC Chai	racterist	tics	Standard Operating Conditions						
Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions		
		Internal Program Memory Programming Specifications							
D110	VPP	Voltage on MCLR/VPP pin	9.00	_	13.25	٧			
D113	IDDP	Supply Current during Programming	_	_	10	mA			
		Data EEPROM Memory							
D120	ED	Cell Endurance	100K	1M	_	E/W	-40°C to +85°C		
D120A	ED	Byte Endurance	10K	100K	_	E/W	+85°C to +125°C		
D121	VDRW	VDD for Read/Write	VMIN	_	5.5	V	Using EECON to read/write VMIN = Minimum operating voltage		
D122	TDEW	Erase/Write Cycle Time	_	4	_	ms			
D123	TRETD	Characteristic Retention	40	_	-	Year	Provided no other specifications are violated		
D124	TREF	Number of Total Erase/Write Cycles to Data EEPROM before Refresh*	1M	10M	_	Cycles	-40°C to +85°C		
D124A	TREF	Number of Total Erase/Write Cycles before Refresh*	100K	1M	_	Cycles	+85°C to +125°C		
		Program Flash Memory							
D130	EР	Cell Endurance	10K	100K	_	E/W	-40°C to +85°C		
D130A	EР	Cell Endurance	1000	10K	_	E/W	+85°C to +125°C		
D131	VPR	VDD for Read	VMIN	_	5.5	٧	VMIN = Minimum operating voltage		
D132	VIE	VDD for Block Erase	4.5	_	5.5	V	Using ICSP™ port		
D132A	Viw	VDD for Externally Timed Erase or Write	4.5	_	5.5	V	Using ICSP port		
D132B	VPEW	VDD for Self-Timed Write	VMIN	_	5.5	٧	VMIN = Minimum operating voltage		
D133	TIE	ICSP Erase Cycle Time	_	4	_	ms	VDD ≥ 4.5V		
D133A	Tıw	ICSP Erase or Write Cycle Time (externally timed)	1	_	-	ms	VDD ≥ 4.5V		
D133A	Tıw	Self-Timed Write Cycle Time	_	2	_	ms			
D134	TRETD	Characteristic Retention	40	_		Year	Provided no other specifications are violated		

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>\*</sup> See **Section 5.8 "Using the Data EEPROM"** for more information.

### TABLE 27-3: COMPARATOR SPECIFICATIONS

Operating Conditions: VDD range as described in Section 27.1 "DC Characteristics", -40°C < TA < +125°C **Param Characteristics** Min Units Comments Sym Тур Max No. D300 Vioff Input Offset Voltage ±5.0 ±10 mV D301 Vісм Input Common Mode Voltage 0 VDD - 1.5٧ D302 CMRR **CMRR** +55\* db Response Time(1) D300 TRESP 300\* 400\* PIC18FXX8 ns 350\* 600\* PIC18LFXX8 ns D301 TMC2OV Comparator Mode Change to 10\* μs Output Valid

Note 1: Response time measured with one comparator input at (VDD – 1.5)/2 while the other input transitions from Vss to VDD.

#### TABLE 27-4: VOLTAGE REFERENCE SPECIFICATIONS

<b>Operating Conditions:</b> VDD range as described in <b>Section 27.1 "DC Characteristics"</b> , -40°C < TA < +125°C							
Param No.	Sym	Characteristics	Min	Тур	Max	Units	Comments
D310	VRES	Resolution	VDD/24	_	VDD/32	LSB	
D311	VRAA	Absolute Accuracy	_	_	0.5	LSB	
D312	VRUR	Unit Resistor Value (R)	_	2K*	_	Ω	
D310	TSET	Settling Time <sup>(1)</sup>	_	_	10*	μs	

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** Settling time measured while CVRR = 1 and CVR<3:0> transitions from 0000 to 1111.

<sup>\*</sup> These parameters are characterized but not tested.

## 27.3 AC (Timing) Characteristics

## 27.3.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created using one of the following formats:

1. TppS2pp	S	3. Tcc:st	(I <sup>2</sup> C specifications only)
2. TppS		4. Ts	(I <sup>2</sup> C specifications only)
Т			
F	Frequency	Т	Time
Lowercase	letters (pp) and their meanings:		
рр			
СС	CCP1	osc	OSC1
ck	CLKO	rd	RD
cs	CS	rw	RD or WR
di	SDI	SC	SCK
do	SDO	SS	SS
dt	Data in	t0	TOCKI
io	I/O port	t1	T1CKI
mc	MCLR	wr	WR
Uppercase	letters and their meanings:		
S			
F	Fall	Р	Period
Н	High	R	Rise
1	Invalid (High-Impedance)	V	Valid
L	Low	Z	High-Impedance
I <sup>2</sup> C only			
AA	output access	High	High
BUF	Bus free	Low	Low
Tcc:st (I <sup>2</sup> C	specifications only)		
CC			
HD	Hold	SU	Setup
ST			
DAT	DATA input hold	STO	Stop condition
STA	Start condition		


### 27.3.2 TIMING CONDITIONS

The temperature and voltages specified in Table 27-5 apply to all timing specifications unless otherwise noted. Figure 27-5 specifies the load conditions for the timing specifications.

TABLE 27-5: TEMPERATURE AND VOLTAGE SPECIFICATIONS – AC

	Standard Operating Conditions (unless otherwise stated)			
	Operating temperature -40°C ≤ Ta ≤ +85°C for industrial			
AC CHARACTERISTICS	-40°C ≤ Ta ≤ +125°C for extended			
AC CHARACTERISTICS	Operating voltage VDD range as described in DC specification,			
	Section 27.1 "DC Characteristics".			
	LF parts operate for industrial temperatures only.			

### FIGURE 27-5: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



### 27.3.3 TIMING DIAGRAMS AND SPECIFICATIONS

### FIGURE 27-6: EXTERNAL CLOCK TIMING




TABLE 27-6: EXTERNAL CLOCK TIMING REQUIREMENTS

		EXTERNAL CLOCK TIME			1	
Param No.	Symbol	Characteristic	Min	Max	Units	Conditions
1A	Fosc	External CLKI Frequency <sup>(1)</sup>	DC	40	MHz	EC, ECIO oscillator, -40°C to +85°C
		Oscillator Frequency <sup>(1)</sup>	DC	25	MHz	EC, ECIO oscillator, +85°C to +125°C
			DC	4	MHz	RC oscillator
			0.1	4	MHz	XT oscillator
			4	25	MHz	HS oscillator, -40°C to +85°C
			4	25	MHz	HS oscillator, +85°C to +125°C
			4	10	MHz	HS + PLL oscillator, -40°C to +85°C
			4	6.25	MHz	HS + PLL oscillator, +85°C to +125°C
			DC	200	kHz	LP oscillator
1	Tosc	External CLKI Period <sup>(1)</sup>	25	_	ns	EC, ECIO oscillator, -40°C to +85°C
		Oscillator Period <sup>(1)</sup>	40	_	ns	EC, ECIO oscillator, +85°C to +125°C
			250	_	ns	RC oscillator
			250	10,000	ns	XT oscillator
			40	_	ns	HS oscillator, -40°C to +85°C
			40	_	ns	HS oscillator, +85°C to +125°C
			100	250	ns	HS + PLL oscillator, -40°C to +85°C
			160	250	ns	HS + PLL oscillator, +85°C to +125°C
			5	200	μs	LP oscillator
2	TCY	Instruction Cycle Time <sup>(1)</sup>	100 160	_	ns ns	TCY = $4/F$ OSC, $-40$ °C to $+85$ °C TCY = $4/F$ OSC, $+85$ °C to $+125$ °C
3	TosL,	External Clock in (OSC1)	30	_	ns	XT oscillator
	TosH	High or Low Time	2.5	_	ns	LP oscillator
			10	_	μs	HS oscillator
4	TosR,	External Clock in (OSC1)	_	20	ns	XT oscillator
	TosF	Rise or Fall Time	_	50	ns	LP oscillator
				7.5	ns	HS oscillator

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "Min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "Max." cycle time limit is "DC" (no clock) for all devices.

TABLE 27-7: PLL CLOCK TIMING SPECIFICATIONS (VDD = 4.2 TO 5.5V)

Param No. Sym		Characteristic	Min	Typ†	Max	Units	Conditions
_	Fosc	Oscillator Frequency Range	4		10	MHz	HS mode only
_	Fsys	On-Chip VCO System Frequency	16	_	40	MHz	HS mode only
_	t <sub>rc</sub>	PLL Start-up Time (Lock Time)	_	_	2	ms	
_	$\Delta$ CLK	CLKO Stability (Jitter)	-2	_	+2	%	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 27-7: CLKO AND I/O TIMING




TABLE 27-8: CLKO AND I/O TIMING REQUIREMENTS

Param No.	Symbol	Characteristic		Min	Тур	Max	Units	Conditions
10	TosH2ckL	OSC1 ↑ to CLKO ↓		_	75	200	ns	(1)
11	TosH2ckH	OSC1 ↑ to CLKO ↑		_	75	200	ns	(1)
12	TckR	CLKO Rise Time		_	35	100	ns	(1)
13	TckF	CLKO Fall Time		_	35	100	ns	(1)
14	TckL2ioV	CLKO ↓ to Port Out Valid		_	_	0.5 Tcy + 20	ns	(1)
15	TioV2ckH	Port In Valid before CLKO ↑		0.25 Tcy + 25	_	_	ns	(1)
16	TckH2iol	Port In Hold after CLKO ↑		0	_	_	ns	(1)
17	TosH2ioV	OSC1 ↑ (Q1 cycle) to Port Ou	t Valid	_	50	150	ns	
18	TosH2ioI	OSC1 ↑ (Q2 cycle) to Port	PIC18FXX8	100	_	_	ns	
18A		Input Invalid (I/O in hold time)	PIC18 <b>LF</b> XX8	200	_	_	ns	
19	TioV2osH	Port Input Valid to OSC1 ↑ (I/O	in setup time)	0	_	_	ns	
20	TioR	Port Output Rise Time	PIC18FXX8	_	10	25	ns	
20A			PIC18 <b>LF</b> XX8	_	_	60	ns	
21	TioF	Port Output Fall Time	PIC18FXX8	_	10	25	ns	
21A			PIC18 <b>LF</b> XX8	_	_	60	ns	
22†	TINP	INT pin High or Low Time	•	Tcy	_	_	ns	
23†	TRBP	RB7:RB4 Change INT High or Low Time		Tcy	_	_	ns	
24†	TRCP	RC7:RC4 Change INT High or	r Low Time	20	_	_	ns	

<sup>†</sup> These parameters are asynchronous events not related to any internal clock edges.

Note 1: Measurements are taken in RC mode where CLKO pin output is 4 x Tosc.

FIGURE 27-8: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 27-9: BROWN-OUT RESET AND LOW-VOLTAGE DETECT TIMING




TABLE 27-9: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER, BROWN-OUT RESET AND LOW-VOLTAGE DETECT REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
30	TmcL	MCLR Pulse Width (low)	2	_	_	μs	
31	TWDT	Watchdog Timer Time-out Period (no prescaler)	7	18	33	ms	
32	Tost	Oscillation Start-up Timer Period	1024 Tosc	_	1024 Tosc	_	Tosc = OSC1 period
33	TPWRT	Power-up Timer Period	28	72	132	ms	
34	Tioz	I/O High-Impedance from MCLR Low or Watchdog Timer Reset	_	2	_	μs	
35	TBOR	Brown-out Reset Pulse Width	200	_	_	μs	For VDD ≤ BVDD (see D005)
36	TIRVST	Time for Internal Reference Voltage to become stable	_	20	50	μs	
37	TLVD	Low-Voltage Detect Pulse Width	200	_	_	μs	For VDD ≤ VLVD (see D420)

FIGURE 27-10: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS




TABLE 27-10: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

Param No.	Symbol		Characteristic	c	Min	Max	Units	Conditions
40	Tt0H	T0CKI High I	Pulse Width	No prescaler	0.5 Tcy + 20	_	ns	
				With prescaler	10	_	ns	
41	Tt0L	T0CKI Low F	Pulse Width	No prescaler	0.5 Tcy + 20	_	ns	
				With prescaler	10	_	ns	
42	Tt0P	T0CKI Period	d	No prescaler	Tcy + 10	_	ns	
				With prescaler	Greater of: 20 ns or <u>Tcy + 40</u> N	_	ns	N = prescale value (1, 2, 4,, 256)
45	Tt1H	T1CKI	Synchronous, r	no prescaler	0.5 Tcy + 20	_	ns	
		High Time	Synchronous,	PIC18FXX8	10	_	ns	
			with prescaler	PIC18 <b>LF</b> XX8	25	_	ns	
			Asynchronous	PIC18FXX8	30	_	ns	
				PIC18 <b>LF</b> XX8	50	_	ns	
46	Tt1L	T1CKI	Synchronous, r	no prescaler	0.5 Tcy + 5	_	ns	
		Low Time	Synchronous,	PIC18FXX8	10	_	ns	
			with prescaler	PIC18 <b>LF</b> XX8	25	_	ns	
			Asynchronous	PIC18FXX8	30	_	ns	
				PIC18 <b>LF</b> XX8	TBD	TBD	ns	
47	Tt1P	T1CKI Input Period	Synchronous		Greater of: 20 ns or <u>TCY + 40</u> N	_	ns	N = prescale value (1, 2, 4, 8)
			Asynchronous		60	_	ns	
	Ft1	T1CKI Oscilla	ator Input Frequency Range		DC	50	kHz	
48	Tcke2tmrl	Delay from E Timer Increm	xternal T1CKI C nent	Clock Edge to	2 Tosc	7 Tosc	_	

**Legend:** TBD = To Be Determined

FIGURE 27-11: CAPTURE/COMPARE/PWM TIMINGS (CCP1 AND ECCP1)




TABLE 27-11: CAPTURE/COMPARE/PWM REQUIREMENTS (CCP1 AND ECCP1)

Param No.	Symbol	Chara	acteristic		Min	Max	Units	Conditions
50	TccL	CCPx Input Low Time	No prescal	er	0.5 Tcy + 20	_	ns	
			With	PIC18FXX8	10	_	ns	
			prescaler	PIC18 <b>LF</b> XX8	20	_	ns	
51	TccH	CCPx Input High Time	No prescal	er	0.5 Tcy + 20	_	ns	
			With	PIC18FXX8	10	_	ns	
			prescaler	PIC18 <b>LF</b> XX8	20	_	ns	
52	TccP	CCPx Input Period			3 TCY + 40 N	_	ns	N = prescale value (1, 4 or 16)
53	TccR	CCPx Output Fall Time	)	PIC18FXX8	_	25	ns	
				PIC18 <b>LF</b> XX8		45	ns	
54	TccF	CCPx Output Fall Time	9	PIC18FXX8	_	25	ns	
				PIC18 <b>LF</b> XX8	_	45	ns	

FIGURE 27-12: PARALLEL SLAVE PORT TIMING (PIC18F248 AND PIC18F458)




TABLE 27-12: PARALLEL SLAVE PORT REQUIREMENTS (PIC18F248 AND PIC18F458)

Param No.	Symbol	Characteristic			Max	Units	Conditions
62	TdtV2wrH	Data-In Valid before WR ↑ or Constitution (setup time)	Pata-In Valid before WR ↑ or CS ↑ Setup time)			ns ns	Extended Temp. range
63	TwrH2dtl	$\overline{WR} \uparrow or  \overline{CS} \uparrow to  Data-In  Invalid$	PIC18FXX8	20	_	ns	
		(hold time)	PIC18 <b>LF</b> XX8	35	_	ns	
64	TrdL2dtV	RD ↓ and CS ↓ to Data-Out Val	id	_	80	ns	
				_	90	ns	Extended Temp. range
65	TrdH2dtl	RD ↑ or CS ↓ to Data-Out Invalid		10	30	ns	
66	TibfINH	Inhibit the IBF flag bit being cleared from WR ↑ or CS ↑		_	3 Tcy	ns	





FIGURE 27-13: EXAMPLE SPI™ MASTER MODE TIMING (CKE = 0)

TABLE 27-13: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 0)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS ↓ to SCK ↓ or SCK ↑ Input		Tcy	_	ns	
71	TscH	SCK Input High Time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK Input Low Time	Continuous	1.25 Tcy + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input	to SCK Edge	100	_	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the of Byte 2	e 1st Clock Edge	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to	SCK Edge	100	_	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8	_	45	ns	
76	TdoF	SDO Data Output Fall Time		_	25	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8	_	25	ns	
		(Master mode)	laster mode) PIC18 <b>LF</b> XX8		45	ns	
79	TscF	SCK Output Fall Time (Master mode)		_	25	ns	
80	TscH2doV,	SDO Data Output Valid after PIC18FXX8		_	50	ns	
	TscL2doV	SCK Edge	PIC18 <b>LF</b> XX8	_	100	ns	



**EXAMPLE SPI™ MASTER MODE TIMING (CKE = 1)** FIGURE 27-14:

TABLE 27-14: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 1)

Param No.	Symbol	Characterist	Characteristic		Max	Units	Conditions
71	TscH	SCK Input High Time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK Input Low Time	Continuous	1.25 Tcy + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input	to SCK Edge	100	_	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to to f Byte 2	he 1st Clock Edge	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to	o SCK Edge	100	_	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8	_	45	ns	
76	TdoF	SDO Data Output Fall Time		_	25	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8	_	25	ns	
		(Master mode)	PIC18 <b>LF</b> XX8	_	45	ns	
79	TscF	SCK Output Fall Time (Master	utput Fall Time (Master mode)		25	ns	
80	TscH2doV,	SDO Data Output Valid after			50	ns	
	TscL2doV	SCK Edge	PIC18 <b>LF</b> XX8		100	ns	
81	TdoV2scH, TdoV2scL	SDO Data Output Setup to SCK Edge		Tcy	_	ns	





FIGURE 27-15: EXAMPLE SPI<sup>TM</sup> SLAVE MODE TIMING (CKE = 0)

TABLE 27-15: EXAMPLE SPI™ MODE REQUIREMENTS, SLAVE MODE TIMING (CKE = 0)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS ↓ to SCK ↓ or SCK ↑ Input		Tcy	_	ns	
71	TscH	SCK Input High Time (Slave mode)	Continuous	1.25 Tcy + 30	_	ns	
71A			Single Byte	40	_	ns	(Note 1)
72	TscL	SCK Input Low Time (Slave mode)	Continuous	1.25 Tcy + 30	_	ns	
72A			Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input to SCK I	Edge	100	_	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st Cloc	k Edge of Byte 2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to SCK Ed	dge	100		ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8		45	ns	
76	TdoF	SDO Data Output Fall Time		_	25	ns	
77	TssH2doZ	SS ↑ to SDO Output High-Impedance		10	50	ns	
78	TscR	SCK Output Rise Time (Master mode)	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8		45	ns	
79	TscF	SCK Output Fall Time (Master mode)	tput Fall Time (Master mode)		25	ns	
80	TscH2doV,	SDO Data Output Valid after SCK	PIC18FXX8	_	50	ns	
	TscL2doV	Edge	PIC18 <b>LF</b> XX8		100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK Edge		1.5 Tcy + 40	_	ns	



**EXAMPLE SPI™ SLAVE MODE TIMING (CKE = 1)** FIGURE 27-16:

TABLE 27-16: EXAMPLE SPI™ SLAVE MODE REQUIREMENTS (CKE = 1)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS ↓ to SCK ↓ or SCK ↑ Input	SCK ↓ or SCK ↑ Input			ns	
71	TscH	SCK Input High Time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
72	TscL	SCK Input Low Time	Continuous	1.25 Tcy + 30	_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st Cl	ock Edge of Byte 2	1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to SCK E	Edge	100	_	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8	_	45	ns	
76	TdoF	SDO Data Output Fall Time		_	25	ns	
77	TssH2doZ	$\overline{SS} \uparrow$ to SDO Output High-Impedance		10	50	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8	_	25	ns	
		(Master mode)	PIC18 <b>LF</b> XX8	_	45	ns	
79	TscF	SCK Output Fall Time (Master mode)	•	_	25	ns	
80	TscH2doV,	SDO Data Output Valid after SCK	PIC18FXX8	_	50	ns	
	TscL2doV	Edge	PIC18 <b>LF</b> XX8	_	100	ns	
82	TssL2doV	SDO Data Output Valid after SS ↓	PIC18FXX8	_	50	ns	
		Edge	PIC18 <b>LF</b> XX8	_	100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK Edge		1.5 Tcy + 40	_	ns	

FIGURE 27-17: I<sup>2</sup>C™ BUS START/STOP BITS TIMING




TABLE 27-17: I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS (SLAVE MODE)

	ND-12-17-17-16-18-18-18-18-18-18-18-18-18-18-18-18-18-										
Param No.	Symbol	Characte	ristic	Min	Max	Units	Conditions				
90	Tsu:sta	Start Condition	100 kHz mode	4700	_	ns	Only relevant for Repeated				
		Setup Time	400 kHz mode	600	_		Start condition				
91	THD:STA	Start Condition	100 kHz mode	4000	_	ns	After this period, the first				
		Hold Time	400 kHz mode	600	_		clock pulse is generated				
92	Tsu:sto	Stop Condition	100 kHz mode	4700	_	ns					
		Setup Time	400 kHz mode	600	_						
93	THD:STO	Stop Condition	100 kHz mode	4000	_	ns					
		Hold Time	400 kHz mode	600	_						

FIGURE 27-18: I<sup>2</sup>C™ BUS DATA TIMING




TABLE 27-18: I<sup>2</sup>C™ BUS DATA REQUIREMENTS (SLAVE MODE)

Param No.	Symbol	Characte	eristic	Min	Max	Units	Conditions
100	THIGH	Clock High Time	100 kHz mode	4.0	_	μs	PIC18FXX8 must operate at a minimum of 1.5 MHz
			400 kHz mode	0.6	-	μs	PIC18FXX8 must operate at a minimum of 10 MHz
			SSP Module	1.5 TcY	-		
101	TLOW	Clock Low Time	100 kHz mode	4.7	l	μs	PIC18FXX8 must operate at a minimum of 1.5 MHz
			400 kHz mode	1.3		μS	PIC18FXX8 must operate at a minimum of 10 MHz
			SSP module	1.5 TcY	_	ns	
102	TR	SDA and SCL Rise	100 kHz mode	_	1000	ns	
		Time	400 kHz mode	20 + 0.1 CB	300	ns	CB is specified to be from 10 to 400 pF
103	TF	SDA and SCL Fall	100 kHz mode		300	ns	
		Time	400 kHz mode	20 + 0.1 CB	300	ns	CB is specified to be from 10 to 400 pF
90	Tsu:sta	Start Condition	100 kHz mode	4.7	-	μs	Only relevant for Repeated
		Setup Time	400 kHz mode	0.6		μs	Start condition
91	THD:STA	Start Condition	100 kHz mode	4.0	_	μs	After this period the first
		Hold Time	400 kHz mode	0.6	_	μs	clock pulse is generated
106	THD:DAT	Data Input Hold	100 kHz mode	0	_	ns	
		Time	400 kHz mode	0	0.9	μs	
107	TSU:DAT	Data Input Setup	100 kHz mode	250	_	ns	(Note 2)
		Time	400 kHz mode	100	_	ns	
92	Tsu:sto	Stop Condition	100 kHz mode	4.7	_	μs	
		Setup Time	400 kHz mode	0.6	_	μs	
109	TAA	Output Valid from	100 kHz mode	_	3500	ns	(Note 1)
		Clock	400 kHz mode	_	_	ns	
110	TBUF	Bus Free Time	100 kHz mode	4.7	_	μs	Time the bus must be free
			400 kHz mode	1.3	_	μs	before a new transmission can start
D102	Св	Bus Capacitive Load	ding	_	400	pF	

**Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.

<sup>2:</sup> A Fast mode I<sup>2</sup>C™ bus device can be used in a Standard mode I<sup>2</sup>C bus system, but the requirement TSU;DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line.

Before the SCL line is released, TR max. + TSU:DAT = 1000 + 250 = 1250 ns (according to the Standard mode  $I^2C$  bus specification).

FIGURE 27-19: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS TIMING WAVEFORMS




TABLE 27-19: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions	
90 Tsu:sta		Start Condition 100 kHz mode		2(Tosc)(BRG + 1)	— ns		Only relevant for	
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_		Repeated Start	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		condition	
91	THD:STA	Start Condition	ndition 100 kHz mode 2(Tosc)(BRG +		_	ns	After this period, the	
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_		first clock pulse is	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_		generated	
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns		
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_			
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_			
93	THD:STO	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns		
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_			
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_			

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.

FIGURE 27-20: MASTER SSP I<sup>2</sup>C™ BUS DATA TIMING




TABLE 27-20: MASTER SSP I<sup>2</sup>C™ BUS DATA REQUIREMENTS


Param. No.	Symbol	Characteristic		mbol Characteristic Min		Max	Units	Conditions
100	THIGH	Clock High Time	100 kHz mode	2(Tosc)(BRG + 1)		ms		
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms		
101	TLOW	Clock Low Time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms		
102	TR	SDA and SCL	100 kHz mode	_	1000	ns	CB is specified to be	
		Rise Time	400 kHz mode	20 + 0.1 CB	300	ns	from 10 to 400 pF	
			1 MHz mode <sup>(1)</sup>	_	300	ns		
103	TF	SDA and SCL	100 kHz mode	_	300	ns	CB is specified to be	
		Fall Time	400 kHz mode	20 + 0.1 CB	300	ns	from 10 to 400 pF	
			1 MHz mode <sup>(1)</sup>	_	100	ns		
90	Tsu:sta	Start Condition Setup Time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	Only relevant for Repeated Start	
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	condition	
91	THD:STA	Start Condition Hold Time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	After this period, the first clock pulse is	
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	ms	generated	
106	THD:DAT	Data Input Hold Time	100 kHz mode	0	_	ns		
			400 kHz mode	0	0.9	ms		
107	TSU:DAT	Data Input	100 kHz mode	250	_	ns	(Note 2)	
		Setup Time	400 kHz mode	100	_	ns		
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms		
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)		ms		
109	TAA	Output Valid from Clock	100 kHz mode	_	3500	ns		
			400 kHz mode	_	1000	ns		
			1 MHz mode <sup>(1)</sup>			ns		
110	TBUF	Bus Free Time	100 kHz mode	4.7	_	ms	Time the bus must be	
			400 kHz mode	1.3	_	ms	free before a new transmission can start	
D102	Св	Bus Capacitive L	oading	_	400	pF		

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.

Before the SCL line is released, parameter #102 + parameter #107 = 1000 + 250 = 1250 ns (for 100 kHz mode).

<sup>2:</sup> A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but parameter #107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line.


## FIGURE 27-21: USART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



### TABLE 27-21: USART SYNCHRONOUS TRANSMISSION REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Max	Units	Conditions	
120	TckH2dtV	SYNC XMIT (Master & Slave) Clock High to Data-Out Valid	PIC18FXX8	_	50	ns	
			PIC18 <b>LF</b> XX8	_	150	ns	
121	Tckrf	Clock Out Rise Time and Fall Time	PIC18FXX8		25	ns	
		(Master mode)	PIC18 <b>LF</b> XX8	_	60	ns	
122	Tdtrf	Tdtrf Data-Out Rise Time and Fall Time		_	25	ns	
			PIC18 <b>LF</b> XX8		60	ns	

## FIGURE 27-22: USART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING



### **TABLE 27-22: USART SYNCHRONOUS RECEIVE REQUIREMENTS**

Param No.	Symbol	Characteristic	Min	Max	Units	Conditions
125	TdtV2ckl	SYNC RCV (Master & Slave) Data-Hold before CK ↓ (DT hold time)	10	_	ns	
126	TckL2dtl	Data-Hold after CK ↓ (DT hold time)	15		ns	

TABLE 27-23: A/D CONVERTER CHARACTERISTICS: PIC18FXX8 (INDUSTRIAL, EXTENDED)
PIC18LFXX8 (INDUSTRIAL)


Param No.	Symbol	Characte	eristic	Min	Тур	Max	Units	Conditions
A01	NR	Resolution	_	_	10	bit	VREF = VDD ≥ 3.0V	
A03	EIL	Integral Linearity	Error	_	_	<±1	LSb	VREF = VDD ≥ 3.0V
A04	EDL	Differential Linea	rity Error	_	_	<±1	LSb	VREF = VDD ≥ 3.0V
A05	EFS	Full Scale Error		_	_	<±1	LSb	VREF = VDD ≥ 3.0V
A06	Eoff	Offset Error		_	_	<±1.5	LSb	VREF = VDD ≥ 3.0V
A10	_	Monotonicity <sup>(3)</sup>		ç	guarante	ed	_	VSS ≤ VAIN ≤ VREF
A20	VREF	Reference Voltag		0V	_	_	V	
A20A		(VREFH – VREFL)		3V	_	_	٧	For 10-bit resolution
A21	VREFH	Reference Voltage High		Vss	_	VDD + 0.3V	V	
A22	VREFL	Reference Voltage Low		Vss - 0.3V	_	VDD	٧	
A25	VAIN	Analog Input Voltage		Vss - 0.3V	_	VREF + 0.3V	٧	
A30	ZAIN	Recommended Impedance of Analog Voltage Source		_	_	10.0	kΩ	
A40	lad	A/D Conversion	PIC18FXX8	_	180	_	μΑ	Average current
		Current (VDD)	PIC18 <b>LF</b> XX8	_	90	_	μА	consumption when A/D is on (Note 1)
A50	IREF	VREF Input Curre	ent (Note 2)	0	_	5	μΑ	During VAIN acquisition. Based on differential of VHOLD to VAIN. To charge CHOLD.
				_	_	150	μΑ	During A/D conversion cycle.

Note 1: When A/D is off, it will not consume any current other than minor leakage current. The power-down current specification includes any such leakage from the A/D module.

VREF current is from RA2/AN2/VREF- and RA3/AN3/VREF+ pins or VDD and VSS pins, whichever is selected as reference input.

- 2:  $VSS \le VAIN \le VREF$
- **3:** The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.

#### FIGURE 27-23: A/D CONVERSION TIMING



### **TABLE 27-24: A/D CONVERSION REQUIREMENTS**

Param No.	Symbol	Characte	eristic	Min	Max	Units	Conditions
130	TAD	A/d Clock Period	PIC18FXX8	1.6	20 <sup>(5)</sup>	μs	Tosc based, VREF ≥ 3.0V
			PIC18 <b>LF</b> XX8	3.0	20 <sup>(5)</sup>	μs	Tosc based, VREF full range
			PIC18FXX8	2.0	6.0	μs	A/D RC mode
			PIC18 <b>LF</b> XX8	3.0	9.0	μs	A/D RC mode
131	TCNV	Conversion Time (not including acquisition time) (Note 1)		11	12	TAD	
132	TACQ	Acquisition Time (Note	3)	15 10	_	μs μs	-40°C ≤ Temp ≤ +125°C 0°C ≤ Temp ≤ +125°C
135	Tswc	Switching Time from C	onvert $\rightarrow$ Sample	_	(Note 4)		
136	Тамр	Switching Time from Convert → Sample  Amplifier Settling Time (Note 2)		1	_	μs	This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 5 mV @ 5.12V) from the last sampled voltage (as stated on CHOLD).

- Note 1: ADRES register may be read on the following TcY cycle.
  - 2: See Section 20.0 "Compatible 10-Bit Analog-to-Digital Converter (A/D) Module" for minimum conditions when input voltage has changed more than 1 LSb.
  - 3: The time for the holding capacitor to acquire the "New" input voltage when the voltage changes full scale after the conversion (AVDD to AVSS or AVSS to AVDD). The source impedance (RS) on the input channels is  $50\Omega$ .
  - 4: On the next Q4 cycle of the device clock.
  - **5:** The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

NOTES:

### 28.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

**Note:** The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range.

"Typical" represents the mean of the distribution at 25°C. "Maximum" or "minimum" represents (mean +  $3\sigma$ ) or (mean –  $3\sigma$ ) respectively, where  $\sigma$  is a standard deviation, over the whole temperature range.

**FIGURE 28-1:** TYPICAL IDD vs. FOSC OVER VDD (HS MODE) 24 Typical: statistical mean @ 25°C mean + 3σ (-40°C to +125°C) Maximum: Minimum: mean – 3σ (-40°C to +125°C) 20 18 4.5V 16 14 loo (mA) 12 10 3.0V 2.5V 2.0V 12 16 28 32 36 40

FOSC (MHz)






FIGURE 28-3: TYPICAL IDD vs. Fosc OVER VDD (HS/PLL MODE)





FIGURE 28-4: MAXIMUM IDD vs. Fosc OVER VDD (HS/PLL MODE)








FIGURE 28-6: MAXIMUM IDD vs. Fosc OVER VDD (XT MODE)





FIGURE 28-7: TYPICAL IDD vs. FOSC OVER VDD (LP MODE)








FIGURE 28-9: TYPICAL IDD vs. FOSC OVER VDD (EC MODE)




FIGURE 28-10: MAXIMUM IDD vs. Fosc OVER VDD (EC MODE)




FIGURE 28-11: TYPICAL AND MAXIMUM IDD vs. VDD (TIMER1 AS MAIN OSCILLATOR 32.768 kHz, C1 AND C2 = 47 pF)




FIGURE 28-12: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 20 pF, +25°C)




FIGURE 28-13: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 100 pF, +25°C)




FIGURE 28-14: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 300 pF, +25°C)





FIGURE 28-15: IPD vs. VDD, -40°C TO +125°C (SLEEP MODE, ALL PERIPHERALS DISABLED)








FIGURE 28-17: TYPICAL AND MAXIMUM  $\triangle$ ITMR1 vs. VDD OVER TEMPERATURE (-10°C TO +70°C, TIMER1 WITH OSCILLATOR, XTAL = 32 kHz, C1 AND C2 = 47 pF)




FIGURE 28-18: TYPICAL AND MAXIMUM AIWDT vs. VDD OVER TEMPERATURE (WDT ENABLED)





FIGURE 28-19: TYPICAL, MINIMUM AND MAXIMUM WDT PERIOD vs. VDD (-40°C TO +125°C)








FIGURE 28-21: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 5V, -40°C TO +125°C)




FIGURE 28-22: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 3V, -40°C TO +125°C)





FIGURE 28-23: TYPICAL AND MAXIMUM Vol vs. Iol (VDD = 5V, -40°C TO +125°C)








FIGURE 28-25: MINIMUM AND MAXIMUM VIN vs. VDD (ST INPUT, -40°C TO +125°C)




FIGURE 28-26: MINIMUM AND MAXIMUM VIN vs. VDD (TTL INPUT, -40°C TO +125°C)




FIGURE 28-27: MINIMUM AND MAXIMUM VIN vs. VDD (I<sup>2</sup>CTM INPUT, -40°C TO +125°C)






FIGURE 28-28: A/D NONLINEARITY vs. VREFH (VDD = VREFH, -40°C TO +125°C)






NOTES:


#### 29.0 PACKAGING INFORMATION

#### 29.1 **Package Marking Information**

#### 28-Lead SPDIP



### Example




#### 28-Lead SOIC



### Example



#### 40-Lead PDIP



### Example



Legend: XX...X Customer-specific information

> Υ Year code (last digit of calendar year) ΥY Year code (last 2 digits of calendar year) WW Week code (week of January 1 is week '01') NNN Alphanumeric traceability code

(e3) Pb-free JEDEC designator for Matte Tin (Sn) This package is Pb-free. The Pb-free JEDEC designator (e3)

can be found on the outer packaging for this package.

In the event the full Microchip part number cannot be marked on one line, it will Note: be carried over to the next line, thus limiting the number of available characters for customer-specific information.

### 29.1 Package Marking Information (Continued)


44-Lead PLCC



Example



44-Lead TQFP



Example




### 29.2 Package Details

The following sections give the technical details of the packages.

### 28-Lead Skinny Plastic Dual In-line (SP) - 300 mil Body (PDIP)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	ts INCHES*			М	ILLIMETERS		
Dimension	n Limits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28		
Pitch	р		.100			2.54		
Top to Seating Plane	Α	.140	.150	.160	3.56	3.81	4.06	
Molded Package Thickness	A2	.125	.130	.135	3.18	3.30	3.43	
Base to Seating Plane	A1	.015			0.38			
Shoulder to Shoulder Width	Е	.300	.310	.325	7.62	7.87	8.26	
Molded Package Width	E1	.275	.285	.295	6.99	7.24	7.49	
Overall Length	D	1.345	1.365	1.385	34.16	34.67	35.18	
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43	
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38	
Upper Lead Width	B1	.040	.053	.065	1.02	1.33	1.65	
Lower Lead Width	В	.016	.019	.022	0.41	0.48	0.56	
Overall Row Spacing §	еВ	.320	.350	.430	8.13	8.89	10.92	
Mold Draft Angle Top	α	5	10	15	5	10	15	
Mold Draft Angle Bottom	β	5	10	15	5	10	15	

<sup>\*</sup> Controlling Parameter

Notes:


Dimension D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MO-095

<sup>§</sup> Significant Characteristic

### 28-Lead Plastic Small Outline (SO) - Wide, 300 mil Body (SOIC)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



·	Units			INCHES*			MILLIMETERS		
Dimensi	on Limits	MIN	NOM	MAX	MIN	NOM	MAX		
Number of Pins	n		28			28			
Pitch	р		.050			1.27			
Overall Height	Α	.093	.099	.104	2.36	2.50	2.64		
Molded Package Thickness A2		.088	.091	.094	2.24	2.31	2.39		
Standoff §	A1	.004	.008	.012	0.10	0.20	0.30		
Overall Width	Е	.394	.407	.420	10.01	10.34	10.67		
Molded Package Width	E1	.288	.295	.299	7.32	7.49	7.59		
Overall Length	D	.695	.704	.712	17.65	17.87	18.08		
Chamfer Distance	h	.010	.020	.029	0.25	0.50	0.74		
Foot Length	L	.016	.033	.050	0.41	0.84	1.27		
Foot Angle Top	ф	0	4	8	0	4	8		
Lead Thickness	С	.009	.011	.013	0.23	0.28	0.33		
Lead Width	В	.014	.017	.020	0.36	0.42	0.51		
Mold Draft Angle Top	α	0	12	15	0	12	15		
Mold Draft Angle Bottom	β	0	12	15	0	12	15		

<sup>\*</sup> Controlling Parameter


#### Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MS-013

<sup>§</sup> Significant Characteristic

### 40-Lead Plastic Dual In-line (P) – 600 mil Body (PDIP)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	Inits INCHES*				MILLIMETERS		
Dimension	n Limits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		40			40		
Pitch	р		.100			2.54		
Top to Seating Plane	Α	.160	.175	.190	4.06	4.45	4.83	
Molded Package Thickness	A2	.140	.150	.160	3.56	3.81	4.06	
Base to Seating Plane	A1	.015			0.38			
Shoulder to Shoulder Width	Е	.595	.600	.625	15.11	15.24	15.88	
Molded Package Width	E1	.530	.545	.560	13.46	13.84	14.22	
Overall Length	D	2.045	2.058	2.065	51.94	52.26	52.45	
Tip to Seating Plane	L	.120	.130	.135	3.05	3.30	3.43	
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38	
Upper Lead Width	B1	.030	.050	.070	0.76	1.27	1.78	
Lower Lead Width	В	.014	.018	.022	0.36	0.46	0.56	
Overall Row Spacing §	eB	.620	.650	.680	15.75	16.51	17.27	
Mold Draft Angle Top	α	5	10	15	5	10	15	
Mold Draft Angle Bottom	β	5	10	15	5	10	15	
* Controlling Borometer	P	J	10	10	J	10		

Controlling Parameter


§ Significant Characteristic

Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MO-011

### 44-Lead Plastic Leaded Chip Carrier (L) – Square (PLCC)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



		INCHES* MILLIM			ILLIMETERS	METERS	
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		44			44	
Pitch	р		.050			1.27	
Pins per Side	n1		11			11	
Overall Height	Α	.165	.173	.180	4.19	4.39	4.57
Molded Package Thickness	A2	.145	.153	.160	3.68	3.87	4.06
Standoff §	A1	.020	.028	.035	0.51	0.71	0.89
Side 1 Chamfer Height	А3	.024	.029	.034	0.61	0.74	0.86
Corner Chamfer 1	CH1	.040	.045	.050	1.02	1.14	1.27
Corner Chamfer (others)	CH2	.000	.005	.010	0.00	0.13	0.25
Overall Width	Е	.685	.690	.695	17.40	17.53	17.65
Overall Length	D	.685	.690	.695	17.40	17.53	17.65
Molded Package Width	E1	.650	.653	.656	16.51	16.59	16.66
Molded Package Length	D1	.650	.653	.656	16.51	16.59	16.66
Footprint Width	E2	.590	.620	.630	14.99	15.75	16.00
Footprint Length	D2	.590	.620	.630	14.99	15.75	16.00
Lead Thickness	С	.008	.011	.013	0.20	0.27	0.33
Upper Lead Width	B1	.026	.029	.032	0.66	0.74	0.81
Lower Lead Width	В	.013	.020	.021	0.33	0.51	0.53
Mold Draft Angle Top	α	0	5	10	0	5	10
Mold Draft Angle Bottom	β	0	5	10	0	5	10

<sup>\*</sup> Controlling Parameter


#### Notes

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MO-047

<sup>§</sup> Significant Characteristic

### 44-Lead Plastic Thin Quad Flatpack (PT) 10x10x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)

**Ste:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units INCHES			М	ILLIMETERS*			
Dimension Li	mits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		44			4	4	
Pitch	р	.031				0.8	30	
Pins per Side	n1	11				1	1	
Overall Height	Α	.039	.043	.047	1.00	1.10	1.20	
Molded Package Thickness	A2	.037	.039	.041	0.95	1.00	1.05	
Standoff	A1	.002	.004	.006	0.05	0.10	0.15	
Foot Length	L	.018	.024	.030	0.45	0.60	0.75	
Footprint (Reference)	F		.039 REF.			1.00 REF.		
Foot Angle	ф	0	3.5	7	0	3.5	7	
Overall Width	Е	.463	.472	.482	11.75	12.00	12.25	
Overall Length	D	.463	.472	.482	11.75	12.00	12.25	
Molded Package Width	E1	.390	.394	.398	9.90	10.00	10.10	
Molded Package Length	D1	.390	.394	.398	9.90	10.00	10.10	
Lead Thickness	С	.004	.006	.008	0.09	0.15	0.20	
Lead Width	В	.012	.015	.017	0.30	0.38	0.44	
Pin 1 Corner Chamfer	CH	.025	.035	.045	0.64	0.89	1.14	
Mold Draft Angle Top	α	5	10	15	5	10	15	
Mold Draft Angle Bottom	β	5	10	15	5	10	15	

<sup>\*</sup> Controlling Parameter

#### Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. REF: Reference Dimension, usually without tolerance, for information purposes only.

See ASME Y14.5M JEDEC Equivalent: MS-026 Drawing No. C04-076

Revised 07-22-05

NOTES:

# APPENDIX A: DATA SHEET REVISION HISTORY

### **Revision A (June 2001)**

Original data sheet for the PIC18FXX8 family.

### Revision B (May 2002)

Updated information on CAN module, device memory and register maps, I/O ports and Enhanced CCP.

### **Revision C (January 2003)**

This revision includes the DC and AC Characteristics Graphs and Tables (see Section 28.0 "DC and AC Characteristics Graphs and Tables"), Section 27.0 "Electrical Characteristics" have been updated and CAN certification information has been added.

### **Revision D (September 2004)**

Data Sheet Errata (DS80134 and DS80161) issues have been addressed and corrected along with minor corrections to the data sheet text.

### **Revision E (October 2006)**

Packaging diagrams updated.

TABLE B-1: DEVICE DIFFERENCES

	Features	PIC18F248	PIC18F258	PIC18F448	PIC18F458
Internal	Bytes	16K	32K	16K	32K
Program Memory	# of Single-Word Instructions	8192	16384	8192	16384
Data Memory	(Bytes)	768	1536	768	1536
I/O Ports		Ports A, B, C	Ports A, B, C	Ports A, B, C, D, E	Ports A, B, C, D, E
Enhanced Cap Modules	oture/Compare/PWM	_	_	1	1
Parallel Slave	Port	No	No	Yes	Yes
10-bit Analog-	to-Digital Converter	5 input channels	5 input channels	8 input channels	8 input channels
Analog Compa	arators	No	No	2	2
Analog Compa	arators VREF Output	N/A	N/A	Yes	Yes
Packages		28-pin SPDIP 28-pin SOIC	28-pin SPDIP 28-pin SOIC	40-pin PDIP 44-pin PLCC 44-pin TQFP	40-pin PDIP 44-pin PLCC 44-pin TQFP

# APPENDIX B: DEVICE DIFFERENCES

The differences between the devices listed in this data sheet are shown in Table B-1.

### APPENDIX C: DEVICE MIGRATIONS

This section is intended to describe the functional and electrical specification differences when migrating between functionally similar devices (such as from a PIC16C74A to a PIC16C74B).

**Not Applicable** 

# APPENDIX D: MIGRATING FROM OTHER PICmicro® DEVICES

This discusses some of the issues in migrating from other PICmicro devices to the PIC18FXX8 family of devices.

### D.1 PIC16CXXX to PIC18FXX8

See Application Note *AN716 "Migrating Designs from PIC16C74A/74B to PIC18C442"* (DS00716).

### D.2 PIC17CXXX to PIC18FXX8

See Application Note *AN726 "PIC17CXXX to PIC18CXXX Migration"* (DS00726).

### **INDEX**

Α		Block Diagrams	
A/D	241	A/D	
A/D Converter Flag (ADIF Bit)	243	Analog Input Model	
A/D Converter Interrupt, Configuring		Baud Rate Generator	
Acquisition Requirements		CAN Buffers and Protocol Engine	200
Acquisition Time		CAN Receive Buffer	230
ADCON0 Register		CAN Transmit Buffer	227
S .		Capture Mode Operation	125
ADDECU Parister		Comparator I/O Operating Modes	
ADRESH Register		Comparator Output	
ADRESH/ADRESL Registers		Comparator Voltage Reference	
ADRESL Register		Output Buffer Example	257
Analog Port Pins, Configuring			
Associated Registers Summary	248	Compare (CCP Module) Mode Operation	
Calculating the Minimum Required		Enhanced PWM	
Acquisition Time	245	Interrupt Logic	
Configuring the Module		Low-Voltage Detect (LVD)	
Conversion Clock (TAD)		Low-Voltage Detect with External Input	
Conversion Status (GO/DONE Bit)		MSSP (I <sup>2</sup> C Master Mode)	
Conversion TAD Cycles		MSSP (I <sup>2</sup> C Mode)	152
		MSSP (SPI Mode)	143
Conversions		On-Chip Reset Circuit	
Minimum Charging Time		OSC2/CLKO/RA6 Pin	
Result Registers		PIC18F248/258 Architecture	
Selecting the Conversion Clock	246	PIC18F448/458 Architecture	
Special Event Trigger (CCP)	126		
Special Event Trigger (ECCP)	133, 248	PLL	
TAD vs. Device Operating Frequencies		PORTC (Peripheral Output Override)	
(For Extended, LF Devices) (table)	246	PORTD and PORTE (Parallel Slave Port)	
TAD vs. Device Operating		PORTD in I/O Port Mode	102
Frequencies (table)	246	PORTE	104
Use of the ECCP Trigger		PWM (CCP Module)	128
		RA3:RA0 and RA5 Pins	94
Absolute Maximum Ratings		RA4/T0CKI Pin	
AC (Timing) Characteristics		RB1:RB0 Pins	
Parameter Symbology		RB2/CANTX/INT2 Pin	
Access Bank	54	RB3/CANRX Pin	
ACKSTAT		RB7:RB4 Pins	
ACKSTAT Status Flag			
ADCON0 Register	241	Reads from Flash Program Memory	
GO/DONE Bit	243	Table Read Operation	
ADCON1 Register	241	Table Write Operation	
ADDLW		Table Writes to Flash Program Memory	
Addressable Universal Synchronous Asynchronou		Timer0 in 16-bit Mode	110
Receiver Transmitter. See USART.	.0	Timer0 in 8-bit Mode	110
ADDWF	207	Timer1	114
ADDWF		Timer1 (16-bit Read/Write Mode)	114
		Timer2	
ADRESH Register		Timer3	
ADRESH/ADRESL Registers		Timer3 (16-bit Read/Write Mode)	
ADRESL Register	241	USART Receive	
Analog-to-Digital Converter. See A/D.			
ANDLW	288	USART Transmit	
ANDWF	289	Voltage Reference	
Assembler		Watchdog Timer	
MPASM Assembler	323	BN	
Associated Registers		BNC	
7.00001a.to 2 1.09.01010	02, .0.	BNN	291
В		BNOV	292
Bank Select Register (BSR)	54	BNZ	292
Baud Rate Generator		BOR. See Brown-out Reset.	
		BOV	295
BC		BRA	
BCF		BRG. See Baud Rate Generator.	200
BF			06 065
BF Status Flag	173	Brown-out Reset (BOR)	20, 205

SF	293	Listen Only Mode	226
TFSC	294	Loopback Mode	227
TFSS	294	Message Acceptance Filters	
ΓG	295	and Masks	215, 232
Z	296	Message Acceptance Mask and	
		Filter Operation (diagram)	232
		Message Reception	
Compilers		Message Time-Stamping	
MPLAB C17	324	Message Transmission	
MPLAB C18	324	Modes of Operation	
MPLAB C30		Normal Mode	
ALL	-	Oscillator Tolerance	
AN Module	200	Overview	
Aborting Transmission	228	Phase Buffer Segments	
Acknowledge Error		<u>-</u>	
		Programming Time Segments	
Baud Rate Registers		Propagation Segment	
Baud Rate Setting		Receive Buffer Registers	
Bit Error		Receive Buffers	
Bit Time Partitioning (diagram)		Receive Message Buffering	
Bit Timing Configuration Registers		Receive Priority	230
BRGCON1		Registers	
BRGCON2	236	Resynchronization	235
BRGCON3	236	Sample Point	234
Calculating To, Nominal Bit Rate and		Shortening a Bit Period (diagram)	236
Nominal Bit Time	234	Stuff Bit Error	237
Configuration Mode	226	Synchronization	235
Control and Status Registers	201	Synchronization Rules	
Controller Register Map		Synchronization Segment	
CRC Error		Time Quanta	
Disable Mode	_	Transmit Buffer Registers	
Error Detection	-	Transmit Buffers	
Error Modes and Error Counters			
Error Modes State (diagram)		Transmit Priority	
Error Recognition Mode		Transmit/Receive Buffers	
		Values for ICODE (table)	
Error States		Capture (CCP Module)	
Filter/Mask Truth (table)		CAN Message Time-Stamp	
Form Error		CCP Pin Configuration	
Hard Synchronization		CCP1 Prescaler	
I/O Control Register		CCPR1H:CCPR1L Registers	
Information Processing Time		Software Interrupt	125
Initiating Transmission	228	Timer1/Timer3 Mode Selection	124
Internal Message Reception		Capture (ECCP Module)	133
Flowchart	231	CAN Message Time-Stamp	133
Internal Transmit Message		Capture/Compare/PWM (CCP)	123
Flowchart	229	Capture Mode. See Capture	
Interrupt Acknowledge	239	(CCP Module).	
Interrupt Registers		CCP1 Module	124
Interrupts		Timer Resources	
Bus Activity Wake-up		CCPR1H Register	
Bus-Off		CCPR1L Register	
Code Bits			124
Error		Compare Mode. See Compare	
		(CCP Module).	
Message Error		Interaction of CCP1 and	
Receive		ECCP1 Modules	124
Receiver Bus Passive		PWM Mode. See PWM (CCP Module).	
Receiver Overflow		Ceramic Resonators	
Receiver Warning		Ranges Tested	
Transmit		Clocking Scheme	
Transmitter Bus Passive	239	CLRF	297
Transmitter Warning	239	CLRWDT	297
Lengthening a Bit Period			
(diagram)	225		

# PIC18FXX8

Code Examples		CPFSGT	299
16 x 16 Signed Multiply Routine	76	CPFSLT	
16 x 16 Unsigned Multiply Routine		Crystal Oscillator	
8 x 8 Signed Multiply Routine		Capacitor Selection	18
8 x 8 Unsigned Multiply Routine			
Changing Between Capture Prescalers		D	
Data EEPROM Read		Data EEPROM Memory	59
Data EEPROM Refresh Routine		Associated Registers	
Data EEPROM Write	-	EEADR Register	
Erasing a Flash Program Memory Row		EECON1 Register	
Fast Register Stack		EECON2 Register	
How to Clear RAM (Bank 1) Using		Operation During Code-Protect	
Indirect Addressing	55	Protection Against Spurious Writes	
Initializing PORTA		Reading	
Initializing PORTB		Usage	
Initializing PORTC		Write Verify	
Initializing PORTD		Writing to	
Initializing PORTE		Data Memory	
		General Purpose Registers	
Loading the SSPBUF Register	140	Special Function Registers	
Reading a Flash Program	60	Data Memory Map	44
Memory Word	69	PIC18F248/448	45
Saving Status, WREG and BSR	20	PIC18F258/458	
Registers in RAM	92		_
WIN and ICODE Bits Usage in		DAW	300
Interrupt Service Routine to		DC and AC Characteristics	004
Access TX/RX Buffers		Graphs and Tables	
Writing to Flash Program Memory		DC Characteristics	
Code Protection	265	EEPROM and Enhanced Flash	339
COMF		PIC18FXX8 (Ind., Ext.) and	
Comparator Module		PIC18LFXX8 (Ind.)	
Analog Input Connection Considerations	253	DCFSNZ	
Associated Registers	254	DECF	300
Configuration	250	DECFSZ	301
Effects of a Reset	253	Demonstration Boards	
External Reference Signal	251	PICDEM 1	326
Internal Reference Signal	251	PICDEM 17	327
Interrupts		PICDEM 18R	327
Operation		PICDEM 2 Plus	326
Operation During Sleep		PICDEM 3	326
Outputs		PICDEM 4	326
Reference		PICDEM LIN	327
Response Time		PICDEM USB	327
Comparator Specifications		PICDEM.net Internet/Ethernet	326
Comparator Voltage Reference Module		Development Support	
Accuracy/Error		Device Differences	
Associated Registers		Device Migrations	
		Device Overview	
Configuring		Features	
Connection Considerations			
Effects of a Reset		Direct Addressing	
Operation During Sleep		Disable Mode (CAN Module)	220
Compare (CCP Module)		Е	
CCP1 Pin Configuration		Electrical Characteristics	220
CCPR1 and ECCPR1 Registers	126		
Registers Associated with Capture,		Enhanced Capture/Compare/PWM (ECCP)	
Compare, Timer1 and Timer3		Auto-Shutdown	142
Software Interrupt		Capture Mode. See Capture	
Special Event Trigger115, 12	21, 126, 248	(ECCP Module).	
Timer1/Timer3 Mode Selection		Compare Mode. See Compare	
Compare (ECCP Module)	133	(ECCP Module).	
Registers Associated with Enhanced		ECCPR1H Register	
Capture, Compare, Timer1 and Timer3	133	ECCPR1L Register	132
Special Event Trigger		Interaction of CCP1 and	
Compatible 10-Bit Analog-to-Digital		ECCP1 Modules	132
Converter (A/D) Module. See A/D.		Pin Assignments for Various Modes	132
Configuration Mode (CAN Module)	226	PWM Mode. See PWM (ECCP Module).	
CPESEQ		Timer Resources	132

Enhanced CCP Auto-Shutdown	142	Slave Mode	156
Enhanced PWM Mode.		Addressing	156
See PWM (ECCP Module).		Reception	157
Errata		Transmission	157
Error Recognition Mode (CAN Module)	226	Sleep Operation	177
Evaluation and Programming Tools	327	Stop Condition Timing	176
External Clock Input	19	ID Locations	265, 279
F		INCF	302
		INCFSZ	
Firmware Instructions		In-Circuit Debugger	
Flash Program Memory		In-Circuit Serial Programming (ICSP)	
Associated Registers		Indirect Addressing	
Control Registers		FSR Register	
Erase Sequence		INDF Register	
Erasing		Operation	
Operation During Code-Protect		INFSNZ	
Reading		Initialization Conditions for All Registers	
TABLAT (Table Latch) Register	68	Instruction Cycle	
Table Pointer		Instruction Flow/Pipelining	
Boundaries Based on Operation		Instruction Format	
Table Pointer Boundaries		Instruction Set	
Table Reads and Table Writes		ADDLW	_
TBLPTR (Table Pointer) Register		ADDWF	_
Write Sequence		ADDWFC	
Writing to		ANDLW	
Protection Against Spurious Writes		ANDWF	
Unexpected Termination		BC	
Write Verify	73	BCF	
G		BN	
<del>-</del>	000	BNC	_
GOTO	302	BNN	_
Н		BNOV	_
	75	BNZ	
Hardware Multiplier		BOV	
Operation		BRA	
Performance Comparison (table) HS4 (PLL)		BSF	
NO4 (FLL)	19	BTFSC	_
I		BTFSS	_
I/O Ports	93	BTG	
I <sup>2</sup> C Mode		BZ	
ACK Pulse		CALL	
Acknowledge Sequence Timing		CLRF	
Baud Rate Generator		CLRWDT	_
Bus Collision During a		COMF	
Repeated Start Condition	180	CPFSEQ	
Bus Collision During a Start Condition		CPFSGT	
Bus Collision During a Stop Condition		CPFSLT	
Clock Arbitration		DAW	
Clock Stretching		DCFSNZ	
Effect of a Reset		DECF	
General Call Address Support		DECFSZ	
Master Mode		GOTO	
Operation		INCF	
Reception		INCFSZ	
Repeated Start Condition Timing		INFSNZ	
Start Condition Timing		IORLW	
Transmission		IORWF	
Multi-Master Mode		LFSR	
Communication, Bus Collision	*** * *	MOVF	
and Bus Arbitration	177	MOVFF	
Operation		MOVLM	
Read/Write Bit Information (R/W Bit)		MOVLW	
Registers		MOVWF	
Serial Clock (RC3/SCK/SCL)		MULLW	
` '		MULWF	308

# PIC18FXX8

NEGF		309
NOP		309
POP		310
PUSH		
RCALL		
RESET		-
RETFIE		-
RETLW		
RETURN		
RLCF		
RLNCF		-
RRCF		-
RRNCF		
SETF		
SLEEP		316
SUBFWB		316
SUBLW		317
SUBWF		317
SUBWFB		318
SWAPF		318
TBLRD		
TBLWT		
TSTFSZ		
XORLW		
XORWF		
Summary Table		284
INTCON Register		
RBIF Bit		96
Inter-Integrated Circuit. See I <sup>2</sup> C.		
Interrupt Sources		
A/D Conversion Complete		
CAN Module		
Capture Complete (CCP)		125
Compare Complete (CCP)		126
Interrupt-on-Change (RB7:RB4)		96
TMR0 Overflow		
TMR1 Overflow		
TMR2 to PR2 Match	· · · · · · · · · · · · · · · · · · ·	118
TMR2 to PR2 Match (PWM)		
TMR3 Overflow		
Interrupt-on-Change (RB7:RB4) Flag		121
(RBIF Bit)		06
· · · · · · · · · · · · · · · · · · ·		
Interrupts	-	
Context Saving During		
Enable Registers		
Flag Registers		
INT		
PORTB Interrupt-on-Change		
PORTB Interrupt-on-Change Priority Registers TMR0		88
PORTB Interrupt-on-ChangePriority RegistersTMR0TMR0 Interrupts, Flag Bits		88 92
PORTB Interrupt-on-Change Priority Registers TMR0		88 92
PORTB Interrupt-on-ChangePriority RegistersTMR0TMR0 Interrupts, Flag Bits		88 92 243
PORTB Interrupt-on-Change	. 124, 125,	88 92 243 126
PORTB Interrupt-on-Change	. 124, 125,	88 92 243 126 304
PORTB Interrupt-on-ChangePriority RegistersTMR0IMR0Interrupts, Flag Bits A/D Converter Flag (ADIF Bit)	. 124, 125,	88 92 243 126 304
PORTB Interrupt-on-Change	. 124, 125,	88 92 243 126 304
PORTB Interrupt-on-Change	124, 125,	88 92 243 126 304 304
PORTB Interrupt-on-Change	124, 125,	88 92 243 126 304 304 305
PORTB Interrupt-on-Change	124, 125,	88 92 243 126 304 304 305 226
PORTB Interrupt-on-Change	124, 125,	88 92 243 126 304 304 305 226 43
PORTB Interrupt-on-Change	124, 125,	88 92 243 126 304 304 305 226 43 43

Low-Voltage Detect	259
Characteristics	338
Current Consumption	263
Effects of a Reset	263
Operation	262
Operation During Sleep	263
Reference Voltage Set Point	
Typical Application	
Low-Voltage ICSP Programming	
LVD. See Low-Voltage Detect.	
M	
Master Synchronous Serial Port (MSSP).	
See MSSP.	
Master Synchronous Serial Port.	
See MSSP.	07
Memory Organization	
Data Memory	
Internal Program Memory Operation	
Program Memory	
Migrating from other PICmicro Devices	
MOVF	
MOVFF	
MOVLB	
MOVLW	
MOVWF	307
MPLAB ASM30 Assembler,	
Linker, Librarian	
MPLAB ICD 2 In-Circuit Debugger	325
MPLAB ICE 2000 High-Performance	
Universal In-Circuit Emulator	325
MPLAB ICE 4000 High-Performance	
Universal In-Circuit Emulator	325
MPLAB Integrated Development	
Environment Software	323
MPLAB PM3 Device Programmer	325
MPLINK Object Linker/	
MPLIB Object Librarian	324
MSSP	
Control Registers	
Enabling SPI I/O	
Operation	
Overview	
SPI Master Mode	
SPI Master/Slave Connection	
SPI Mode	
SPI Slave Mode	
TMR2 Output for Clock Shift	
Typical Connection	
MSSP. See also I <sup>2</sup> C Mode, SPI Mode.	
MULLW	308
MULWF	
N	
NEGF	309
NOP	
Normal Operation Mode (CAN Module)	226

0		RD0/PSP0/C1IN+	14
Opcode Field Descriptions	282	RD1/PSP1/C1IN	
Oscillator		RD2/PSP2/C2IN+	
Effects of Sleep Mode	23	RD3/PSP3/C2IN	
Power-up Delays		RD4/PSP4/ECCP1/P1A	14
Switching Feature		RD5/PSP5/P1B	
System Clock Switch Bit		RD6/PSP6/P1C	14
Transitions		RD7/PSP7 <u>/P</u> 1D	14
Oscillator Configurations		RE0/AN5/ <u>RD.</u>	15
Crystal Oscillator, Ceramic Resonators		RE1/AN6/ <u>WR</u> /C1OUT	
EC		RE2/AN7/CS/C2OUT	15
ECIO		VDD	1
HS		Vss	
HS4		Pinout I/O Descriptions	10
LP		Pointer, FSRn	55
RC		POP	310
RCIO		POR. See Power-on Reset.	
XT		PORTA	
Oscillator Selection		Associated Register Summary	9
Oscillator, Timer1		Functions	9
Oscillator, WDT	, ,	LATA Register	93
Oscillator, WD1		PORTA Register	93
P		TRISA Register	
Packaging Information	377	PORTB	
Details		Associated Register Summary	99
Marking		Functions	
Parallel Slave Port (PSP)		LATB Register	96
Associated Registers		PORTB Register	
PORTD		RB7:RB4 Interrupt-on-Change	
PSP Mode Select (PSPMODE) Bit		Flag (RBIF Bit)	96
RE2/AN7/CS/C2OUT		TRISB Register	
PIC18FXX8 Voltage-Frequency	107	PORTC	
Graph (Industrial)	330	Associated Register Summary	10 <sup>-</sup>
PIC18LFXX8 Voltage-Frequency		Functions	
Graph (Industrial)	221	LATC Register	100
PICkit 1 Flash Starter Kit		PORTC Register	
PICSTART Plus Development	521	RC3/SCK/SCL Pin	
Programmer	226	RC7/RX/DT pin	18
Pin Functions		TRISC Register	100, 183
MCLR/VPP	10	PORTD	
OSC1/CLKI		Associated Register Summary	103
OSC2/CLKO/RA6		Functions	
RA0/AN0/CVREF		LATD Register	102
RA1/AN1		Parallel Slave Port (PSP) Function	
RA2/AN2/VREF-		PORTD Register	
RA3/AN3/VREF+		TRISD Register	102
RA4/T0CKI		PORTE	
RA5/AN4/SS/LVDIN		Associated Register Summary	106
RA6		Functions	
RB0/INT0		LATE Register	
RB1/INT1		PORTE Register	
RB2/CANTX/INT2		PSP Mode Select (PSPMODE) Bit	
RB3/CANRX		RE2/AN7/CS/C2OUT	
RB4		TRISE Register	
		Power-Down Mode. See Sleep.	
RB5/PGM RB6/PGC		Power-on Reset (POR)	26. 26!
		MCLR	
RB7/PGD		Oscillator Start-up Timer (OST)	
RC0/T10S0/T1CKI		PLL Lock Time-out	
RC1/T1OSI		Power-up Timer (PWRT)	
RC2/CCP1		Time-out Sequence	
RC3/SCK/SCL		Power-up Delays	<b>.</b>
RC4/SDI/SDA		OSC1 and OSC2 Pin States	
RC5/SDO		in Sleep Mode	2:
RC6/TX/CK		Prescaler, Timer0	
RC7/RX/DT	13		

# PIC18FXX8

Prescaler, Timer2PRO MATE II Universal Device	128	Register File SummaryRegisters	49
Programmer	325	ADCON0 (A/D Control 0)	24
Program Counter	020	ADCON1 (A/D Control 1)	
PCL Register	40	BRGCON1 (Baud Rate Control 1)	
PCLATH Register		BRGCON2 (Baud Rate Control 2)	
PCLATU Register		BRGCON3 (Baud Rate Control 3)	
Program Memory		CANCON (CAN Control)	
Fast Register Stack		CANSTAT (CAN Status)	
Instructions		CCP1CON (CCP1 Control)	
Two-Word		CIOCON (CAN I/O Control)	
Map and Stack for PIC18F248/448	37	CMCON (Comparator Control)	
Map and Stack for PIC18F258/458		COMSTAT (CAN	
PUSH and POP Instructions		Communication Status)	20
Return Address Stack		CONFIG1H (Configuration 1 High)	
Return Stack Pointer (STKPTR)		CONFIG2H (Configuration 2 High)	
Stack Full/Underflow Resets		CONFIG2L (Configuration 2 Low)	
Top-of-Stack Access		CONFIG4L (Configuration 4 Low)	
Program Verification and		CONFIG5H (Configuration 5 High)	
Code Protection	276	CONFIG5L (Configuration 5 Low)	
Associated Registers Summary		CONFIG6H (Configuration 6 High)	
Configuration Register Protection		CONFIG6L (Configuration 6 Low)	
Data EEPROM Code Protection		CONFIG7H (Configuration 7 High)	
Program Memory Code Protection		CONFIG7L (Configuration 7 Low)	
Programming, Device Instructions		CVRCON (Comparator Voltage	
PUSH		Reference Control)	25!
PWM (CCP Module)		DEVID1 (Device ID 1)	
CCPR1H:CCPR1L Registers		DEVID2 (Device ID 2)	
Duty Cycle		ECCP1CON (ECCP1 Control)	
Example Frequencies/Resolutions		ECCP1DEL (PWM Delay)	
Period		ECCPAS (Enhanced Capture/Compare/PWM	
Registers Associated with		Auto-Shutdown Control)	14:
PWM and Timer2	129	EECON1 (EEPROM Control 1)	
Setup for PWM Operation		INTCON (Interrupt Control)	
TMR2 to PR2 Match		INTCON2 (Interrupt Control 2)	
PWM (ECCP Module)		INTCON3 (Interrupt Control 3)	
Full-Bridge Application Example		IPR1 (Peripheral Interrupt Priority 1)	
Full-Bridge Mode		IPR2 (Peripheral Interrupt Priority 2)	
Direction Change		IPR3 (Peripheral Interrupt Priority 3)	
Half-Bridge Mode		LVDCON (LVD Control)	
Half-Bridge Output Mode		OSCCON (Oscillator Control)	
Applications Example	136	PIE1 (Peripheral Interrupt Enable 1)	
Output Configurations		PIE2 (Peripheral Interrupt Enable 2)	
Output Polarity Configuration		PIE3 (Peripheral Interrupt Enable 3)	
Output Relationships Diagram		PIR1 (Peripheral Interrupt Request	
Programmable Dead-Band Delay		(Flag) 1)	
Registers Associated with Enhanced PWM		PIR2 (Peripheral Interrupt Request	
and Timer2	141	(Flag) 2)	8
Setup for PWM Operation		PIR3 (Peripheral Interrupt Request	
Standard Mode		(Flag) 3)	84 223
Start-up Considerations		RCON (Reset Control)	
System Implementation		RCSTA (Receive Status and Control)	
Cyclom implementation		RXB0CON (Receive Buffer 0 Control)	
Q		RXB1CON (Receive Buffer 1 Control)	
Q Clock	128	RXBnDLC (Receive Buffer n	= .
_		Data Length Code)	21:
R		RXBnDm (Receive Buffer n	= 1
RAM. See Data Memory.		Data Field Byte m)	214
RCALL	311	RXBnEIDH (Receive Buffer n	= .
RCON Register		Extended Identifier, High Byte)	211
Significance of Status Bits vs.		RXBnEIDL (Receive Buffer n	12
Initialization Condition	27	Extended Identifier, Low Byte)	21:
RCSTA Register	183	RXBnSIDH (Receive Buffer n	= 10
SPEN Bit		Standard Identifier, High Byte)	213
Receiver Warning			=
Register File	44		

RXBnSIDL (Receive Buffer n		S	
Standard Identifier, Low Byte)	212	SCI. See USART.	
RXERRCNT (Receive Error Count)		SCK Pin	1/15
RXFnEIDH (Receive Acceptance Filter n		SDI Pin	
Extended Identifier, High Byte)	216	SDO Pin	
RXFnEIDL (Receive Acceptance Filter n			
Extended Identifier, Low Byte)	216	Serial Clock (SCK) Pin	143
RXFnSIDH (Receive Acceptance Filter n		Serial Communication Interface.	
Standard Identifier Filter, High Byte)	215	See USART.	
RXFnSIDL (Receive Acceptance Filter n		Serial Peripheral Interface. See SPI.	
Standard Identifier Filter, Low Byte)	215	SETF	
RXMnEIDH (Receive Acceptance Mask n		Slave Select (SS) Pin	
Extended Identifier Mask, High Byte)	217	Slave Select, SS Pin	
RXMnEIDL (Receive Acceptance Mask n		SLEEP	
Extended Identifier Mask, Low Byte)	217	Sleep	
RXMnSIDH (Receive Acceptance Mask n	217	Software Simulator (MPLAB SIM)	
Standard Identifier Mask, High Byte)	016	Software Simulator (MPLAB SIM30)	324
,	210	Special Event Trigger. See Compare.	
RXMnSIDL (Receive Acceptance Mask n	017	Special Features of the CPU	
Standard Identifier Mask, Low Byte)		Configuration Bits	265
SSPCON1 (MSSP Control 1, I <sup>2</sup> C Mode)		Configuration Bits and	
SSPCON1 (MSSP Control 1, SPI Mode)		Device IDs	265
SSPCON2 (MSSP Control 2, I <sup>2</sup> C Mode)		Configuration Registers	
SSPSTAT (MSSP Status, I <sup>2</sup> C Mode)		Special Function Register Map	47
SSPSTAT (MSSP Status, SPI Mode)		Special Function Registers	
Status		SPI Mode	
STKPTR (Stack Pointer)		Associated Registers	151
T0CON (Timer0 Control)		Bus Mode Compatibility	
T1CON (Timer1 Control)		Effects of a Reset	
T2CON (Timer2 Control)	117	Master Mode	
T3CON (Timer3 Control)	119	Master/Slave Connection	
TRISE (PORTE Direction/PSP Control)	105	Registers	
TXBnCON (Transmit Buffer n Control)	206	Serial Clock	
TXBnDLC (Transmit Buffer n		Serial Data In (SDI) Pin	
Data Length Code)	209	Serial Data Out (SDO) Pin	
TXBnDm (Transmit Buffer n		Slave Select	
Data Field Byte m)	208	Slave Select Synchronization	
TXBnEIDH (Transmit Buffer n		Sleep Operation	
Extended Identifier, High Byte)	207	SPI Clock	
TXBnEIDL (Transmit Buffer n			
Extended Identifier, Low Byte)	208	SSPBUF Register	
TXBnSIDH (Transmit Buffer n		SSPSR RegisterSSPOV	
Standard Identifier, High Byte)	207		
TXBnSIDL (Transmit Buffer n		SSPOV Status Flag	173
Standard Identifier, Low Byte)	207	SSPSTAT Register	450 455
TXERRCNT (Transmit Error Count)		R/W Bit	
TXSTA (Transmit Status and Control)		SUBFWB	
WDTCON (Watchdog Timer Control)		SUBLW	
RESET		SUBWF	
Reset		SUBWFB	
MCLR Reset During Normal Operation		SWAPF	318
MCLR Reset During Sleep		Т	
Power-on Reset (POR)		•	
		Table Pointer Operations (table)	
Programmable Brown-out Reset (PBOR) RESET Instruction		TBLRD	
		TBLWT	320
Stack Full Reset		Timer0	
Stack Underflow Reset	-	16-bit Mode Timer Reads and Writes	
Watchdog Timer (WDT) Reset		Associated Registers	111
RETFIE		Operation	111
RETLUM	_	Overflow Interrupt	111
RETURN		Prescaler	111
Revision History		Prescaler. See Prescaler, Timer0.	
RLCF		Switching Prescaler Assignment	111
RLNCF		- -	
RRCF	314		
DDM:-F	215		

# PIC18FXX8

Timer1	113	Half-Bridge PWM Output	136
16-bit Read/Write Mode	115	I <sup>2</sup> C Bus Data	353
Associated Registers	116	I <sup>2</sup> C Bus Start/Stop Bits	
Operation		I <sup>2</sup> C Master Mode (Reception,	
Oscillator		7-bit Address)	175
Overflow Interrupt	•	I <sup>2</sup> C Master Mode (Transmission,	
Special Event Trigger (CCP)		7 or 10-bit Address)	174
Special Event Trigger (ECCP)		I <sup>2</sup> C Slave Mode (Transmission,	
TMR1H Register		10-bit Address)	161
TMR1L Register		I <sup>2</sup> C Slave Mode (Transmission,	
TMR3L Register		7-bit Address)	150
Timer2		I <sup>2</sup> C Slave Mode with SEN = 0 (Reception,	100
Associated Registers		10-bit Address)	160
Operation		I <sup>2</sup> C Slave Mode with SEN = 0 (Reception,	100
Postscaler. See Postscaler, Timer2.	117	7-bit Address)	150
PR2 Register	117 100	I <sup>2</sup> C Slave Mode with SEN = 1 (Reception,	130
	117, 120		105
Prescaler. See Prescaler, Timer2.	117 110	10-bit Address)	105
SSP Clock Shift			101
TMR2 Register		7-bit Address)	
TMR2 to PR2 Match Interrupt		Low-Voltage Detect	262
Timer3		Master SSP I <sup>2</sup> C Bus Data	
Associated Registers		Master SSP I <sup>2</sup> C Bus Start/Stop Bits	355
Operation		Parallel Slave Port (PIC18F248	
Oscillator		and PIC18F458)	
Overflow Interrupt		Parallel Slave Port Read	
Special Event Trigger (CCP)		Parallel Slave Port Write	
TMR3H Register		PWM Direction Change	139
Timing Conditions	342	PWM Direction Change at Near	
Load Conditions for Device		100% Duty Cycle	139
Timing Specifications	342	PWM Output	128
Temperature and Voltage		Repeated Start Condition	172
Specifications – AC	342	Reset, Watchdog Timer (WDT),	
Timing Diagrams		Oscillator Start-up Timer (OST),	
A/D Conversion	359	Power-up Timer (PWRT)	345
Acknowledge Sequence	176	Slave Mode General Call Address Sequence	
Baud Rate Generator with		(7 or 10-bit Address Mode)	166
Clock Arbitration	170	Slave Synchronization	
BRG Reset Due to SDA Arbitration		Slow Rise Time (MCLR Tied to VDD)	
During Start Condition	179	SPI Master Mode	
Brown-out Reset (BOR) and		SPI Master Mode Example (CKE = 0)	349
Low-Voltage Detect	345	SPI Master Mode Example (CKE = 1)	
Bus Collision During a Repeated		SPI Slave Mode (with CKE = 0)	
Start Condition (Case 1)	180	SPI Slave Mode (with CKE = 1)	
Bus Collision During a Repeated		SPI Slave Mode Example (CKE = 0)	
Start Condition (Case2)	180	SPI Slave Mode Example (CKE = 1)	
Bus Collision During a Stop		Stop Condition Receive or	
Condition (Case 1)	181	Transmit Mode	176
Bus Collision During a		Time-out Sequence on POR w/PLL Enabled	
Stop Condition (Case 2)	181	(MCLR Tied to VDD)	29
Bus Collision During		Time-out Sequence on Power-up	20
Start Condition (SCL = 0)	170	(MCLR Not Tied to VDD)	
Bus Collision During		Case 1	28
Start Condition (SDA Only)	170	Case 2	
Bus Collision for Transmit and	170	Time-out Sequence on Power-up	20
Acknowledge	177	(MCLR Tied to VDD)	20
	177	Timer0 and Timer1 External Clock	
Capture/Compare/PWM	0.47		340
(CCP1 and ECCP1)		Transition Between Timer1 and	00
CLKO and I/O		OSC1 (HS with PLL)	22
Clock Synchronization		Transition Between Timer1 and	
Clock/Instruction Cycle		OSC1 (HS, XT, LP)	21
External Clock		Transition Between Timer1 and	
First Start Bit		OSC1 (RC, EC)	22
Full-Bridge PWM Output	137		

	Transition from OSC1 to	
	Timer1 Oscillator	21
	USART Asynchronous Reception1	92
	USART Asynchronous Transmission 1	
	USART Asynchronous Transmission	
	(Back to Back)1	90
	USART Synchronous Receive	
	(Master/Slave)3	57
	USART Synchronous Reception	
	(Master Mode, SREN)1	95
	USART Synchronous Transmission	
	USART Synchronous Transmission	J-T
	(Master/Slave)3	57
	USART Synchronous Transmission	57
		04
	(Through TXEN)1	
	Wake-up from Sleep via Interrupt	
ımı	ng Diagrams and Specifications	
	A/D Conversion Requirements	
	A/D Converter Characteristics	58
	Capture/Compare/PWM Requirements	
	(CCP1 and ECCP1)3	47
	CLKO and I/O Timing	
	Requirements3	44
	Example SPI Mode Requirements	
	(Master Mode, CKE = 0)3	49
	Example SPI Mode Requirements	
	(Master Mode, CKE = 1)	50
	Example SPI Mode Requirements	
	(Slave Mode, CKE = 0)	51
	Example SPI Slave Mode	•
	Requirements (CKE = 1)	52
	External Clock Timing Requirements	
	I <sup>2</sup> C Bus Data Requirements	40
	(Slave Mode)	E 1
	l <sup>2</sup> C Bus Start/Stop Bits Requirements	54
	(Slave Mode)3	53
	Master SSP I <sup>2</sup> C Bus Data	
	Requirements3	56
	Master SSP I <sup>2</sup> C Bus Start/Stop Bits	
	Requirements3	55
	Parallel Slave Port Requirements	
	(PIC18F248 and PIC18F458)3	
	PLL Clock3	44
	Reset, Watchdog Timer, Oscillator	
	Start-up Timer, Power-up Timer,	
	Brown-out Reset and Low-Voltage	
	Detect Requirements3	45
	Timer0 and Timer1 External	
	Clock Requirements3	46
	USART Synchronous Receive	
	Requirements3	57
	USART Synchronous Transmission	
	Requirements3	57
ST	FSZ3	
	TA Register	_ '
7.0	BRGH Bit1	QΕ
	ום זוט זוט ווטווט ווט	υŰ

U	
USART	183
Asynchronous Mode	
Reception	
Setting Up 9-Bit Mode with	
Address Detect	191
Transmission	
Asynchronous Reception	
Asynchronous Transmission	
Associated Registers	190
Baud Rate Generator (BRG)	
Associated Registers	
Baud Rate Error, Calculating	
Baud Rate Formula	
Baud Rates for Asynchronous Mode	
(BRGH = 0)	187
Baud Rates for Asynchronous Mode	
(BRGH = 1)	188
Baud Rates for Synchronous Mode	
High Baud Rate Select (BRGH Bit)	
Sampling	
Serial Port Enable (SPEN) Bit	
Synchronous Master Mode	
Reception	195
Transmission	
Synchronous Master Reception	
Associated Registers	195
Synchronous Master Transmission	
Associated Registers	193
Synchronous Slave Mode	
Reception	
Transmission	
Synchronous Slave Reception	197
Synchronous Slave Transmission	
Associated Registers	197
V	
•	
Voltage Reference Specifications	340
W	
	~~ 4
Wake-up from Sleep	
Using Interrupts	
Watchdog Timer (WDT)	
Associated Registers	
Control Register	2/2
Postscaler	
Programming Considerations	
RC Oscillator	
Time-out Period	
WCOL Status Flog 171, 172, 173, 173, 174, 175, 175, 175, 175, 175, 175, 175, 175	
WCOL Status Flag	1/6
WDT. See Watchdog Timer.	_
WWW, On-Line Support	b
X	
XORLW	321
VODIVE	1

### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com, click on Customer Change Notification and follow the registration instructions.

### **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- Technical Support
- · Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://support.microchip.com

### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

To:	Technical Publications Manager	Total Pages Sent
RE:	Reader Response	
Fron	n: Name	
	Company	
	City / State / ZIP / Country	
	Telephone: ()	FAX: ()
Appl	lication (optional):	
Wou	ıld you like a reply?YN	
Devi	ice: PIC18FXX8	Literature Number: DS41159E
Que	stions:	
1. \	What are the best features of this doc	eument?
_		
_		
2. I	How does this document meet your h	ardware and software development needs?
-		
2 I	Do you find the organization of this do	pourment easy to follow? If not, why?
J. I	Do you lind the organization of this do	ocument easy to follow: If not, why:
-		
4. \	What additions to the document do yo	ou think would enhance the structure and subject?
_		
_		
5. \	What deletions from the document co	uld be made without affecting the overall usefulness?
-		
<u>-</u>		formation (what and wham)
6. I	Is there any incorrect or misleading in	formation (what and where)?
-		
7. I	How would you improve this documer	nt?
	· ·	
_		
_		

### PIC18FXX8 PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

Device	Temperat Range	•	 Pattern
Device	PIC18F448 VDD rang PIC18LF24 PIC18LF44	8/458T <sup>(2)</sup> ;	458 <sup>(1)</sup> , PIC18F248/258T <sup>(2)</sup> , 8/458 <sup>(1)</sup> , PIC18LF248/258T <sup>(2)</sup> ,
emperature Range	I = E =	-40°C to +85°C (Inc -40°C to +125°C (Ext	dustrial) tended)
ackage	PT = L = SO = SP = P =	SOIC Skinny Plastic DIP	Flatpack)
attern	QTP, SQTI (blank other	P, Code or Special Re erwise)	equirements

#### Examples:

- a) PIC18LF258-I/L 301 = Industrial temp., PLCC package, Extended VDD limits, QTP pattern #301.
- b) PIC18LF458-I/PT = Industrial temp., TQFP package, Extended VDD limits.
- c) PIC18F258-E/L = Extended temp., PLCC package, normal VDD limits.

Note 1: F = Standard Voltage Range

LF = Wide Voltage Range

2: T = in tape and reel PLCC and TQFP packages only.



### WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200

Fax: 480-792-7277 Technical Support:

http://support.microchip.com

Web Address: www.microchip.com

**Atlanta** 

Alpharetta, GA Tel: 770-640-0034 Fax: 770-640-0307

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Dallas

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Kokomo

Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara

Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

**Toronto** 

Mississauga, Ontario, Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

**Asia Pacific Office** 

Suites 3707-14, 37th Floor Tower 6, The Gateway Habour City, Kowloon Hong Kong

Tel: 852-2401-1200 Fax: 852-2401-3431

Australia - Sydney

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

China - Beijing

Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

China - Chengdu Tel: 86-28-8665-5511

Fax: 86-28-8665-7889

China - Fuzhou

Tel: 86-591-8750-3506 Fax: 86-591-8750-3521

China - Hong Kong SAR

Tel: 852-2401-1200 Fax: 852-2401-3431

China - Qingdao

Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

China - Shanghai Tel: 86-21-5407-5533

Fax: 86-21-5407-5066

China - Shenyang

Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

China - Shenzhen

Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

China - Shunde

Tel: 86-757-2839-5507 Fax: 86-757-2839-5571

China - Wuhan

Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

China - Xian

Tel: 86-29-8833-7250 Fax: 86-29-8833-7256

#### ASIA/PACIFIC

India - Bangalore

Tel: 91-80-4182-8400 Fax: 91-80-4182-8422

India - New Delhi

Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune

Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

Japan - Yokohama

Tel: 81-45-471-6166 Fax: 81-45-471-6122

Korea - Gumi

Tel: 82-54-473-4301 Fax: 82-54-473-4302

Korea - Seoul

Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Penang

Tel: 60-4-646-8870 Fax: 60-4-646-5086

Philippines - Manila

Tel: 63-2-634-9065 Fax: 63-2-634-9069

Singapore Tel: 65-6334-8870

Fax: 65-6334-8850 Taiwan - Hsin Chu

Tel: 886-3-572-9526 Fax: 886-3-572-6459

Taiwan - Kaohsiung Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan - Taipei

Tel: 886-2-2500-6610 Fax: 886-2-2508-0102 Thailand - Bangkok

Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### **EUROPE**

Austria - Wels

Tel: 43-7242-2244-3910 Fax: 43-7242-2244-393 Denmark - Copenhagen Tel: 45-4450-2828

Fax: 45-4485-2829

France - Paris

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany - Munich

Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen

Tel: 31-416-690399 Fax: 31-416-690340

Spain - Madrid

Tel: 34-91-708-08-90 Fax: 34-91-708-08-91 **UK - Wokingham** 

Tel: 44-118-921-5869 Fax: 44-118-921-5820

08/29/06