

5ch System Motor Driver

BD8203EFV

General Description

BD8203EFV is a 5ch system motor driver for CD/DVD. A linear BTL mode can be adopted for all 5ch to reduce noise. It has a Built-in 5V regulator, a changeable regulator, and a general-purpose operational amplifier. Designed best for car audio systems.

Features

- Linear BTL method is implemented for the actuator driver and the DC motor driver to reduce noise.
- Loading driver 1ch
- Built-in regulator 2ch (1ch output changeable)
- MUTE function and Standby function
- Built-in general-purpose operational amplifier 1ch
- Built-in internal operational amplifier for the voltage detection between driver outputs and for VC standard

Applications


Car Audio

Key Specifications


- Power Supply Voltage Range:
 Driver Part Pre Steps and Regulator1 7.5V to 14V
 Driver Part Power Steps 4.5V to VPREVCC V
 Power Steps of Two Regulators 4.5V to VPREVCC V
- Standby-on Current: 1mA(Max)
 Operating Temperature Range: -40°C to +85°C

Package


W(Typ) x D(Typ) x H(Max)



Typical Application Circuit



Block Diagram and Pin Configuration



Pin Description

n Des	cription				
No.	Symbol	Description	No.	Symbol	Description
1	SGND	Signal GND	21	IN4	CH4(SPDL)input
2	REG5	REG5V Output	22	IN3	CH3(SLD)input
3	PREVCC	PRE part, REG circuit, power supply terminal(+8V)	23	IN2	CH2(TRK)input
4	PVCC1	Power supply 1	24	IN1	CH1(FCS) input
5	PGND	Power GND	25	VCO	Standard voltage (VC) output
6	VO1+	CH1(FCS) Positive output	26	VCI	Standard voltage (VC) input
7	VO1-	CH1(FCS) Negative output	27	VSPDL	Voltage detection value output between VO4 outputs
8	VO2+	CH2(TRK) Positive output	28	OPIN+	General purpose Op Amp non-reversing input
9	VO2-	CH2(TRK) Negative output	29	OPIN-	General purpose Op Amp reversing input
10	VO3+	CH3(SLD) Positive output	30	OPOUT	General purpose Op Amp output
11	VO3-	CH3(SLD) Negative output	31	SGND	Signal GND
12	VO4+	CH4(SPDL) Positive output	32	SGND	Signal GND
13	VO4-	CH4(SPDL) Negative output	33	MUTE123	MUTE CH1,2,3
14	VO5+	CH5(LOAD) Positive output	34	MUTE4	MUTE CH4(SPDL)
15	VO5-	CH5(LOAD) Negative output	35	TSDM	Thermal shutdown flag output
16	PGND	Power GND	36	REGRST	REG Reset input
17	PVCC2	Power supply 2	37	REGCTL	REGVAR Output changeability input terminal
18	VCTL	CH5(LOAD) Voltage control input	38	REGVARVCC	REGVAR Tr power supply terminal
19	FWD	CH5(LOAD) FWD input	39	REGVAR	REGVAR output
20	RVS	CH5(LOAD) RVS input	40	SGND	Signal GND

Absolute Maximum Ratings (Ta=25°C)

Parameter	Symbol	Limit	Unit
Power Supply Voltage	Vprevcc, Vpvcc1, Vpvcc2, Vregvarvcc	15	V
Input Terminal Voltage1	V _{IN1} (Note 1)	VPREVCC	V
Input Terminal Voltage2	V _{IN2} (Note 2)	V _{REG5}	V
Output Terminal Voltage	V _{OUT} (Note 3)	V_{REG5}	V
Operating Temperature Range	Topr	-40 to +85	°C
Storage Temperature	Tstg	-55 to +150	°C
Junction Temperature	Tjmax	150	°C
Power Dissipation	Pd (Note 4)	4.7	W

(Note 1) Input terminal 1 : REGRST (Note 2) Input terminal 2 : REGCTL, MUTE123, MUTE4, VCI, RVS, FWD, IN1, IN2, IN3, IN4, OPIN+, OPIN-, VCTL (Note 3) Output terminal : VCO, TSDM, VSPDL

(Note 4) Ta =25°C, Standard board mounting

(70mm x 70mm x 1.6mm, 4 glass epoxy layer substrate, 70mm x 70mm of the back copper foil area)

Reduce power by 34.6mW for each degree above 25°C.

Caution: Operating the IC over the absolute maximum ratings may damage the IC. The damage can either be a short circuit between pins or an open circuit between pins and the internal circuitry. Therefore, it is important to consider circuit protection measures, such as adding a fuse, in case the IC is operated over the absolute maximum ratings.

Recommended Operating Conditions (Ta=-40°C to +85°C)

(Set the power supply voltage taking allowable dissipation into considerations.)

Parameter	Symbol	Min	Тур	Max	Unit
Driver Part Pre Steps and Regulator 1 Power-Supply Voltage	VPREVCC	7.5	8	14	٧
Driver Part Power Steps Power-Supply Voltage	VPVCC1, VPVCC2	4.5	8	VPREVCC	٧
Power Steps of Two Regulators Power-Supply Voltage	VREGVARVCC	4.5	5	VPREVCC	V

Electrical Characteristics

(Unless otherwise specified, VPREVCC=VPVCC1=VPVCC2=8V, VREGVARVCC=5V, VVCO=1.65V, Ta=25°C)

Parameter		Symbol	MIN	TYP	MAX	Unit	Conditions
Circuit Current	Quiescent Current	lq	-	37	55	mA	MUTE123=MUTE4=H, FWD=RVS=L
	Standby-on Current	I _{STBY}	-	-	1	mA	Standby mode(REGRST = L)
	Input Offset Voltage	VIOBTL	-5	0	+5	mV	
	Output Offset Voltage	Vofbtl	-75	-	+75	mV	
BTL Driver	Output Saturation Voltage (Vertical Harmony)	Vosatbtl	-	1.5	2.3	V	I _L =500mA
	Input Output Gain	G_{VBTL}	16.8	18	19.2	dB	
	Input Impedance	RZINBTL	20	40	80	kΩ	
	Slew Rate	V _{SLBTL}	1.0	-	-	V/µs	
	Input Offset Voltage	V _{IOOP1}	-10	-	+10	mV	
	Input Bias Voltage	I _{BOP1}	-300	-	-	nA	
	H Level Output Voltage	V _{OHOP1}	4	-	-	V	
General-purpose	L Level Output Voltage	V _{OLOP1}	-	-	0.2	V	
Operational Amplifier	Output Sink Current Ability	ISINKOP1	2	-	-	mA	
•	Output Source Current Ability	I _{SOUOP1}	2	-	-	mA	
	Range of Same Phase Input	V _{ICMOP1}	0		3.8	V	V _{REG5} =5.0V
	Slew Rate	V _{SLOP1}	0.5	-	-	V/µs	


Electrical Characteristics – continued

(Unless otherwise specified, VPREVCC=VPVCC1=VPVCC2=8V, VREGVARVCC=5V, VVC0=1.65V, Ta=25°C)

(Unless otherwi	se specified, V _{PREVCC} =V _{PVCC1} =V _F						
	Parameter	Symbol	MIN	TYP	MAX	Unit	Conditions
	Output Offset Voltage	V000P2	-50	-	+50	mV	V _{VO4+} = V _{VO4-} = 3.4V
Operational	H Level Output Voltage	V _{OHOP2}	4	-	-	V	
Amplifier for the	L Level Output Voltage	V _{OLOP2}	-	-	0.2	V	
Voltage	Output Sink Current Ability	ISINKOP2	2	-	-	mA	
Detection between	Output Source Current Ability	I _{SOUOP2}	2	-	-	mA	
Driver Outputs	Range of Same Phase Input	VICMOP2	0		6.8	V	V _{REG5} =5.0V
	Input Output Gain	G _{VOP2}	-6.2	-5	-3.8	dB	
	Slew Rate	V _{SLOP2}	0.5	-	-	V/µs	
	Output Offset Voltage	V000P3	-10	-	+10	mV	
	Input Bias Voltage	І ворз	-300	-	-	nA	
Internal	H level Output Voltage	V _{OHOP3}	3.5	-	-	V	
Operational	L level Output Voltage	V _{OLOP3}	-	-	0.2	V	
Amplifier for VC Standard	Output Sink Current Ability	ISINKOP3	0.5	-	-	mA	
	Output Source Current Ability	I _{SOUOP3}	10	-	-	mA	
	Range of Same Phase Input	V _{ICMOP3}	1.1	-	3.5	V	V _{REG5} =5.0V BTL range of operation
	Input Terminal Inflow Current	I _{INLD}	-	27	55	μΑ	V _{FWD} ,V _{RVS} =3.3V
	VCTL Terminal Inflow Current	INVCTL	-1	-	-	μA	V _{VCTL} =2V
Loading Driver	Output Offset Voltage	Vofld	-50	0	+50	mV	
Loading Driver	Output Saturation Voltage H	Vohld	-	1.1	1.4	V	I _L =500mA
	Output Saturation Voltage L	Volld	-	0.45	0.8	V	IL=500mA
	Input Output Gain	GVLD	7.5	9.0	10.5	dB	V _{VCTL} =1V
	REG5 Terminal Output Voltage	Voreg5	4.75	5.0	5.25	V	I _L =100mA
Regulator 1	REG5 Terminal Output Current Ability	I _{REG5_I}	100	-	-	mA	
	Load Change Regulation	$V_{\text{REG5_LOAD}}$	-80	-	-	mV	I _L =0mA to 100mA
	Input Change Regulation	V _{REG5_LINE}	-20	-	+30	mV	VPREVCC=7.5V to 9V, IL=100mA
	Range of REGVAR Output Voltage Setting	Vregvarr	0.5	-	4.1	V	I _L =100mA
	REGVAR Terminal Output Current Ability	I _{REGVAR_I}	100	-	-	mA	
D 11 0	REGVAR Terminal Output Voltage	VREGVAR	3.4	3.6	3.8	V	IL=100mA,VREGCTL=3.3V
Regulator 2 (Output	Input Output Gain	G _{V2}	-	1.09	-	V/V	
Changeability)	Load Change Regulation Input Change Regulation	VREGVAR_LOAD VREGVAR_LINE	-80 -20	-	+30	mV mV	IL=0mA to 100mA VREGCTL=3.3V, VREGVARVCC=4.5V to 5.5V,
	Range of REGVARVCC Voltage	V _{REGVAR_ON}	V _{REGVAR} +0.9V	-	V _{PREVCC}	V	I _L =100mA
	REGCTL Terminal Input Current	IREGCTL_I	-1	-	-	μA	VREGCTL=3.3V
	Input Voltage of Input Terminal H	VIHFUN	2.0	-	VPREVCC	V	MUTE123,MUTE4,RVS,FWD
	Input Voltage of Input Terminal L	VILFUN	-	-	0.8	V	MUTE123,MUTE4,RVS,FWD
	TSDM Terminal L Output Voltage	V _{OL_TSDM}	-	-	0.4	V	R _{TSDM} =33kΩ Pull-up3.3V
- <i>.</i> :	VCO Drop Mute Voltage	VMVco	0.4	0.7	1	V	
Function	PREVCC Drop Mute Voltage	VMPREVcc	3.4	3.8	4.2	V	
	REGRST Terminal Reset ON Voltage	V _{RESON1}	-	-	0.8	V	Turning OFF of regulator 1 and regulator 2
	REGRST Terminal Reset OFF Voltage	VRESOFF	2.0	-	VPREVCC	V	Turning ON of regulator 1 and regulator 2

Application Information

1. Standard Example Application Circuit



Functional Description

Table for operation (VPREVCC=VPVCC1=VPVCC2=8V, VREGVARVCC=5V, VVC0=1.65V)

	Input					Output					
REGRST	MUTE123	MUTE4	FWD	RVS	REG5	REGVAR	Operational amplifier	VO1 to VO3	VO4	VO5	
Low	-	-	-	-	STANDBY	STANDBY	STANDBY	STANDBY	STANDBY	STANDBY	
High	Low	Low	-	ı	ON	ON	ON	OFF	OFF		
High	High	Low	-	-	ON	ON	ON	ON	OFF		
High	Low	High		-	ON	ON	ON	OFF	ON		
High	High	High	-	-	ON	ON	ON	ON	ON		
High		-	Low	Low	ON	ON	ON			OFF	
High	-	-	High	Low	ON	ON	ON			Forward	
High	-	-	Low	High	ON	ON	ON			Reverse	
High	1	-	High	High	ON	ON	ON			Brake	

(1) BTL Driver Control

BTL driver's ON/OFF can control with MUTE123 and MUTE4 terminal.

Input		Output made	VO1(FCS), VO2(TRK),	\/O4/CDDL\		
REGRST	MUTE123	MUTE4	Output mode	VO3(SLD)	VO4(SPDL)	
Low	-	-	STANDBY	Hi-Z	Hi-Z	
High	Low	Low	ALL OFF	Hi-Z(M) (Note 1)	Hi-Z(M) (Note 1)	
High	High	Low	FCS, TRK, SLD,	ON	Hi-Z(M) (Note 1)	
High	Low	High	SPDL ON	Hi-Z(M) (Note 1)	ON	
High	High	High	ALL ON	ON	ON	

(Note 1) V_{VO1+} = V_{VO1-} = V_{PVCC1}/2 [V] (Typ), V_{VO2+} = V_{VO2-} = V_{PVCC1}/2 [V] (Typ)

 $V_{VO3+} = V_{VO3-} = (V_{PVCC2}-0.7)/2 [V] (Typ),$

 $V_{VO4+} = V_{VO4-} = [[(V_{PVCC2}-0.7)/2] \times 15.6 + V_{VCO} \times 20] / (15.6 + 20) [V] (Typ) at Hi-Z(M).$

(Example) $V_{VO4+} = V_{VO4-} \approx 2.53 \text{ [V](Typ)}$ at $V_{PVCC2}=8[V], V_{VCO}=1.65[V]$

(2) Loading Driver

High

Only VCTL, FWD, and RVS terminal individually controls the load. (This is not controlled by turning ON/OFF the MUTE123 and MUTE4 terminal) It operates according to the truth table below.

Input Voltage Output between VO5+(Pin14) VO5-(Pin15) mode REGRST VCTL(Pin18) FWD(Pin19) RVS(Pin20) outputs Low STANDBY 0 Hi-Z Hi-Z (Note 2) Hi-Z(M)(Note 3) Hi-Z(M)(Note 3) High L L **OFF** 0 (Note 2) High Н Forward G_{VLD} x V_{CTL} Т Н 1 (Note 2) L Н G_{VLD} x V_{CTL} Н High Reverse

Brake


Н

(Note 2) VCTL (Pin18) is an arbitrary value of 0- REG5 (= 5.0[V](Typ)).


Н

(Note 3) $V_{VO5+} = V_{VO5-} = (V_{PVCC2}-0.7)/2[V]$ (Typ) at Hi-Z(M). (Note 4) $V_{VO5+} = V_{VO5-} = (V_{PVCC2}-0.7)/2[V]$ (Typ) at M.

(Note 2)



When Forward mode is set




M (Note 4)

M (Note 4)

0

When Reverse mode is set

(3) 5V Regulator 1




(a) Regulator 1 Control


ON/OFF of regulator 1 can be controlled by REGRST terminal.

REGRST	Regulator 1		
Low	OFF		
High	ON		


(b) Vcc - Vout Characteristic



(c) Timing Chart



(4) 3.6V Changeable Regulator 2




(a) Regulator 2 Controls

ON/OFF of regulator 2 can be controlled by REGRST terminal.

REGRST	Regulator 2
Low	OFF
High	ON


(b) Vcc - Vout Characteristics




(c) VREGCTL - VOUT Characteristic

REGVAR can be set through REGCTL terminal.


The range of REGVAR of the output voltage setting is 0.5-4.1V (At VREGVARVCC=5V (Typ)).



(d) Timing Chart




(5) OPAMP for the Voltage Detection between Driver Outputs




The voltage difference between VO4+, VO4- of the BTL driver for VSPDL is measured and outputted to VSPDL terminal.

$$V_{VSPDL} = \frac{5600}{10k} \ \left(V_{VO4-} - V_{VO4+} \right) + V_{VC}$$



(6) Thermal Shutdown Flag Output Function TSDM = Hi-Z (normal operation)

When thermal shutdown is activated, TSDM terminal becomes Low, all driver outputs (VO1-VO5) and regulator outputs (REG5, REGVAR) are turned OFF (output Hi-Z).



Thermal shutdown	TSDM
OFF	Hi-Z
ON	Low

(7) Power Supply Drop Mute and VC Drop Mute Function


Power supply drop mute functions at VPREVCC<VMPREVCC(3.8V Typ). At this condition all driver outputs (VO1-VO5) are turned OFF (output Hi-Z).

VC drop mute functions at V_{VCO}<V_{MVCO}(0.7V Typ). At this condition driver outputs (VO1-VO4) also are turned OFF (output Hi-Z).

Mute function list (REGRST=MUTE123=MUTE4=FWD=High at the mode state of turning ON)

mate rameticm net	vate ranous interpretation of the residence in the residence of the range of the range of the range of the residence of the range of th					
Thermal shutdown	PREVCC	VCO	REG5,REGVAR	VO1 to VO4	VO5	
OFF	> V _{MPREVCC}	> V _{MVCO}	ON	ON	ON	
ON	-	-	OFF	OFF	OFF	
OFF	< V _{MPREVCC}	-	ON	OFF	OFF	
OFF	> V _{MPREVCC}	< V _{MVCO}	ON	OFF	ON	

(8) Start-up Sequence Regulations



Terminal \times where the destination of hanging the diode on the power supply side is REG5 must defend the above-mentioned sequence so as not to impress the voltage more than the voltage of REG5 terminal.

Please insert in the cereal and use the limit resistance for the terminal when you impress the voltage more than the voltage of REG5 terminal.


(Limit resistance 10kO or more is inserted in the cereal about REGCTL terminal.)

(Limit resistance 10kO or more is inserted in the cereal about REGCTL terminal. **Terminal where destination of hanging diode on power supply side is REG5


REGCTL, MUTE123, MUTE4, VCI, RVS, FWD, IN1, IN2, IN3, IN4, OPIN+, OPIN-, VCTL

Method of Calculating Gain

(a) Loading




(b) Focus, Tracking, Sled, Spindle



- Noise Measures
 - The cause of PWM driver's noise is the following.
 - A. Noise from VCC and GND line
 - B. Radiation noise

Measures of A

- ① Because a high current is generated by the PWM, Lower wiring impedance at driver's power supply (PVCC) and GND line (PGND) is recommended. This can be achieved by separating the power supply line of other devices from the main supply to eliminate the common impedance, and connecting it to another line.
- ② Use electrolytic capacitor with low ESR to power supply pin (PVCC1, PVCC2, PREVCC) of drivers and GND pin (PGND) to make it stable. Please connect the ceramic capacitor with a high frequency characteristic directly to the pin (or as close as possible to the IC).



3 There is a method of inserting LC filter in the power supply line or GND line, when the first two measures are not sufficient to solve the noise problem.

(Example)




Figure 1. LC Filter Chart

④ In addition, there is a technique of adding a capacitor of about 2200pF (arbitrary capacitance) between each output and GND in the PWM driver. In this case, the wiring for GND must not be common with other signals.







Figure 2. Snubber Circuit

3. ASO


Pin 6 to Pin 15 ASO Data (TON = 0.1sec) $V_{PREVCC} = V_{PVCC1} = V_{PVCC2} = 15V$ $Ta = 25^{\circ}C$









I/O Equivalent Circuits



I/O Equivalent Circuit - continued




I/O Equivalent Circuit - continued



Pin Name	Equivalent-Circuit Diagram of the Terminals
IN1, 2, 3, 4	PREVCC PR
OPIN + -	PREG5 REG5 SGND REG5 REG5 SGND SGND SGND
OPOUT	REG5 REG5 OPOUT SGND SGND

I/O Equivalent Circuit - continued



(Note) Resistance in the above-mentioned equivalent-circuit diagram of the terminals is 25°C, and a value at typical.

Operational Notes

1. Reverse Connection of Power Supply

Connecting the power supply in reverse polarity can damage the IC. Take precautions against reverse polarity when connecting the power supply, such as mounting an external diode between the power supply and the IC's power supply pins.

2. Power Supply Lines

Design the PCB layout pattern to provide low impedance supply lines. Separate the ground and supply lines of the digital and analog blocks to prevent noise in the ground and supply lines of the digital block from affecting the analog block. Furthermore, connect a capacitor to ground at all power supply pins. Consider the effect of temperature and aging on the capacitance value when using electrolytic capacitors.

3. Ground Voltage

Ensure that no pins are at a voltage below that of the ground pin at any time, even during transient condition.

4. Ground Wiring Pattern

When using both small-signal and large-current ground traces, the two ground traces should be routed separately but connected to a single ground at the reference point of the application board to avoid fluctuations in the small-signal ground caused by large currents. Also ensure that the ground traces of external components do not cause variations on the ground voltage. The ground lines must be as short and thick as possible to reduce line impedance.

5. Thermal Consideration

Should by any chance the power dissipation rating be exceeded the rise in temperature of the chip may result in deterioration of the properties of the chip. In case of exceeding this absolute maximum rating, increase the board size and copper area to prevent exceeding the Pd rating.

6. Recommended Operating Conditions

These conditions represent a range within which the expected characteristics of the IC can be approximately obtained. The electrical characteristics are guaranteed under the conditions of each parameter.

7. Inrush Current

When power is first supplied to the IC, it is possible that the internal logic may be unstable and inrush current may flow instantaneously due to the internal powering sequence and delays, especially if the IC has more than one power supply. Therefore, give special consideration to power coupling capacitance, power wiring, width of ground wiring, and routing of connections.

8. Operation Under Strong Electromagnetic Field

Operating the IC in the presence of a strong electromagnetic field may cause the IC to malfunction.

9. Testing on Application Boards

When testing the IC on an application board, connecting a capacitor directly to a low-impedance output pin may subject the IC to stress. Always discharge capacitors completely after each process or step. The IC's power supply should always be turned off completely before connecting or removing it from the test setup during the inspection process. To prevent damage from static discharge, ground the IC during assembly and use similar precautions during transport and storage.

10. Inter-pin Short and Mounting Errors

Ensure that the direction and position are correct when mounting the IC on the PCB. Incorrect mounting may result in damaging the IC. Avoid nearby pins being shorted to each other especially to ground, power supply and output pin. Inter-pin shorts could be due to many reasons such as metal particles, water droplets (in very humid environment) and unintentional solder bridge deposited in between pins during assembly to name a few.

11. Unused Input Pins

Input pins of an IC are often connected to the gate of a MOS transistor. The gate has extremely high impedance and extremely low capacitance. If left unconnected, the electric field from the outside can easily charge it. The small charge acquired in this way is enough to produce a significant effect on the conduction through the transistor and cause unexpected operation of the IC. So unless otherwise specified, unused input pins should be connected to the power supply or ground line.

Operational Notes - continued

12. Regarding the Input Pin of the IC

This monolithic IC contains P+ isolation and P substrate layers between adjacent elements in order to keep them isolated. P-N junctions are formed at the intersection of the P layers with the N layers of other elements, creating a parasitic diode or transistor. For example (refer to figure below):

When GND > Pin A and GND > Pin B, the P-N junction operates as a parasitic diode. When GND > Pin B, the P-N junction operates as a parasitic transistor.

Parasitic diodes inevitably occur in the structure of the IC. The operation of parasitic diodes can result in mutual interference among circuits, operational faults, or physical damage. Therefore, conditions that cause these diodes to operate, such as applying a voltage lower than the GND voltage to an input pin (and thus to the P substrate) should be avoided.




Figure 3. Example of monolithic IC structure

13. Area of Safe Operation (ASO)

Operate the IC such that the output voltage, output current, and power dissipation are all within the Area of Safe Operation (ASO).

14. Thermal Shutdown Circuit(TSD)

This IC has a built-in thermal shutdown circuit that prevents heat damage to the IC. Normal operation should always be within the IC's power dissipation rating. If however the rating is exceeded for a continued period, the junction temperature (Tj) will rise which will activate the TSD circuit that will turn OFF all output pins. When the Tj falls below the TSD threshold, the circuits are automatically restored to normal operation.

Note that the TSD circuit operates in a situation that exceeds the absolute maximum ratings and therefore, under no circumstances, should the TSD circuit be used in a set design or for any purpose other than protecting the IC from heat damage.


15. Capacitor Between Output and Ground

If a large capacitor is connected between the output pin and ground pin, current from the charged capacitor can flow into the output pin and may destroy the IC when the VCC or IN pin is shorted to ground or pulled down to 0V. Use a capacitor smaller than $0.1\mu F$ between output and ground.


16. About the capacitor between the outputs

The output current increases with reference to the change between the outputs when the capacitor is connected between the driver outputs. Therefore, please add bypass capacitor $(0.1\mu F)$ as nearest as possible to the power supply (PVCC) and GND(PGND) of this IC as the route of the output current. Please select the value of the capacitor which will have no effect on the IC's normal characteristics, it is possible to pull out capacity at the low temperature happening to the electrolytic capacitor more than the capacity value of the capacitor between the outputs.

Ordering Information



Marking Diagram



Physical Dimension Tape and Reel Information Package Name HTSSOP-B40 13. 6 ± 0.1 (MAX13.95 include.BURR) (8.4)Ç 8±0. 4 ± 0 . $2\pm0.$ 3 0 0.625 1PIN MARK 0. $17^{+0.05}_{-0.03}$ 0.5 0 2 0. $24^{+0.05}_{-0.04} \oplus 0.08$ 85±0. 08±0. 0.65 □ 0. 08 S (UNIT:mm) 0 PKG: HTSSOP-B40 Drawing No. EX194-5002-2 <Tape and Reel information> Tape Embossed carrier tape (with dry pack) Quantity 2000pcs Direction The direction is the 1pin of product is at the upper left when you hold of feed reel on the left hand and you pull out the tape on the right hand Direction of feed *Order quantity needs to be multiple of the minimum quantity

Revision History

Date	Revision	Changes	
04.Nov.2015	001	New Release	

Notice

Precaution on using ROHM Products

1. Our Products are designed and manufactured for application in ordinary electronic equipments (such as AV equipment, OA equipment, telecommunication equipment, home electronic appliances, amusement equipment, etc.). If you intend to use our Products in devices requiring extremely high reliability (such as medical equipment (Note 1), transport equipment, traffic equipment, aircraft/spacecraft, nuclear power controllers, fuel controllers, car equipment including car accessories, safety devices, etc.) and whose malfunction or failure may cause loss of human life, bodily injury or serious damage to property ("Specific Applications"), please consult with the ROHM sales representative in advance. Unless otherwise agreed in writing by ROHM in advance, ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of any ROHM's Products for Specific Applications.

(Note1) Medical Equipment Classification of the Specific Applications

JAPAN	USA	EU	CHINA
CLASSⅢ	CL ACCIII	CLASSIIb	CLASSIII
CLASSIV	CLASSⅢ	CLASSⅢ	

- 2. ROHM designs and manufactures its Products subject to strict quality control system. However, semiconductor products can fail or malfunction at a certain rate. Please be sure to implement, at your own responsibilities, adequate safety measures including but not limited to fail-safe design against the physical injury, damage to any property, which a failure or malfunction of our Products may cause. The following are examples of safety measures:
 - [a] Installation of protection circuits or other protective devices to improve system safety
 - [b] Installation of redundant circuits to reduce the impact of single or multiple circuit failure
- 3. Our Products are designed and manufactured for use under standard conditions and not under any special or extraordinary environments or conditions, as exemplified below. Accordingly, ROHM shall not be in any way responsible or liable for any damages, expenses or losses arising from the use of any ROHM's Products under any special or extraordinary environments or conditions. If you intend to use our Products under any special or extraordinary environments or conditions (as exemplified below), your independent verification and confirmation of product performance, reliability, etc, prior to use, must be necessary:
 - [a] Use of our Products in any types of liquid, including water, oils, chemicals, and organic solvents
 - [b] Use of our Products outdoors or in places where the Products are exposed to direct sunlight or dust
 - [c] Use of our Products in places where the Products are exposed to sea wind or corrosive gases, including Cl₂, H₂S, NH₃, SO₂, and NO₂
 - [d] Use of our Products in places where the Products are exposed to static electricity or electromagnetic waves
 - [e] Use of our Products in proximity to heat-producing components, plastic cords, or other flammable items
 - [f] Sealing or coating our Products with resin or other coating materials
 - [g] Use of our Products without cleaning residue of flux (even if you use no-clean type fluxes, cleaning residue of flux is recommended); or Washing our Products by using water or water-soluble cleaning agents for cleaning residue after soldering
 - [h] Use of the Products in places subject to dew condensation
- 4. The Products are not subject to radiation-proof design.
- 5. Please verify and confirm characteristics of the final or mounted products in using the Products.
- 6. In particular, if a transient load (a large amount of load applied in a short period of time, such as pulse. is applied, confirmation of performance characteristics after on-board mounting is strongly recommended. Avoid applying power exceeding normal rated power; exceeding the power rating under steady-state loading condition may negatively affect product performance and reliability.
- 7. De-rate Power Dissipation depending on ambient temperature. When used in sealed area, confirm that it is the use in the range that does not exceed the maximum junction temperature.
- 8. Confirm that operation temperature is within the specified range described in the product specification.
- 9. ROHM shall not be in any way responsible or liable for failure induced under deviant condition from what is defined in this document.

Precaution for Mounting / Circuit board design

- 1. When a highly active halogenous (chlorine, bromine, etc.) flux is used, the residue of flux may negatively affect product performance and reliability.
- 2. In principle, the reflow soldering method must be used on a surface-mount products, the flow soldering method must be used on a through hole mount products. If the flow soldering method is preferred on a surface-mount products, please consult with the ROHM representative in advance.

For details, please refer to ROHM Mounting specification

Precautions Regarding Application Examples and External Circuits

- 1. If change is made to the constant of an external circuit, please allow a sufficient margin considering variations of the characteristics of the Products and external components, including transient characteristics, as well as static characteristics.
- 2. You agree that application notes, reference designs, and associated data and information contained in this document are presented only as guidance for Products use. Therefore, in case you use such information, you are solely responsible for it and you must exercise your own independent verification and judgment in the use of such information contained in this document. ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of such information.

Precaution for Electrostatic

This Product is electrostatic sensitive product, which may be damaged due to electrostatic discharge. Please take proper caution in your manufacturing process and storage so that voltage exceeding the Products maximum rating will not be applied to Products. Please take special care under dry condition (e.g. Grounding of human body / equipment / solder iron, isolation from charged objects, setting of lonizer, friction prevention and temperature / humidity control).

Precaution for Storage / Transportation

- 1. Product performance and soldered connections may deteriorate if the Products are stored in the places where:
 - [a] the Products are exposed to sea winds or corrosive gases, including Cl2, H2S, NH3, SO2, and NO2
 - [b] the temperature or humidity exceeds those recommended by ROHM
 - [c] the Products are exposed to direct sunshine or condensation
 - [d] the Products are exposed to high Electrostatic
- Even under ROHM recommended storage condition, solderability of products out of recommended storage time period
 may be degraded. It is strongly recommended to confirm solderability before using Products of which storage time is
 exceeding the recommended storage time period.
- 3. Store / transport cartons in the correct direction, which is indicated on a carton with a symbol. Otherwise bent leads may occur due to excessive stress applied when dropping of a carton.
- 4. Use Products within the specified time after opening a humidity barrier bag. Baking is required before using Products of which storage time is exceeding the recommended storage time period.

Precaution for Product Label

QR code printed on ROHM Products label is for ROHM's internal use only.

Precaution for Disposition

When disposing Products please dispose them properly using an authorized industry waste company.

Precaution for Foreign Exchange and Foreign Trade act

Since concerned goods might be fallen under listed items of export control prescribed by Foreign exchange and Foreign trade act, please consult with ROHM in case of export.

Precaution Regarding Intellectual Property Rights

- 1. All information and data including but not limited to application example contained in this document is for reference only. ROHM does not warrant that foregoing information or data will not infringe any intellectual property rights or any other rights of any third party regarding such information or data.
- 2. ROHM shall not have any obligations where the claims, actions or demands arising from the combination of the Products with other articles such as components, circuits, systems or external equipment (including software).
- 3. No license, expressly or implied, is granted hereby under any intellectual property rights or other rights of ROHM or any third parties with respect to the Products or the information contained in this document. Provided, however, that ROHM will not assert its intellectual property rights or other rights against you or your customers to the extent necessary to manufacture or sell products containing the Products, subject to the terms and conditions herein.

Other Precaution

- 1. This document may not be reprinted or reproduced, in whole or in part, without prior written consent of ROHM.
- 2. The Products may not be disassembled, converted, modified, reproduced or otherwise changed without prior written consent of ROHM.
- In no event shall you use in any way whatsoever the Products and the related technical information contained in the Products or this document for any military purposes, including but not limited to, the development of mass-destruction weapons.
- The proper names of companies or products described in this document are trademarks or registered trademarks of ROHM, its affiliated companies or third parties.

Notice-PGA-E Rev.002

General Precaution

- 1. Before you use our Products, you are requested to care fully read this document and fully understand its contents. ROHM shall not be in an y way responsible or liable for failure, malfunction or accident arising from the use of a ny ROHM's Products against warning, caution or note contained in this document.
- 2. All information contained in this docume nt is current as of the issuing date and subject to change without any prior notice. Before purchasing or using ROHM's Products, please confirm the latest information with a ROHM sale s representative.
- 3. The information contained in this doc ument is provided on an "as is" basis and ROHM does not warrant that all information contained in this document is accurate an d/or error-free. ROHM shall not be in an y way responsible or liable for any damages, expenses or losses incurred by you or third parties resulting from inaccuracy or errors of or concerning such information.

Notice – WE © 2015 ROHM Co., Ltd. All rights reserved. Rev.001



BD8203EFV - Web Page

Distribution Inventory

Part Number	BD8203EFV
Package	HTSSOP-B40
Unit Quantity	2000
Minimum Package Quantity	2000
Packing Type	Taping
Constitution Materials List	inquiry
RoHS	Yes