# HITACHI

KAOHSIUNG HITACHI **ELECTRONICS CO.,LTD** P.O. BOX 26-27 2,13TH EAST ST. K.E.P.Z. KAOHSIUNG TAIWAN R.O.C. TEL:(07) 821-5811 (7 LINE) FAX:(07) 821-5815

FOR	MESSRS:	
rur.	MESSINS.	

DATE: May.13,2008

# CUSTOMER'S ACCEPTANCE SPECIFICATIONS TX20D17VM2BBA

CONTENTS

No.	ITEM	SHEET No.	PAGE
1	COVER	7B64PS 2701- TX20D17VM2BBA-2	1-1/1
2	RECORD OF REVISION	7B64PS 2702- TX20D17VM2BBA-2	2-1/1
3	GENERAL DATA	7B64PS 2703- TX20D17VM2BBA-2	3-1/1
4	ABSOLUTE MAXIMUM RATINGS	7B64PS 2704- TX20D17VM2BBA-2	4-1/2~2/2
5	ELECTRICAL CHARACTERISTICS	7B64PS 2705- TX20D17VM2BBA-2	5-1/3~3/3
6	OPTICAL CHARACTERISTICS	7B64PS 2706- TX20D17VM2BBA-2	6-1/2~2/2
7	BLOCK DIAGRAM	7B64PS 2707- TX20D17VM2BBA-2	7-1/1
8	INTERFACE PIN CONNECTION	7B64PS 2708- TX20D17VM2BBA-2	8-1/2~2/2
9	INTERFACE TIMNG	7B64PS 2709- TX20D17VM2BBA-2	9-1/3~3/3
10	DIMENSIONAL OUTLINE	7B63PS 2710- TX20D17VM2BBA-2	10-1/2
10		7B64PS 2710- TX20D17VM2BBA-2	10-2/2
11	DESIGNATION OF LOT MARK	7B64PS 2711- TX20D17VM2BBA-2	11-1/1
12	COSMETIC SPECIFICATION	7B64PS 2712- TX20D17VM2BBA-2	12-1/4~4/4
13	PRECAUTION	7B64PS 2713- TX20D17VM2BBA-2	13-1/5~5/5

\*When product will be discontinued, customer will be informed by HITACHI with twelve months prior to discontinuation.

PROPOSED BY: ACCEPTED BY;

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.

Sh. No.

7B64PS 2701-TX20D17VM2BBA-2 PAGE

# RECORD OF REVISION

	*	•						
DATE	SHEET No.	SUMMARY						
May.13,'08	7B64PS 2708-	8.1 TFT-LCD MODULE(CN1)						
	TX20D17VM2BBA-2							
	PAGE 8-1/2	CN1 JAE : FA5B040HF1R3000(Sn plating)						
		<b>↓</b> :						
		FA5B040HP1R3000(Au plating)						
	7B64PS 2710-	10.2 BACK SIDE						
	TX20D17VM2BBA-2	The lot label size and position is changed.						
	PAGE 10-2/2	Changed:						
		Note 1 CN1 : FA5B040HF1R3000(JAE)						
	·	↓						
		FA5B040HP1R3000(JAE)						
	7B64PS 2711-	11.1 LOT MARK						
	TX20D17VM2BBA-2	Changed: 5 digits for production number						
	PAGE 11-1/1							
		6 digits for production number						
·		o digits for production number						
		11.3 LOCATION OF LOT MARK						
	1							
		Changed: TX200171/2000-						
		100000 may (2013 - 12) 100 may (2013 - 12) 10						
		The state of the s						
		(26)						
	:							
		(14).						
		TX20D77VM28BA REV: 8004T7. (5D). 123456. HTTACHI. MADE.IN-TAIIWAN.						
		THEODIE MACERI CRISSIN , \$						
		Added: 11.4 REVISION(Rev.) CONTROL						
		Rev No. ITEM						
		A CN1 JAE : FA5B040HF1R3000						
		B CN1 JAE : FA5B040HP1R3000						
-								
·								
		•						

DATE May.13,'08 Sh. No.

7B64PS 2702-TX20D17VM2BBA-2 PAGE 2-1/1

KAOHSIUNG HITACHI

ELECTRONICS CO.,LTD.

## 3. GENERAL DATA

The specifications are applied to the following TFT-LCD module with Back-light unit. Note: Inverter device for Back-Light is not built in this module.

Product Name

TX20D17VM2BBA

Effective Display Area

 $(H)174.0 \times (V)104.4$ 

[mm]

Display Dots

 $(H)(800 \times 3) \times (V)480$ 

[dots]

(Display Pixels)

(H 800 x V 480)

[pixels]

Pixel Pitch

 $(H)0.2175 \times (V)0.2175$ 

[mm]

Color Pixel Arrangement

R+G+B Vertical Stripe

Display Mode

Transmissive Mode, Normally White Mode

Surface Polarizing Film

Polarizing Film with Antiglare Coating

Number of Colors

262k

[colors]

Interface

C-MOS,R.G.B x6 bit Digital each

Color Saturation

60%(typ.) for NTSC

Viewing Direction

12 O'clock. (The direction it's hard to be discolored)

Backlight

CCFL, 1pc Side-light type (U shaped)

**Dimensions Outline** 

(H)192(typ.)  $\times$  (V)123.5(typ.)  $\times$  (t)12.7(max.)

[mm]

Weight

Approximately 350

[g]

Touch Panel

Resistance type, The Surface is anti-glare type.

## 4. ABSOLUTE MAXIMUM RATINGS

## 4.1 ENVIROMENTAL ABSOLUTE MAXIMUM RATINGS

Itom	Operating		Non-op	eration	Unit	Note
ltem	Min.	Max.	Min.	Max.	Offic	Note
Temperature	-20	70	-30	85	$^{\circ}\mathbb{C}$	1) 2) 5)
Humidity	2	2)	. 2	2)	%RH_	1)
Vibration	-	4.9(0.5G)	_	19.6(2G)	m/s <sup>2</sup>	3)
Shock	-	29.4(3G)	-	490(50G)	m/s <sup>2</sup>	4)
Corrosive Gas	Not Acc	ceptable	Not Acceptable			
Illumination at LCD Surface	-	50,000		50,000	lx	
CFL	50000h		•		At 25℃	
life time	(Average) (Note6)		-		IL = 4mA max.	

Notes 1) "Temperature" and "Humidity" shall be measured on panel surface.

The ratings apply to every part of this module and shall not be exceeded.

The operating temperature only guarantee the display can be operated; regarding the contrast response time, illumination and other features related to the quality are judged by Ta=25℃ condition.

Generally the illumination will down and LCD response time will becomes slower when the display operated under a lower temperature environment.

2) Ambient temp. Ta≤40°C: 85%RH max. Without condensation.

Ta>40 $^{\circ}$ C :Absolute humidity must be lower than the humidity of 85% at 40 $^{\circ}$ C Without condensation.

- 3) Frequency of the vibration shall be between 20 Hz and 50 Hz. (except resonance point)
- 4) Pulse width of the shock shall be 10 ms.
- 5) In Non-operation condition (Ta>70°C) the TFT-LCD module should be put within 96 hrs. In Non-operation condition (Ta<-20°C) the TFT-LCD module should be put within 240 hrs and without condensation.
- 6) When brightness reached 50% of initial brightness.

## 4.2 ELECTRICAL ABSOLUTE MAXIMUM RATINGS

#### 4.2.1 TFT-LCD MODULE

VSS=0V

ltem	Symbol	Min.	Max.	Unit	Note
Power Supply Voltage for logic	VDD	0	4.0	٧	
Input signal Voltage for logic	VI	-0.3	VDD+0.3	V	1)
Electrostatic Durability	VESD0	±100		V	2),3)
	VESD1	<u>±8</u>		kV	2),4)

- Notes 1) The specification is applied to pixel data signal, timing signal and clock signal.
  - 2) Discharge circuit to be connected: 200pF 250Ω, Environmental: 25°C 70%RH
  - 3) The specification is applied to I/F connector pins.
  - 4) The specification is applied to the surface of both a metal bezel and a LCD panel.

## 4.2.2 BACK-LIGHT UNIT

GND=0V

ltem	Symbol	Min.	Max.	Unit	Note
Lamp Current	IL	-	7.0	mArms	1)
Lamp Voltage	VL	_	2100	Vrms	2)

Notes 1) To be measured at GND terminal side

2) The specification is applied at connector pins for back-light units.

KAOHSIUNG HITACHI	DATE	May 13 '08	Sh.	7B64PS 2704-TX20D17VM2BBA-2 PAGE	1-2/2
ELECTRONICS CO.,LTD.	DAIL	May.13,'08	No.	7BOH O 2704-1720D17 VIVIZBBA-2 1 AGE	7-212

## 5. ELECTRICAL CHARACTERISTICS


### 5.1 TFT-LCD MODULE

Ta=25℃ . VSS=0V

						- ,	
Item		Symbol	Min.	Тур.	Max.	Unit	Note
Power Supply Voltag	е	VDD	3.0	3.3	3.6	V	
Input Voltage for	Hi	VIH	2.0	_	VDD	V	1)
Logic Circuits	Lo	VIL	VSS	-	0.8	V	1)
Power Supply Current		IDD		300	400	mA	2),3)
Vsync Frequency		fV	-	60	75	Hz	
Hsync Frequency		fH	_	31.6	39.2	kHz	
DCLK Frequency		fCLK	-	33.3	40	MHz	

Notes 1) The specification is applied to pixel data signal, timing signal and clock signal.

2) fV=60Hz, fCLK=33.3MHz, VDD=3.3V, DC Current.



Typical value is measured when displaying Black raster.

Maximum is measured when displaying Vertical-stripe pattern of 2 pixel pitch.

3) Current capacity for VDD power source should be larger than 1A. This TFT-LCD Module has a fuse (0.4A).

## 5.2 BACK-LIGHT UNIT

Ta=25°C

Item	Symbol	Min.	Тур.	Max.	Unit	Note
Lamp Current	IL	_	4.0	7.0	mArms	1),3)
Lamp Voltage	VL	_	1000	_	Vrms	
Frequency	fL	50	-	70	kHz	2)
Starting Lamp Voltage	VS	1600	-	-	Vrms	Ta=25℃
		2100	-	-	VIIIIS	Ta= 0°C

Notes 1) Larger IL causes the shorter life of a CCFL.

2) Frequency of power supply for a CCFL may cause interference with Hsync frequency and causes beat or flicker on the display.

Therefore, lamp frequency shall be as different as possible from Hsync frequency in order to avoid the interference.

- 3) To be measured at GND terminal side
- 4) Starting Lamp Voltage should be kept 1 sec at least.
- 5) The inverter should be built-in a safety circuit which detects over current, over voltage and distorted wave form of lamp current.

KAOHSIUNG HITACHI	DATE	May.13,'08	sh.	7B64PS 2705-TX20D17VM2BBA-2 PAGE 5-1/	12
ELECTRONICS CO.,LTD.	DATE	Nay. 13, 06	lo.	7B04F3 2703-1X20D17.VIVI2BBA-2 FAGE 3-17	<u> </u>

## 5.3 ELECTRICAL CHARACTERISTICS OF TOUCH PANEL

## 5.3.1 ELECTRICAL CHARACTERISTICS

ITEM		SPECIFICAYION	NOTE
Resistance	X1-X2	380~1010Ω	At Connector
Between Terminai	Y1-Y2	180~520Ω	At Connector
Insulation Resistance	X-Y	20 M $\Omega$ min.	Operating Voltage : 25V DC
Linearity	X	1.5% max.	- (Note 1,2,3)
Lineanty	Υ	1.5% max.	- (Note 1,2,3)
Chattering		10ms max.	

## 5.3.2 MECHANICAL CHARACTERISTICS

ITEM	SPECIFICATION	NOTE
Pen Input Pressure	5~80gF	R0.8mm polyacetal pen
Surface Hardness	3H	JIS K5400

## 5.3.3 OPTICAL CHARASTERISTICS


ITEM	SPECIFICATION	NOTE
Transparency	80% min.	

Note 1: Operating Volatge 5V DC


Note 2: Test Area of Linearity

Note 3: (1) Marerial of Pen = Poly - Acetalresin

(2) End Shape = R0.8mm (3) Test force = 150gF




Note 4 : Measurement condition of Linearity Linearity Definition



Va : maximum voltage in the active area of touch panel Vb : minimum voltage in the active area of touch panel

X : random measuring point Vxm : Actual voltage of Lx point Vxi : Theoretical voltage of Lx point



Linearity:[|Vxi-Vxm|/(Va-Vb)]\*100%

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD. DATE	May.13,'08 Sh. No.	7B64PS 2705-TX20D17VM2BBA-2	PAGE 5-3/3
--	--------------------	-----------------------------	------------

# 6. OPTICAL CHARCACTERISTICS

The following items are measured on the conditions that this unit operation (TFT-LCD And the Back-light) and measuring systems are stable. It takes about 15 minutes. The ambient light excluding The Back-light unit is nothing.

• Measuring equipment: TOPCON BM-7, Prichard 1980A, or equivalent


Measuring point


: Active area center

 $Ta=25^{\circ}C$  , VDD=3.3V , fV=60Hz , IL=4.0mA

				, , , , ,	<del> </del>	Γ.	<del> </del>	
Item		Symbol	Condition	Min.	Тур.	Max.	Unit	Note
Contrast Ratio		CR		100	200	-		2)
Response Time	RISE	ton		-	20	40	ms	3)
	FALL	toff		-	10	20	ms	3)
Brightness (White)	1	Bwh		360	480	-	cd/m <sup>2</sup>	, , , ,
Brightness Uniforn	nity	Buni		70	-	-	%	4)
Color Position	Red	Х		0.57	0.62	0.67		
On CIE	Reu	у .	<i>θ</i> =0 ° 1)	0.29	0.34	0.39		
	х	.,	0.24	0.29	0.34			
	Green	у		0.55	0.60	0.65		
	Blue	. X		0.09	0.14	0.19	_	
	Diue	y		0.02	0.07	0.12		
	White	х		0.25	0.30	0.35	,	
	vviiite	y		0.26	0.31	0.36		
		$\theta$ x	<i>⊕</i> =0°	50	_	_		
Viewing Angle	x - x'	θx'	<i>∂=</i> 180°	50	-	-	doa	1\
(CR≧10)	د. بر	θу	<i>θ</i> =90°	50	-	_	deg.	1)
	y – y'	∂y'	<i>⊕</i> =270°	50	_	-		


KAOHSIUNG HITACHI		May.13,'08	Sh.	7B64PS 2706-TX20D17VM2BBA-2 PAGE	6 1/2
ELECTRONICS CO.,LTD.	DATE	Nay. 13, 06	10.	7604F3 2700-1X20D17VWI266A-2 FAGE	0-1/2






# 2) Definition of Contrast Ratio(CR):

## 3) Definition of Response Time



## 4) Definition of Birghtness Uniformity




The brightness uniformity (Buni) is defined as the following equation.

where, Bmax = Maximum brightness among 9 measuring points
Bmin = Minimum brightness among 9 measuring points


•	: measuring	g point
	oaoaiiii	g pon

KAOHSIUNG HITACHI	DATE	Sh	7DC4DC 970C TV00D47V440DDA 0	0/0
ELECTRONICS CO.,LTD.	DATE	May 13,'08 No	7B64PS 2706-TX20D17VM2BBA-2	-2/2

# 7. BLOCK DIAGRAM 7.1 TFT-LCD MODULE



## 7.2 BACK-LIGHT UNIT



Color of wires from CCFL to CN2

3 (GND): White 1 (VL): Pink

# 8. INTERFACE PIN CONNECTION

## 8.1 TFT-LCD MODULE

CN1 《JAE; FA5B040HP1R3000(Au plating)》

Pin No.	Symbol	Description	Note
1	VDD	Power Supply (typ.+3.3V)	1)
2	VDD	Trowel Supply (typ.+3.34)	''
3	VDD		
4	VDD	<del>-</del>	
5	NC	Non Connect	4)
		Non-Connect	4)
6	DTMG	Display Timing	2)
7	VSS	GND (0V)	2)
8	NC	Non-Connect	4)
9	VSS	GND (0V)	2)
10	(IC)		3)
11	VSS	GND (0V)	2)
12	B5	4	
13	B4	Blue Data	
14	B3		
15	VSS	GND (0V)	2)
16	B2		
17	B1	Blue Data	
18	B0		
19	VSS	GND (0V)	2)
20	G5		
21	G4	Green Data	
22	G3	T	
23	VSS	GND (0V)	2)
24	G2		
25	G1	Green Data	
	G0		
		GND (0V)	2)
	R5		
29	R4	Red Data	
30	R3		
\$	VSS	GND (0V)	2)
			1
		Red Data	
		·	,
		· · ·	3)
		017 (010	
		GND (0V)	
		Dot Clock	
			2)
		GND (0V)	
26 27 28 29	G0 VSS R5 R4 R3	GND (0V)	2) 2) 3) 2) 2)

Notes 1) All VDD pins shall be connected to +3.3V(Typ.).

- 2) All VSS pins shall be grounded. Metal bezel is internally connected to VSS.
- 3) Keep open electrically. HITACHI test use only.
- 4) Unconnected to the module

## 8.2 BACK-LIGHT UNIT

CN2 《JST; BHR-03VS-1》

Pin No.	Symbol	Description	Note
1	VL	Power Supply	
2	NC	Non-Connect	
3	GND	GND (0V)	

KAOHSIUNG HITACHI	DATE	May.13,'08	Sh.	7B64PS 2708-TX20D17VM2BBA-2 PAGE 8-	1/2
ELECTRONICS CO.,LTD.	DATE	May. 13, 00	No.	7804F3 2700-1X20D17-VW28BA-2 FAGE 0-	)- I/Z

# 8.3 T/P unit

Pin No.	Symbol	Description
1	X2	Analog signal digitizer (Right)
2	Y1	Analog signal digitizer (Up)
3	X1	Analog signal digitizer (Left)
4	Y2	Analog signal digitizer (Down)

# 8.4 RELATIONSHIP BETWEEN DISPLAYED COLOR AND INPUT DATA

	Red Data				Green Data				Blue Data										
	Input	R5	R4	R3	R2	R1	R0	G5	G4	G3	G2	G1	GO	B5	В4	В3	В2	B1	B0
color		MSI	3			L	SB	MS	В			L	.SB	MS	В			L	SB
	Black	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	Red(0)	1	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0
	Green(0)	0	0	0	0	0	0	1	1	1	1	1_	1	0	0	0	0	0	0
Basic	Blue(0)	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1
Color	Cyan	0	0	0	0	0	0_	1	1	1	1	1	1	1	1	1	1	1	1
	Magenta	1	1_	1	1	1	1	0	0_	0	0	0	0	1	1	1	1	1_	1
	Yellow	1	1	1	1	1	1	1	1_	1	1	1_	1	0	0	0	0	0	0
	White	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	Black	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0_	0	0
	Red(62)	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0_	0	0
	Red(61)	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0
Red		:	:	:	:	:	<u>:</u>	:	<u>:</u>	;	:	:	:	<u> </u> :	:_	<u>:</u>	:	:	:
Red	:	:		:	:	:	:_	<u>:</u>	:_	:	:	:	:	:	:	<u>:</u>	:	:	<u>:</u>
	Red(2)	1	1	1	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0
	Red(1)	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0
	Red(0)	1	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0
	Black	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	Green(62)	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	- 0	0
	Green(61)	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0
Croon		:	:	:	:	:		:	:_	<u>:</u>	:	:	:	:	:	<u> </u> :	:	<u>:</u>	:
Green	:		:	:	:	:	:	:	:	:	:	:	:	:	:	<u>:</u>	:	:	:
	Green(2)	0	0	0	0	0	0	1	1	1	1	0	1	0	0	0	0	0	0
	Green(1)	0	0	0	0	0	0	1	1	1	1	1	0	0	0	0	0	0	0
	Green(0)	0	0	0	0	0	0	1	1	1	1	1	1	0	0	0	0	0	0
	Black	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	Blue(62)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
	Blue(61)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0
Blue		:	:	:	<u> </u>	:	:	<u> </u> :	<u>  :</u>	<u> </u> :	:	:	:	<u> </u> :	:	<u> </u> :	:	<u> </u>	<u>:</u>
Diue	:	:		:	] :	:	:	:	:	<u> </u> :	:	:	<u>  :</u>	<u>  :</u>	:	<u> </u> :	:	:	<u>  :</u>
	Blue(2)	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	0	1
	Blue(1)	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	0
<u></u>	Blue(0)	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1

# Notes 1) Definition of gray scale:

Color(n)···Number in parenthesis indicates gray scale level.

Higher n corresponds to darker level.


2) Data: 1: High, 0: Low

KAOHSIUNG HITACHI	DATE	May.13,'08	7B64PS 2708-TX20D17VM2BBA-2 PAGE 8-2/2
ELECTRONICS CO.,LTD.	DATE	No	75041 0 2700 17X205 11 VIVI2557X 2 11 7X02 0 272

# 9. INTERFACE TIMING

# 9.1 TIMING CHART

(Data: Latched at Fall edge of DCLK)



\*The DTMG signal for this module is defined as above-mentioned timings for Vsync and Hsync.

This module synchronizes with only DTMG and don't require inputting Vsync and Hsync signals.


During Blanking priod, DTMG should be "Low" level

KAOHSIUNG HITACHI	DATE	May.13,'08	h.	7B64PS 2709-TX20D17VM2BBA-2 PAGE	0-1/3	
ELECTRONICS CO.,LTD.	DATE	Nay. 13, 00		7B04F3 2709-1A20D17VWZBBA-2 I AGE	0-170	

# 9.2 INTERFACE TIMING SPECIFICATIONS

	Item	Symbol	Min.	Тур.	Max.	Unit	Note
DCLK	Period	tclk	25	30	33		
	Width-Low	twcL	12	-	-		
	Width-Hi	twch	12	-	_	ns	
	Rise time	trclk	-	-	25		,
	Fall time	tfCLK	-	-	25		
	Duty	D	0.45	0.5	0.55	-	D= tclkl/tclk
Hsync	Set up time	tsн	5	-	-	no	for DCLK
	Hold time	tнн	10	-	-	ns	IOI DOLK
	Period	tHP	944	1056	1088	fork	
	Width-Active	twн	4	128	-	tclk	
	Rise/Fall time	tHr,tHf	-	-	30	ns	
Vsync	Set up time	tsv	0	-	_	tclk	for Hsync
	Hold time	thv	2	_	-	tCLK	IOI FISSIIC
	Period	tvp	515	525	610	<b>t</b> HP	
	Width-Active	twv	1	2	_	LHP	
	Rise/Fall time	tvr,tvf	-	-	50	ns	
DTMG	Set up time	tsı	5	-	-	ns	for DCLK
	Hold time	tHI	10	-	-	115	IOI DOLK
	Rise/Fall time	tır,tıf	-	-	30	ns	
	Horizontal Back porch	tнвр	7	216	-	tclk	
	Horizontal Front porch	thep	_	40	-	ICLK	
	Vertical Back porch	tvbp	4	34	-	<b>t</b> HP	
	Vertical Front porch	tvfp		11	<b>100</b>	LHP.	
Data	Set up time	tso	5	-	-	nc	for DCLK
	Hold time	tho	10	-	-	ns	IUI DOLK
	Rise/Fall time	tor,tof	-	-	25	ns	

## 9.3 TIMING BETWEEN INTERFACE SIGNAL AND POWER SUPPLY



#### **POWER ON**

 $t_1 \leq 15 \text{ms}$ 

 $0 \text{ms} < t_2 \leq 45 \text{ms}$ 

 $0.1s \leq t_3$ 

#### POWER OFF

5ms ≤ t₄

 $0ms \le t_5 \le 45ms$ 

 $0 \text{ms} \leq t_6 \leq 20 \text{ms}$ 


 $0.4s \le t_7$ 

## Note 1) Set $0V \le VI(t) \le VDD(t)$ .


Here , VI(t) ,VDD(t) indicate the transitional state of VI ,VDD when power supply is turned ON or OFF.

2) Do not keep interface signal high-impedance when power on.

# 10.OUTLINE DIMENSIONS



# 10.2 BACK SIDE




Note: 1) CN1 FA5B040HP1R3000(JAE)

2) CN2 BHR-03VS-1(JST)

KAOHSIUNG HITACHI	DATE	May 12 109	Sh.	7DC2DC2740 TV20D47W40DD4.0	40.0/0	
ELECTRONICS CO.,LTD:	DATE	May.13,'08	No.	7B63PS2710-TX20D17VM2BBA-2 PAGE	10-2/2	

## 11. DESIGNATION OF LOT MARK

#### 11.1 LOT MARK



#### **Notes**

1)

Year	Mark
2008	8
2009	9
2010	0
2011	1
2012	2

2)

Month	Mark	Month	Mark
1	01	7	07
2	02	8	08
3	03	9	09
4	04	10	10
5	05	11	11
6	06	12	12

3)

Week (Days)	Mark
1~7	1
8~14	2
15~21	3
22~28	4
29~31	. 5

- 4) The special mark may be added by manufacturing accordingly to production number.
- 11.2 REVISION(REV.) CONTROL

REV. column is controlled by the manufacturing. A-Z except I and O is to be written on this column


#### 11.3 LOCATION OF LOT MARK

Lot mark is printed on a label. The label is on rear side of module as shown in the drawing at Section 10.

The style of character may be changed without notice.

11.4 REVISION(Rev.) CONTROL

Rev No.	ITEM
Α	CN1 JAE: FA5B040HF1R3000
В	CN1 JAE: FA5B040HP1R3000



KAOHSIUNG HITACHI		May 42 '00	Sh.	7B64PS 2711-TX20D17VM2BBA-2 PAGE 11-	4/4
ELECTRONICS CO.,LTD.	DATE	Way. 13, 06	No.	7804PS 2711-1X20DT/VM2BBA-2 FAGE 11-	- 1/ 1

## 12. COSMETIC SPECIFICATIONS

#### 12.1 CONDITION FOR COSMETIC INSPECTION

### (1) Viewing zone


a) The figure shows the correspondence between eyes (of inspector) and TFT-LCD module.

 $\theta \leq 45^{\circ}$ : when non-operating inspection

 $\theta \leq 5^{\circ}$ : when operating inspection

b) Inspection should be executed only from front side and only A-zone. Cosmetic of B-zone and C-zone are ignored.

(refer to 12.2 Definition of zone)



## (2) Environmental

a) Temperature : 25°C

The appearance inspection at Back-light on is done at 25°C on a TFT-LCD

b) Ambient light: More than 2000 [lx] and non-directive.

c) Back-light: when non-operating inspection, Back-light should be off.

## (3) Operating inspection


Operating inspection should be done with 8 color mode (without gray scale).

## 12.2 DEFINITION OF ZONE

A-zone: LCD Display area (pixel area)

B-zone: Area between A-zone and C-zone

C-zone: Metallic bezel area (include I/F connector)



# 12.3 COSMETIC SPECIFICATIONS

When displaying conditions are not stable (ex. at turn on or off), the following specifications are not applied.

No	ITEM		Max. acceptable number A-zone	Unit	Note		
	Dot defect		1-dot	4	pcs	1),2),4)	
			2-dots	1		,	
		Sparkle	3-dots	0	Units	1),2),5)	
		mode	4-dots	0			
			Density	2	pcs/ <i>ø</i> 20mm	1),2),6)	
			Total	5	pcs	1),2)	
1			1-dot	5	pcs	1),3),4)	
			2-dots	2			
	·	Black	3-dots	0	Units	1),3),5)	
		mode	4-dots	0			
			Density	3	pcs/ <i>ø</i> 20mm	1),3),6)	
			Total	5	pcs	1),3)	
			Total	10	pcs	1)	
2		Line defect		Serious one is	_	_	
3	Uneven	brightness		not allowed			
	Stains, Foreign Materials Line shape W: width (mm) L: length (mm)	W≦0.02	L : Ignore	Ignore			
		W≦0.03	L≦2.0	10			
4			L>2.0	0	pcs	7)	
		W≦0.06	L≦1.0	10	P	'/	
			L>1.0	0			
		W>0.06		(See dot shape)			
	Stains, Foreign Materials	D≦	0.22	Ignore			
5	Dot shape		0.33	5	pcs	7)	
	D: ave. dia (mm)	· D>	0.33	0			
	Scratch on polarizer	W≦0.01	L : Ignore	Ignore			
	Line shape	W≦0.02	L≦40	10			
6	W : width (mm)	VV <u>≦</u> 0.02	L>40	0	pcs	8)	
	└─L: length (mm) ─	W≦0.04	L≦20	10			
		VV <u>≤</u> 0.04	L>20	0			
	Scratch on polarizer	D≦	≦0.2	Ignore			
7	Dot shape	D≦	≦0.4	10	pcs	8)	
	<u>D</u> : ave. dia (mm)	D>	>0.4	0			

		, , , , , , , , , , , , , , , , , , ,	- ,			
KAOHSIUNG HITACHI		Sh	.			10.011
ELECTRONICS CO.,LTD.	DATE	May.13,'08 No	7B64PS    -	2712-TX20D17VM2BBA-2	PAGE 	12-2/4

No	ITEM		Max. acceptable number A-zone	Unit	Note
	Bubbles, peeling	D≦0.3	Ignore		
	In polarizer	D≦0.5	10		0)
8	D:ave.dia(mm)	D≦1.0	5	pcs	8)
		D>1.0	0		
9	Wrinkles on polarizer		Serious one is not allowed	-	_

Note 1) Dot defect: defect area > 1/2 dot

- 2) Sparkle mode: brightness of dot is more than 30% at black raster. (visible to eye)
- 3) Black mode: brightness of dot is less than 70% at white raster. (visible to eye)
- 4) 1 dot: defect dot is isolated, not attached to other defect dot.
- 5) N dots: N defect dots are consecutive. (N means the number of defects dots)
- 6) Density: number of defect dots inside 20mm  $\phi$ .
- 7) Those stains which can be wiped out easily are not defects.
- 8) Polarizer area inside of B-zone is not applied.

#### 12.4 TOUCH PANEL APPEARANCE

ITEM		CRITERIA		APPLIED				
	Lengh(mm)	Width(mm)	Determine	Zone				
Line Defect	>3	>0.05	None					
	≦3	≦0.05	Ignored					
	≧10	≧0.10	None	Α				
Scratch	<10	0.10>W≧0.05	max 4 points					
	<10	< 0.05	Ignored					
Line defect can i	not across Active a	rea, silver area and	insulation area.	В				
Foreign	Defect	Type.	Determine					
Material	D>0	.3mm	None					
(Note 2)	0.3mm≥[	0>0.2mm	max 3 points	` <b>A</b>				
	0.2mm≧[	D>0.1mm	max 5 points					
,	0.1mi	m≧D	Ignored					
,	D≦0	.5mm	Ignored	В				
	·	·	·					

Note 1) D=(Long  $\phi$  + Short  $\phi$ ) / 2

KAOHSIUNG HITACHI	DATE	May 13 '09	Sḥ.	7B64PS 2712-TX20D17VM2BBA-2 PAGE 12-3/4
ELECTRONICS CO.,LTD.	DATE	Way. 13, 06	No.	7B04F3 2712-1X20D17-VW2BBA-2 EAGE 12-3/4

ITEM	CRITERIA						
Tip Corner	XYX	X					
		Υ	≦3.0mm				
	Z	Z	≦T				
Tip Side	X	X	≦3.0mm				
		Y	≦3.0mm				
	Z	Z	≦T				
Crack		None allowed					

#### 13. PRECAUTION

- 1. Please pay attention to the followings when you use this TFT-LCD Module with Back-light unit.
- 2. Life support applications: HITACHI's products are not authorized for use in life support systems.


#### 13.1 PRECAUTION TO HANDLING AND MOUNTING

- (1) You should consider the mouting structure so that uneven force (ex. twisted stress) is not applied to the module.
- (2) To improve the strength of module against the mechanical shock the space between the module and the case should be less than 1.0mm.
- (3) Protection material in front of LCD's screen surface is recommended to protect a polarizer, LCD-glass and metal bezel. Please be note that the protection material should not touch them direct.
- (4) Acetic acid type and chloline type materials for the cover case are not desiable because the former generate corrosive gas of attacking the polarizer at high temperature and the latter causes circuit break by electro-chemical reaction.
- (5) Do not touch, push or rub the exposed polarizers with glass, tweezers or anything harder than HB pencil lead. And please do not rub by dustclothes with chemical treatment. Do not touch the surface of polarizer with bare hand or greasy close. (Some cosmetics are detrimental to the polarizer.)
- (6) When the surface becomes dusty, please wipe gently with absorbent cotton or other soft materials chamois soaked Normal-Hexane. Normal-Hexane is recommended for clearning the adhesives used to attach front/rear polarizers. Do not use acetone, toluene and alcohol because they cause chemical damage to the polarizer.
- (7) Wipe off saliva or water drops as soon as possible. Their long time contact with polarizer cuses deformations and color fading.
- (8) The module should never be opened or modified. It may cause not to operate properly.
- (9) Metallic bezel of a module should not be handled with bare hand or dirty gloves. Otherwise, color of a metallic frame may become dirty during its storage. It is recommended to use clean soft gloves and clean finger stalls when a module is handled at incoming inspection process and production (assembly) process.
- (10) When you adopt a metallic shield board on backside of TFT-LCD Module, it should not be too close to TFT-LCD Module.
- (11) Do not pull or do not fold the CCFL cable.

KAOHSIUNG HITACHI	D 4 TE	NA 40 200	Sh.		10.4/5
ELECTRONICS CO.,LTD.	DATE	May.13, 08	No.	7B64PS 2713-TX20D17VM2BBA-2 PAGE 1	13-1/5

#### 13.2 Mounting Precaution of T/P

(1) When assembling the Touch Panel and you case, please refer to the figure below.



- (2) The clearance between the Touch Panel and case shall be designed so that the case edge never presses the input screen when it is deformed by heat or other causes.
- (3) The case shall be designed not to touch the tail portion (FPC for Touch Panel).
- (4) The boundary space between the effective area and the insulated area is unstable. Touching this area may effect the operation of the Touch Panel.

  The case must be designed so that it does not touch the boundary space.

#### 13.3 PRECAUTION TO OPERATION

- (1) You should adopt radiation structure to satisfy the temperature specification.
- (2) Optical response time, luminance and chromaticity depend on the temperature of a TFT-LCD module. (At lower temperature it becomes longer.)
- (3) Response time and saturation time of CCFL luminance become longer at lower temperature operation.

KAOHSIUNG HITACHI		May 13 '09 St	1. 7B64PS 2713-TX20D17VM2BBA-2 PAGE 13-2/5	
ELECTRONICS CO.,LTD.	DATE	May.13,'08 No	7864PS 2713-1X20D17VM2BBA-2 EAGE 13-2/3	

- (4) Sudden temperature change may cause dew on and/or in the a module. Dew males damage to a polarizer and/or electrical contacting portion. Dew causes fading of displayed quality.
- (5) Fixed patterns displayed on a module for a long time may cause after-image. It will be recovered soon.
- (6) Please connect the Back-light connector to the inverter circuit directly.

  The long cable between CCFL and the inverter may cause the brightness drop of CCFL and may cause the rise of starting lamp voltage(Vs).
- (7) The module should not be connected or removed while a main system works.
- (8) Inserting or pulling I/F connectors causes any truble when power supply and signal datas are on-state. I/F connectors should be inserted and pulled after power supply and signal datas are turned off.
- (9) Resistance range: Your controller shall be set up to allow the resistance range of Touch Panel specified in our CAS.
- (10) Pointed position of Touch Panel may shift owing to a change in resistance of Touch Panel depending on the operation condition. To compensate this shift, the set shall be given a calibration function.
- (11) Input shall be made with a stylus pen (poly acetal, R0.8). Chances are very high that use of a metal piece including a ball point pen or sharp edge will impair accuracy.
- (12) The Touch Panel is an auxiliary input device. The system shall be designed to have other input device.

## 13.4 ELECTROSTATIC DISCHARGE CONTROL

- (1) Since a module consists of a TFT cell and electronic circuits with CMOS-ICs, which are very weak to electrostatic discharge, persons who are handling a module should be grounded through adequate methods such as a list band.

  I/F connector pins should not be touched directly with bare hands.
- (2) Protection film for a polarizer on a module should be slowly peeled off so that the electrostatic charge can be minimized.

### 13.5 PRECAUTION TO STRONG LIGHT EXPOSURE

A module should not be exposed under strong light. Otherwise, characteristics of a polarizer and color filter in a module may be degraded.

KAOHSIUNG HITACHI	DATE	May.13,'08	Sh.	7B64PS 2713-TX20D17VM2BBA-2 PAGE	12 3/5
ELECTRONICS CO.,LTD.	DATE	Iviay. 13, 00	No.	7804P3 2713-1A20D17VW2BBA-2-1FAGE	13-3/3

#### 13.6 PRECAUTION TO STORAGE

When TFT-LCD Modules are stored for long time, following precautions should be taken care of:

- (1) Modules should be stored in a dark place. It is prohibited to apply sunlight or fluorescent light during storage. Modules should be stored at 0 to 35°C at normal humidity (60%RH or less).
- (2) The surface of polarizers should not come in contact with any other object. It is recommended that modules should be stored in the HITACHI's shipping box.

### 13.7 PRECAUTION TO HANDLE PROTECTIVE FILM

- (1) When the protective film is peeled off, static electricity is generated between the film and the polarizer. This film should be peeled off slowly and carefully by people who are electrically grounded and with well ion-blown equipment or in such a condition, etc.
- (2) The protective film is attached to the polarizer with a small amount of glue. If some stress is applied to rub the protective film against the polarizer during the time you peel off the film, the glue is apt to remain more on the polarizer. So please carefully peel off the protective film without rubbing it against the polarizer.
- (3) When the module with protective film attached is stored for long time, sometimes there remains a very small amount of glue, still on the polarizer after the protective film is peeled off. Please refrain from storing the module at the module at the high temperature and high humidity for glue is apt to remain in these condition.
- (4) The glue may be taken for the modules failure, but you can remove the glue easily. When the glue remains on the polarizer surface or its vestige is recognized, please wipe them off with absorbent cotton waste or other soft material like chamois soaked with Norm-Hexane.

#### 13.8 SAFETY

- (1) If module is broken, be careful to handle not to injure. (TFT-LCD and Lamp are made of glass.) Please wash hands sufficiently when you touch the liquid crystal coming out from broken LCDs.
- (2) As Back-light unit has high voltage circuit internal, do not open the case and do not insert foreign materials in the case.
- (3) The CCFL inverter should be designed to include the function of output shutdown in case the output overcurrent happen due to any backlight trouble. The shutdown function should be assured to work in abnormal condition at the actual systems.
- (4) Wear finger cots or gloves whenever or assembling a TOUCH PANEL its glass edges are shape.

KAOHSIUNG HITACHI	DATE	May 12 200	Sh.	7B64PS 2713-TX20D17VM2BBA-2 PA	ے ا	12 1/5
ELECTRONICS CO.,LTD.	DATE	May.13,'08	No.	7804PS 2713-1X20D17-VM2BBA-2-PA	GE	13-4/5

#### 13.9 ENVIROMENTAL PROTECTION

- (1) This TFT-LCD Module include Cold Cathode Fluorescent Lamp (CCFL). CCFL contains a small amount of mercury. Please follow local ordinance or regulations for disposal.
- (2) Flexible circuits board, printed circuits board and solder used in a module contain small amount of lead (Pb). Please follow local ordinance or regulations for its disposal.

#### 13.10 USE RESTRICTIONS AND LIMITATIONS

- (1) This product is not authorized for use in life support devices or systems, military applications or other applications which pose a significant risk of personal injury.
- (2) In no event shall HITACHI, Ltd., be liable for any incidental, indirect or consequential damages in connection with the installation or use of this product, even if informed of the possibility thereof in advance. These limitations apply to all causes of action in the aggregate, including without limitation breach of contact, breach of warranty, negligence, strict liability, misrepresentation and other torts.

#### **13.11 OTHERS**

(1) Electrical components which may not affect electrical performance are subjective to change without notice because of their availability.

KAOHSIUNG HITACHI	DATE May.13,'08	Sh. 7B64PS 2713-TX20D17VM2BBA-2 PAGE 1	13.5/5
ELECTRONICS CO.,LTD.	DATE May. 13, 00	No. 1004F3 2/13-1720D1/VIVI2BBA-2 FAGE	13-3/3